

# Full-Scale Field Trial of Low-Temperature Mercury Control Process



DE-FC26-06NT42777

# Process Background

- ◆ CONSOL-developed process for controlling mercury emissions from coal-fired power plants.
- ◆ Piloted at AE Mitchell Station in 2003 – 2005.
- ◆ Capable of achieving >90% mercury removal.
- ◆ Relatively simple concept; low capex and opex expected.
- ◆ Best suited for bituminous coal-fired plants that have high levels of unburned carbon.



# Process Background

- ◆ Applicability depends on plant geometry, configuration, other site-specific considerations.
- ◆ Co-removal of sulfur trioxide; potential to improve heat rate.
- ◆ Provisional patent filed July 13, 2006.
- ◆ DOE selected the project, full-scale test at PPL Martins Creek Unit 1 (half flow) award in February 2006.
- ◆ Team:
  - PPL Martins Creek, LLC
  - Lechler, Inc.
  - Martin Marietta Magnesia Specialties
  - CONSOL Energy Inc., Research & Development
  - U.S. Dept. of Energy, NETL




# Potential Market Size

	<u>No. of Units</u>	<u>Capacity, MWe</u>
U.S. coal-fired EGUs >25 MWe	1143	328,052
- Elim. >400 MWe	-319	-206,863
- Elim. status ex. "OP" (EIA)	-44	-2,684
- Elim. FGD and FBC (EIA, ICR, EPA-AR)	-173	-27,903
- Elim. Units in ICR, but not in EIA and EPA-AR	-37	-2,981
- Elim. west of Miss. River	-26	-2,233
- <u>Elim. FGD announced (EV)</u>	<u>-83</u>	<u>-17,665</u>
Candidate units*	316	42,151

\*Additional candidates include steam-only units and small EGUs.




# Conventional Operation




# Mercury Removal with Deep Cooling of Flue Gas via Water and $Mg(OH)_2$ Spray

## Bituminous Coal



# Mercury Removal with Deep Cooling of Flue Gas via Air Heater

## Bituminous Coal



# Martins Creek LTMC Project

- ◆ Unit No. 1, nominal 130 MWe, 2% S coal fired
- ◆ Dual air heaters & dual ESP inlet ducts
- ◆  $\text{Mg}(\text{OH})_2$  and water injections into “A” duct, “B” duct untreated
- ◆ Target 200-240 °F ESP inlet
- ◆ Mercury measurement (CEMS) on each duct
- ◆ Testing to begin May 2007, with a 2-6 Month operation period



# Statement of Project Objectives

- ◆ Determine the performance, operability, and economics of the LTMC process on a full scale utility boiler.
- ◆ Demonstrate that magnesium hydroxide slurry injection into the flue gas with the humidification water can reduce  $\text{SO}_3$  concentration to avoid corrosion at the low-temperature conditions.
- ◆ Demonstrate that water spray humidification can maintain ESP performance under low- $\text{SO}_3$  conditions.




# Work Plan

- ◆ **Phase 1** Preparatory Activities, to prepare for installation and operation of the process
- ◆ **Phase 2** Installation/Construction, to design, procure, construct and install the magnesium-hydroxide and water injection systems
- ◆ **Phase 3** Process Testing, to achieve greater than 90% mercury removal and maintain ESP performance
- ◆ **Phase 4** Post-Test Activities, to analyze process data, report results, and dismantle the equipment




# Elemental Hg Removed As Temperature Is Reduced


## Pilot Plant




# Oxidized Hg Removed As Temperature Is Reduced Pilot Plant



# Total Hg Removed As Temperature Is Reduced Pilot Plant



# Hg Removal Vs "Carbon Treat Rate" Pilot Plant



# Martin's Creek LTMC Project ESP inlet Duct





Dick Winschel, Director Research Services  
4000 Brownsville Rd.  
South Park PA 15129  
412-854-6683

Roy Scandrol, Business Dev. Mgr.  
4000 Brownsville Rd.  
South Park PA 15129  
412-854-6643