


# **Sorbent Based Post-Combustion CO<sub>2</sub> Slipstream Testing**

**Project # DE-FE0012870**



**Dr. Jeannine Elliott  
Dr. Bob Copeland**

**2015 NETL CO<sub>2</sub>  
Capture Technology  
Meeting**

**June 25, 2015**

# Project Objectives

- The objective is to develop a new post-combustion capture technology that captures CO<sub>2</sub> at less than \$40 per tonne (DOE's near term cost target)
- Demonstrate TDA's sorbent technology under realistic conditions at the 0.5 MW<sub>e</sub> (~10 tpd) scale to collect data necessary for scale up to the next level plant
- Major Project Tasks
  - Design, construction, and operation of slipstream test unit to capture CO<sub>2</sub> from flue gas at the National Carbon Capture Center (NCCC)
- Successful project completion will move the technology along the commercialization road map towards slipstream demonstrations and multi MW installations by 2020-2025



National Carbon Capture Center

# Project Overview

## DoE Project DE-FE0012870

### Funding - Total Project \$5,880,378

- DOE: \$4,704,509
- Cost Share: \$1,175,868

### Project Dates

- April 1, 2014 to May 31, 2018

- **Budget Period 1: Optimization & Design**
  - \$1,542,398
- **Budget Period 2: Construction & Installation**
  - \$2,946,991
- **Budget Period 3: Operation**
  - \$1,390,989


---

# Technology Background & Approach


# TDA's Approach

## TDA Research has developed:

- A solid alkalized alumina adsorbent, and
- A CO<sub>2</sub> capture process designed around this process




TDA CO<sub>2</sub> Capture on Supercritical 550 MW plant



- Moving bed had expensive conveyors, although the beds would be smaller
- New multiple fixed bed design
  - Low cost construction
  - Simple bed design
  - Eliminates power lost to moving sorbent
- Lower overall cost than moving bed

# Sorbent-based Post Combustion CO<sub>2</sub> Capture

- **Process advantages:**
  - An inexpensive, durable sorbent
  - Regenerates with low pressure steam
  - Operates at near isothermal conditions, ambient pressure
  - Does not require heat recovery from solids
  - Extremely low heat of adsorption
  - Uses counter-current operation to:
    - Maximize capture efficiency
    - Maximize sorbent loading
- **Patents filed July 2014**
  - Pending U.S. and PCT applications




Heat of adsorption

Heat of adsorption ranges from 3 kcal/mole at higher CO<sub>2</sub> concentrations of 10-14%, to 10.3 kcal/mole at CO<sub>2</sub> concentrations of 1-5%


# Process Design

- Multiple Fixed Bed Contactor
  - Provides counter-flow contact between the solids and gases
- Beds cycle between adsorption and regeneration functions
- Gas flows in series across regeneration beds
- Multiple fixed beds are flexible and can allow demonstration of multiple process design configurations
- Slipstream unit is being designed as multiple fixed bed unit



# Earlier Demonstration Testing at Western Research Institute

- Slipstream project builds on previous DoE funded research
  - Contract #DE-NT0005497
- Demonstrated continuous CO<sub>2</sub> capture in 8 bed bench-scale unit in field testing with coal flue gas at Western Research Institute (Laramie, WY)



Testing of 8 bed apparatus at Western Research Institute



---

# Project Scope

# Project Schedule


---

- **Budget Period 1: Optimization & Design**
  - April 2014 to November 2015
- **Budget Period 2: Construction & Installation**
  - December 2015 to Feb 2017
- **Budget Period 3: Operation**
  - March 2017 to May 2018

# Major Project Tasks

- **Preliminary Techno-Economic Analysis**
  - Based on integration with a nominal 550 MW<sub>e</sub> greenfield supercritical plant, Case 12
- **Pilot Plant Design Optimization and Basis Design**
  - Process experiments to finalize process design
  - Basic process specification and design
- **Pilot Plant Detailed Design and Engineering**
  - Design a 0.5 MW<sub>e</sub> pilot plant to capture 10 tons per day of CO<sub>2</sub>,
  - Hazard Review with NCCC and Initial Environmental, Health and Safety (EH&S) study
- **Scale-up production of the sorbent**
  - QA/QC testing of sorbent at TDA
- **Fabricate slip stream unit and install at NCCC**
- **Demonstrate this process in slipstream testing**
  - Under parametric and steady state conditions
- **Update the Techno-Economic Analysis and finalize the EH&S assessment**

# Project Schedule



LEGEND: Plan Scheduled Milestone   
 Revised Plan Decision Point

---

# Budget Period 1


# Progress to Date

---

- **Project kick-off meeting held at DoE on May 2014**
- **Several improved process designs developed**
  - New bench-scale unit constructed for optimization testing which mimics slipstream unit
  - Several generations of changes have been made as part of optimization
  - Reconstruction of bench-scale apparatus for optimization experiments delayed project schedule.
- **Engineering and design of 0.5 MW slip stream unit started**
  - Design presented to NCCC for discussion on requirements and logistics
  - Multiple fixed beds design reactor design and layout developed
  - PFD and P&IDs prepared
- **Preliminary Hazard Review with NCCC completed May 2015**
- **EH&S report to be completed June 2015**

# Process Design Optimization

- Multiple Fixed Bed Contactor
  - Provides counter-flow contact between the solids and gases
- Beds cycle between adsorption and regeneration functions
- Gas flows in parallel through adsorption beds and in series across regeneration beds



# Features & Benefits of 12 Bed Design

- Previous TDA bench-scale apparatus had 8 beds and limited ability to simulate recycle options
- New 12 bed apparatus is redesigned for improved performance and better simulation of slip stream unit & commercial system


Feature	Advantage	Benefit
12 beds (vs. 8 beds)	Additional regeneration stages	<ul style="list-style-type: none"><li>• Additional stripping for same steam usage</li><li>• Trade-off of adding more beds to be assessed</li></ul>
Steam saver recycle with controlled flow and timing	Steam in wet flue effluent recycled back to regeneration side to rehydrate bed can be optimized in controlled manner	<ul style="list-style-type: none"><li>• Steam usage decreased</li><li>• Steam saver can now be tuned for maximize benefit</li></ul>
Adsorption Breakthrough recycle	Effluent flue in last adsorption bed recycle back to feed to keep capture up	<ul style="list-style-type: none"><li>• This recycle option was not available in previous bench-scale apparatus</li></ul>

- TDA is collecting data to evaluate optimized process conditions and performance of recycles/purge steps



# Slipstream Unit at NCCC

- 0.5 MW<sub>e</sub> Skid mounted system
- Adsorber/Regeneration Contractor is a multiple fixed bed unit
- Sorbent is regenerated by steam
- Adsorber/Regenerator operates near isothermal (adiabatically) at 120 to 140°C with about 17 psia steam
- Operation pressure is near atmospheric pressure





**System to be located at NCCC  
Pilot Bay #3 47" x30"**


# Pilot-scale Unit Design

- Engineering design of 0.5 MW of skid mounted slip stream unit with multiple fixed beds (5000 lb/hr flue gas)
- Pilot System includes 4 units
  - Adsorber/Regeneration Contractor
    - 12 Beds switch between adsorption, regeneration, purge operations
  - Support unit (heat exchanger, blower, flow metering, exhaust cooler)
    - Blowers to increase pressure of flue which is provided to the unit from NCCC with virtually no pressure head
    - Steam and resistive heat exchangers to heat flue gas up to the operating temperature and control (fine tune) the regeneration steam temperature
    - Flow metering to measure flue gas and steam flow rates
    - Cooling water heat exchangers to cool exhaust gases to less than 60°C to make it compatible with NCCC exhaust vent system.
  - Instrument/control unit
    - Gas analyzers and control system units
- Engineering issues being addressed related to bed design, flow distribution, valves & manifolding to minimize pressure drop, transportation/weight of units
- SolidWorks models complete on contactor unit

# Slipstream Unit Reactor Design




- Beds are cylindrical reactors with carbon steel flanges.
- Top flange is removable to fill sorbent.
- A main 3 way ball valve is the central piece of each valve assembly with a number of 2 way ball valves for each gas stream.
- All valves are pneumatically actuated.



**Manifolding & valves to control multiple operation on each bed**



# Slipstream Unit Bed Design

Flow distribution simulation through reactors




- A 4.5" high plenum above and below the sorbent bed for flow distribution.
- A grated plate/screen is secured at the bottom of the plenum to keep the sorbent in place.
- CFD modeling with the Solids Works flow simulation program on adsorption and regeneration flow distribution.

# Slipstream Unit Bed Design



- SolidWorks models of the reactors and piping developed
- Sorbents beds are arranged in two rows on two skid mounted units
- 12 beds in internally insulated box, entire trailer at operating temperature, removable panels for maintenance/repair



---

# Budget Periods 2 & 3

# Budget Period 2

## BP 2 Tasks      December 2015 to February 2017

- Scale-up production of the sorbent
- QA/QC testing of sorbent at TDA
- Fabricate the sorbent bed vessels for the pilot plant and other modules
- Finalize Test Plan
  - Operating conditions and key parameter parametric conditions selected
  - Operator training
- Integrate the unit at the NCCC



# Budget Period 3 Tasks

## Budget Period 3 March 2017 to May 2018

- Demonstrate this process in slipstream testing at the NCCC under both parametric and steady state conditions using coal derived flue gas.
- Update the Techno-Economic Analysis and finalize the EH&S assessment
- Data from the pilot plant test will be used to develop recommendations for the next level of scale up





# Summary

---

- Process design optimization is focused on the flow pattern of the gases (which is controlled by the programming of the system) through the multiple fixed bed system
- We have moved forward with hardware design even as we continue to push of the optimization of the system
- Initial process flow diagrams and P&IDs of the slipstream system have been prepared
- We have completed initial Process Hazard Analysis with NCCC
- We have nearly completed preliminary Environmental, Health and Safety (EH&S) review
- We will complete final process optimization and economic analysis
- By end of Budget Period 1 we will complete engineering design, HAZOP review and submit design package to DoE

# TDA Research Inc.

Privately Owned/Began operations in 1987

80 Full-time technical staff

Located just west of Denver, CO

**Wheat Ridge Facility**



**Golden Facility**



# Acknowledgements

---

- Project funding provided under DoE Contract # DE-FE0012870
- Andy O’Palko
- Lynn Brickett