APPENDIX B: CARBON DIOXIDE CAPTURE TECHNOLOGY SHEETS PRE-COMBUSTION SOLVENTS

CO₂ CAPTURE FROM IGCC GAS STREAMS USING AC-ABC PROCESS

Primary Project Goals

SRI International is developing, for integrated gasification combined cycle (IGCC)-based power plants, a carbon dioxide (CO₂) capture technology based on the use of a high-capacity and low-cost aqueous ammoniated solution containing ammonium carbonate (AC), which reacts with CO₂ to form ammonium bicarbonate (ABC).

Technical Goals

- Test the technology on a bench-scale batch reactor to validate the concept.
- Determine the optimum operating conditions for a small pilot-scale reactor.
- Design and build a small pilot-scale reactor capable of continuous integrated operation.
- Perform pilot-scale tests to evaluate the process in a coal gasifier environment.
- Perform a technical and economic evaluation on the technology.

Technical Content

The technology is based on the use of an aqueous ammoniated solution containing AC, which reacts with CO₂ to form ABC.




Figure 1: Acid Gas Removal in Gasification System

The concentrated ammoniated solution is used to capture CO₂ and hydrogen sulfide (H₂S) from synthesis gas (syngas) at high pressure. This technique reduces the size of the CO₂ stripper and operates at high pressure, reducing CO₂ compression needs. Both reduce electric power consump-

Technology Maturity:

Pilot-scale using actual syngas

Project Focus:

Ammonium Carbonate

Participant:

SRI International

Project Number:

FE0000896

NETL Project Manager:

Meghan Napoli

Meghan.Napoli@netl.doe.gov

Principal Investigator:

Gopala Krishnan SRI International Gopala.Krishnan@sri.com

Partners:

Great Point Energy

Performance Period:

9/30/09 - 3/31/12

tion. AC has high net CO_2 loading, is a low-cost and readily available reagent, and requires little solvent makeup; the solubility of hydrogen (H_2) , carbon monoxide (CO), and methane (CH_4) in absorber solution is extremely low.




Figure 2: Schematic of the CO₂ and H₂S Capture System

The project, in its first phase, has constructed a bench-scale batch reactor unit to test the technology at SRI's facility in California. Testing is being done to validate the concept and to determine the optimum operating conditions.

Absorber testing is being done to first determine the solubility of shifted-gas components $[H_2, CO, \text{nitrogen } (N_2), \text{argon } (Ar)]$, then determine the reactivity of CO_2 , H_2S , and carbonyl sulfide (COS); mixed-gas testing will determine the relative reaction kinetics.

Regenerator testing is being done to determine CO_2 and H_2S release characteristics, as well as the relative kinetics of CO_2 and H_2S release. Optimal operating conditions derived in bench-scale testing will be carried over into a pilot-scale test.

Pilot-scale testing will be performed on a slip stream of Great Point Energy's 1 ton/day pilot gasifier located at Brayton Point, MA. SRI will design and construct a pilot-scale continuous, integrated test system. The pilot-scale test will emphasize stability of integrated operation. The tests will be of longer duration, about six to eight times longer total test time than with the simulated tests at SRI. The effects of trace contaminants will be observed, as the pilot tests will use a gas stream from an operating gasifier that has undergone minimum cleanup and will contain trace contaminants.




Figure 3: Pilot-Scale Integrated Testing (Preliminary)

A technical and economic analysis is underway using Aspen modeling to generate the equipment sizing and heat and material flows; DOE cost models; and a base case, 750-MW nominal IGCC plant without CO_2 capture to compare the AC-ABC process with a similar-size plant using CO_2 capture with a Selexol subsystem.

Table 1: Solvent Parameters

	Parameter	Current R&D Value	Target R&D Value
Solvent Properties	Type of solvent	Aqueous ammoniated solution	Aqueous ammoniated solution
	Molecular weight	Nominal 18	Nominal 18
	Boiling point (°C)	Varies with pressure; 100°C at 1 atm	Varies with pressure; 100°C at 1 atm
	Heat of reaction (kJ/mole CO ₂)	40–60 depending on the NH ₃ /CO ₂ ratio	40–60
	CO ₂ loading/working capacity ¹ , wt%	10	20
	Solvent concentration to stripper (mol/liter)	6 M NH₃	8 M NH ₃
	Heat capacity of solution (kJ/K/kg)	3.5	3.5
	Viscosity, cP	1	1
Operating Conditions	Absorption temperature, °C	25	25–40
	Absorption pressure, atm	20	50
	CO ₂ capture efficiency, %	>90	>90
	Regeneration method	Heating with steam	Heating with steam
	Regeneration temperature, °C	N/A	150
	Regeneration pressure, atm	N/A	50
Heat Integration	Required regeneration steam temperature, °C	120	170
Miscellaneous	Solvent make-up rate, kg/kg CO ₂	N/A	N/A
Product Quality	CO ₂ purity, %	>98	98.1
	N ₂ concentration, %	N/A	1.9
	Other contaminants, %	N/A	0.01
Process Performance	Electricity requirement, kJ/kg CO ₂	N/A	17.7
	Heat requirement, kJ/kg CO ₂	N/A	620.6
	Total energy (electricity equivalent), kJ/kg CO ₂	N/A	638.3

Note:

Equations Describing Chemical Reaction:

 $NH_4OH + CO_2 = NH_4HCO_3$

 $(NH_4)_2CO_3 + CO_2 + H_2O = 2NH_4HCO_3$

 $NH_4(NH_2CO_2) + CO_2 + 2H_2O = 2NH_4HCO_3$

 $NH_4HCO_3 = NH_4HCO_3$ (precipitate)

Solvent Reaction Kinetics: The absorption of CO_2 by the ammoniated solution is proportional (1st order) to the CO_2 partial pressure. Preliminary experiments confirm this behavior. The kinetics of CO_2 absorption is expected to be rapid at the elevated pressures and high CO_2 concentrations expected in the IGCC gas stream downstream of the water gas shift (WGS) reactors.

Solvent Heating/Cooling Method: During regeneration, the liquid is heated by steam using a reboiler. In the absorber, the liquid is cooled using a heat exchanger and a coolant from a direct contact cooler.

Solvent Contaminant Resistance: The solvent is expected to be resistant to several contaminants nominally present in an IGCC gas stream. Hydrogen sulfide reacts with the solvent, but it can be removed during the regeneration. The ammonia (NH₃) in the IGCC may negate any NH₃ loss from the solvent. The resistance of the solvent to trace metals is not known yet.

Flue Gas Pretreatment Requirements: The IGCC gas stream needs to undergo WGS reaction to convert CO to CO₂ and to be cooled to a temperature of 25 °C to 50 °C.

^{1.} Working capacity is the loading difference CO₂-rich solution before and after it is regenerated.

Waste Streams Generated: Ammonium sulfate solution from the capture of trace residual NH₃ in the gas.

Technology Advantages

- Low-cost and stable reactive solution.
- Reactive solution has a high CO₂ loading capacity due, in part, to the formation of ABC solids during absorption.
- Optimum operating pressure, including CO₂ output stream, is expected to be between 200 and 700 pounds per square inch (psi), resulting in lower compression costs than conventional technologies.

R&D Challenges

- Precipitation of solids could potentially foul packing and heat exchanger surfaces.
- Absorber operation at an elevated temperature could create excessive residual ammonia in the fuel gas stream leaving the absorber.
- Adequate separation of H₂S and CO₂ in the regenerator gas.

Results To Date/Accomplishments

- Bench-scale mixed gas batch tests, in various gas compositions, were conducted. Carbon dioxide and H₂S capture rates were experimentally determined as a function of temperature, pressure, and solution and gas compositions. Data from regenerator experiments were used to determine the optimum regenerator conditions for the release of CO₂ and H₂S exclusively.
- Bench-scale simple gas mixture batch test runs were conducted. It was observed that:
 - CO₂ and H₂S are absorbed in the system at pressures between 200 and 300 psi and temperatures between 20 and 60 °C.
 - The absorption of CO₂ in the ammoniated solution was found to be efficient, capable of capturing >95% of the feed CO₂ at a temperature above ambient.
 - Absorption tests with H₂S also showed that the ammoniated solutions were highly effective in absorbing H₂S and efficiencies as high as 95% were achieved.
 - The ratio of CO_2/NH_3 (R' value) in solution has a major influence on the rate of both H_2S and CO_2 absorption; the rate increased with decreasing value of the parameter.
 - The total pressure had a positive effect on the rate, as expected. The NH₃ concentration of the solution had only a minor effect, indicating that high CO₂ loading of the solution can be achieved without a significant effect on the absorption efficiency.
- Bench-scale regenerator tests were conducted with 10–20 wt% CO₂ loaded ammoniated solutions. Regeneration tests showed that:
 - CO₂ can be released from the solution under conditions of 450 psi and 125 °C.
 - The regeneration tests showed that ammoniated solutions suitable for absorption with high NH₃/CO₂ ratios can be generated at moderate temperatures and at elevated pressures.

In summary, the bench-scale tests demonstrated an efficient absorption of CO₂ and H₂S at elevated pressures without the need for sub-ambient operation. High-pressure CO₂ and concentrated H₂S streams can be released during the regeneration of loaded solution.

• Preliminary economic analysis using simulations was performed and indicates that the AB-ABC capture process requires less parasitic electric power consumption and has a lower capital cost than the Selexol process. The cost of CO₂ capture by the AC-ABC process was estimated for a 750-MWe IGCC plant.

Next Steps

- Perform preliminary process modeling.
- Prepare for pilot scale.

Available Reports/Technical Papers/Presentations

 $CO_2 \ Capture \ from \ IGCC \ Gas \ Streams \ Using \ AC-ABC \ Process; \ Presentation \ at the \ 2010 \ NETL \ CO_2 \ Capture \ Technology \ Meeting, \\ Pittsburgh, PA, September \ 13-17, \ 2010. \ \underline{http://www.netl.doe.gov/publications/proceedings/10/co2capture/presentations/thursday/Gopala \ Krishnan - FE0000896.pdf$

 ${
m CO_2}$ Capture from IGCC Gas Streams Using the AC-ABC Process; Presentation at the Pre-Combustion ${
m CO_2}$ Capture Kick-off Meetings, Pittsburgh, PA, November 12–13, 2009; Available at the NETL website.