



U.S. Department of Energy
National Carbon Capture Center



at the Power Systems Development Facility

Post-Combustion Carbon Capture





Post-combustion

- Build test infrastructure at Plant Gaston
- Partner with solvent and process developers for evaluation
- Move technology forward to demonstration phase


Pre-combustion

- Utilize and expand existing syngas infrastructure
- Provide test site for syngas CO₂ capture technology evaluation
- Use data in engineering of full-scale systems

Oxy-combustion

- Scoping / screening studies of new pressurized oxy-combustion process.

Goals of the NCCC




- Offer a unique flexible testing facility where processes can be tested on coal derived gas at various scales
- Serve as a technology development facilitator by providing facilities for technology scale-up
- Solicit and incorporate activities and projects from a wide variety of participants and partners. Find “Best-in-class” Technology.
- Deliver innovation through a cross-cutting, collaborative project that provides an accelerated pathway to cost-effective CO₂ capture technology for coal fueled power production



Post-combustion




Pre-combustion






Oxy-combustion

National Carbon Capture Center at the Power Systems Development Facility




PC4 Test Units






PSTU Flow Diagram




PSTU Baseline Test



- Purpose
 - Hydraulic check
 - Packing clean-out
 - Ambient heat loss estimate
 - Validate analytical methods
 - Instrument calibration
 - Controller tuning
 - Design validation
 - HMB closure




Range of Parameters Tested




- Total 27 test cases
- 3 to 8 hour mass balance time periods for most cases
- CO₂ removal rate 62 - 97%
- MEA concentration 18 – 39wt% (20%, 30%, 40% nominal)
- Flue gas flow rate 3,100 – 5,000 lb/hr
- Liquid flow rate 12,500 – 27,500 lb/hr
- L/G ratio (liquid/gas) 2.8 – 5.5 lb/lb
- Steam flow rate 680 – 2,460 lb/hr
- S/L ratio (steam/liquid) 0.04 – 0.12 lb/lb
- Lean CO₂ loading (Absorber inlet) 0.12 – 0.34 mol/mol
- Rich CO₂ loading (Absorber outlet) 0.37 – 0.55 mol/mol
- **CO₂ mass balance closure 92 – 105%**
- Flue gas composition at Absorber inlet (vol%, wet):
 - H₂O = 6.3 – 7.3
 - O₂ = 4.6 – 7.1
 - CO₂ = 11.4 – 12.9
 - SO₂ < 1 ppmv
 - No CO₂ removed by caustic in Pre-Scrubber

Baseline Test - Reboiler Energy



Baseline Test – MEA Losses



- **Preliminary** results: analytical procedures still in development.
- Short duration of test did not warrant reclaimer operation
- MEA losses in the gas phase measured < 10 ppm
- One nitrosamine compound (nitrosomorpholine) detected at parts-per-trillion level.
- Other compounds detected at parts-per-billion level:
 - Formaldehyde, Acetaldehyde, Butylaldehyde, Ethylamine, and Dimethylamine.
- All compounds detected well below OSHA Permissible Exposure Limits.
- This type of sampling needs to be done with other solvents and other operating conditions to better understand causes and potential methods of emission control.

Baseline Test - Lessons Learned




Operations

- System cleanup – solvent filtration
 - Three days to clean-up particulate from piping
- Water balance
 - Requires close monitoring, controls installed to automate water transfers
- Power plant interaction
 - Utility supplies, boiler operations
- SO₂ removal in pre-scrubber below 1 ppm with negligible CO₂ removal
- Regenerator condenser overhead controls a challenge
 - May modify condenser level control
- MEA losses from wash tower



Baseline Test - Lessons Learned




Equipment

- Gas flow transmitters
 - Impulse line modification
- Differential pressure measurement on packing bed
- Storage of equipment before run
 - Solenoid valves had to be overhauled
- Pump seal design
 - Threaded connections prone to leak
 - Filtration too close to system filtration
- Plate frame design
 - No low point drain
- Liquid distribution in absorber
 - Suspicious temperature profile
- Insulation and heat tracing capability
 - Stable temperatures ~110 F during shutdowns




PSTU Outage Work




- Modifications for B&W Solvent
 - Instrumentation and piping changes
- Plate/Frame heat exchanger drain
- Absorber and regenerator packing change-out
 - From 304SS to 316SS per original spec
- Electrical upgrades
- MTR connections
- Second instrument air compressor
- FTIR probe upgrades
- Instrument improvements




Aker Mobile Test Unit



- Solvent-based mobile test unit in 2nd bay
- Previously tested at power plant in Scotland
- 0.25 MWe capacity
- At PC4, first 24-hour operation
- Testing underway




MTR Membrane Technology



- Membrane Technology & Research (MTR) CO₂ membrane skid
- 50 kW/1 tpd CO₂ Capacity
- Previous testing at 3 sites
- Provides data for larger scale test unit



PC4 Test Plan



2011 Testing

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
PSTU	Commissioning		Baseline Test						B&W Solvent			
2 nd Bay					Aker MTU							
Bench 1									MTR Membrane			
Bench 2									Codexis*			
Bench 3												
Bench 4												
BOP						2 nd Air compressor and Electrical Upgrades						

**Negotiating Codexis Contract*

Potential Technology Developers for 2012 and 2013



Solvent Developers



3H

Process Development



Advanced Membranes



Enzymes



