

# BENCH-SCALE PROCESS FOR LOW-COST CARBON DIOXIDE (CO<sub>2</sub>) CAPTURE USING A PHASE-CHANGING ABSORBENT

DE-FE0013687

GE Global Research

Tiffany Westendorf


Budget Period 1 Briefing  
February 23, 2015



# Agenda

- Technical Background
- Project Structure
- Progress Report by Task
- Budget Period 1 Status
- Plans for Budget Period 2
- Q&A





# Chemistry of GAP-0 reaction with CO<sub>2</sub>




- Extensive screening of multiple solvents
- Absorbs CO<sub>2</sub> very rapidly in the 40-50°C range
- High CO<sub>2</sub> loading (>17% weight gain, >95% of theoretical value)
- Carbamate readily decarboxylates at higher temps
- **Carbamate is solid → new process configuration**

# GAP-0 Properties

- Lower vapor pressure vs. MEA
- Higher heat of reaction vs. MEA
- Lower heat capacity vs. MEA
- >11% Dynamic CO<sub>2</sub> capacity @ 6 bara



# Phase-Changing CO<sub>2</sub> Capture System



- 1 Make the solid (Spray absorption)
- 2 Move the solid (Pressurized solids transport)
- 3 Regenerate the solvent (CO<sub>2</sub> desorption and solvent recycle)

# Risk Assessment

## Absorber

- Heat management
- GAP-0  $\beta$ -isomer
- Atomizer fouling
- Presence of water, heat stable salts

## Extruder


- Heat management
- Dynamic seal stability

## Project

- Solvent availability, cost
- Expertise resources

## Desorber

- Heat management
- Corrosion



# BENCH-SCALE PROCESS FOR CO<sub>2</sub> CAPTURE USING A PHASE-CHANGING ABSORBENT

## Program Team



**GE Global Research  
Niskayuna**

- Bench-Scale Design
- Construction/operation of Continuous System
- EH & S Assessment
- Techno-Economic Assessment

**coperion**  
confidence through partnership

- Extruder Design
- Component Integration
- Heat Management

**Gelest**  
Building New Technology

**SILAR  
LABORATORIES**  
Advanced Process Development


**SiVance**  
Quantities... for Precise Performance

## Solvent Manufacturers

- Aminosilicone Supply

## 36 Month, \$3.0MM Program to Develop a Phase-Change Process for CO<sub>2</sub> Capture

**Program Objective:** Design and optimize a new process for a novel silicone CO<sub>2</sub> capture solvent and establish scalability and potential for commercialization of post-combustion capture of CO<sub>2</sub> from coal-fired power plants. A primary outcome will be a system capable of 90% capture efficiency with less than \$40/tonne CO<sub>2</sub> capture cost.



## Technical Approach

- Design and construct bench-scale unit and obtain parametric data to determine key scale-up parameters
- Perform an EH & S and technical and economic assessment to determine feasibility of commercial scale operation
- Develop scale-up strategy

**\$2.4M DOE share**  
**1/1/2014 – 12/31/2016**

## Program Deliverables

- Strategy for future scale-up
- Technical and economic feasibility determined
- Environmental assessment

## Anticipated Benefits of the Proposed Technology

- 90% CO<sub>2</sub> capture
- \$40/tonne CO<sub>2</sub> capture cost




# Project Structure


- Budget Period 1: Design and Build [2014]
  - Spray absorber, extruder, desorber
  - Preliminary Technical and Economic Assessment
  - Go/No-go: 90% CO<sub>2</sub> Capture, <\$50/tonne CO<sub>2</sub>
- Budget Period 2: Unit Operations Testing [2015]
  - Optimize individual unit operations separately
  - Solvent manufacturability study and EH&S risk assessment
  - Update Technical and Economic Assessment
  - Go/No-go: 90% CO<sub>2</sub> Capture, <\$45/tonne CO<sub>2</sub>
- Budget Period 3: Continuous System Operation [2016]
  - Integrate unit ops into continuous system, generate engineering data for scaleup
  - Final Technical and Economic Assessment
  - Goal: 90% CO<sub>2</sub> Capture, <\$40/tonne CO<sub>2</sub>



# Project Schedule: BP1



# Task 2: Preliminary Process and Cost Modeling



- Model reflects Case 12 of Bituminous Baseline Study, scaled to 550MW net power output
- Incorporated custom property basis for GAP-0
- CO<sub>2</sub> capture system integrated with power plant
- High efficiency driven by high dynamic CO<sub>2</sub> loading, heat integration

Phase-changing aminosilicone process  
offers substantially higher efficiency, lower  
cost vs. MEA

# Task 3: Design and Build – Absorber

## Features


- efficient spray formation
  - Choice of atomizers
- disengagement of particles from gas
  - Co-current, downward spray flow
  - Cyclone solids collection
- wide range of liquid and gas flow rates
  - up to 200mL/min solvent flow rate
  - up to 500slm gas flow rate
- wide range of gas composition
  - 0-100% CO<sub>2</sub> in N<sub>2</sub>
  - SO<sub>2</sub>, NO capability
  - Humidity

	Hydraulic Nozzle	Two-Fluid Nozzle	Rotary Atomizer
Atomization mode	Liquid pressure, internal geometry	Gas pressure	Spinning disk
Cost at bench scale	+	+	-
Droplet size	-	+	+
Droplet size during startup	-	+	+
Atomization independent of CO <sub>2</sub> :GAP-0 feed ratio	+	-	+
Compatible with bench-scale liquid flowrate	+	+	+

# Task 3: Design and Build – Absorber



*Gas supply system*





*Spray absorber and liquid supply system*



# Task 3: Design and Build – Extruder


## Features

- feed 5-30 lb/hr solids
  - 25mm screw diameter
  - K-Tron loss-in-weight feeder
- maintain dynamic seal against pressure
  - Modular screw elements → optimized screw
  - Optimized barrel heating profile
- connection to desorber
  - custom dieplate
  - melt temperature
  - pressure relief
  - desorber bypass for startup





# Task 3: Design and Build – Extruder





*K-Tron solids feeder and 25mm extruder, connected to desorber inlet*

# Task 3: Design and Build – Desorber


## Features

- 2-stage continuous stirred tank reactors
  - Desorber: elevated pressure – produce pressurized CO<sub>2</sub>
  - Polisher: near-atmospheric pressure – complete solvent regeneration
- Range of residence times
  - 3.7L – 5L vessels
  - Liquid Level Control
- Controlled heating, pressure
  - Temperatures up to 180°C
  - Pressures up to 10 bar
  - Cool lean liquid before return to storage
- Measure liquid composition with inline IR probe







# Task 3: Design and Build – Desorber



*Pressurized and atmospheric pressure desorbers*

# Task 3: Design and Build – Desorber




- Measured viscosity of homogenous GAP-0 / GAP-0 carbamate mixtures
- Newtonian flow characteristics (shear-independent)
- Important data for rigorous modeling and pump selection at scale

# Task 3: Design and Build – Integrated System

## Features

- Controls and instrumentation
  - Gas flow controllers and meters
  - Liquid flow controllers and meters
  - Gas composition by Mass Spec, Humidity sensors
  - Liquid composition by IR
  - Temperature controllers and indicators
  - Pressure controllers and gauges
- Data logging
- Engineering controls (pressure relief, toxic gases)
- Unit ops integration
  - Absorber → Extruder solids transfer design in progress
  - Extruder → Desorber installation complete
  - Solvent return from Polisher → Lean Storage design complete



# Task 3: Design and Build – Experiment Plan

	Absorber	Extruder	Desorber
Vary	<ul style="list-style-type: none"> <li>• Gas inlet composition</li> <li>• Gas flow rate</li> <li>• Liquid flow rate</li> <li>• Gas inlet T</li> <li>• CO<sub>2</sub> : GAP-0 mole ratio</li> <li>• Atomizer type &amp; settings</li> </ul>	<ul style="list-style-type: none"> <li>• Solids flow rate</li> <li>• Screw RPM</li> <li>• Screw design</li> <li>• Barrel T profile</li> <li>• Outlet pressure</li> </ul>	<ul style="list-style-type: none"> <li>• Feed rate</li> <li>• Temperature</li> <li>• Pressure</li> <li>• Agitation rate</li> <li>• Residence time</li> </ul>
Measure	<ul style="list-style-type: none"> <li>• % CO<sub>2</sub> capture</li> <li>• % GAP-0 conversion</li> <li>• Gas outlet T</li> <li>• Solids yield</li> </ul>	<ul style="list-style-type: none"> <li>• Maximum delivery pressure</li> </ul>	<ul style="list-style-type: none"> <li>• % GAP-0 conversion</li> <li>• CO<sub>2</sub> flow rate</li> </ul>
Optimize	High % GAP-0 conversion (high quality solids)	High delivery pressure (stable solids seal)	<ul style="list-style-type: none"> <li>• High CO<sub>2</sub> desorbed at pressure</li> <li>• Complete solvent regeneration for recycle</li> </ul>

# BP1 Milestones and Success Criteria


Budget Period	Task	Milestone Title/Description	Planned Completion Date	Actual Completion Date	Verification Method	Comments
1	1	Updated Project Management Plan	1/31/2014	1/31/2014	Project Management Plan file	
1	1	Kickoff Meeting	12/31/2013	11/20/2013	Presentation file	
1	2.1-2.2	Preliminary process and cost modeling complete	3/31/2015		Preliminary Process and Cost Modeling Report	on track to meet planned completion date
1	3.1	Absorber Built and Operational	12/31/2014	12/31/2014	Research Performance Progress Report file	
1	3.2	Extruder Built and Operational	3/31/2015		Research Performance Progress Report file	on track to meet planned completion date
1	3.3	Desorber Built and Operational	12/31/2014	12/31/2014	Research Performance Progress Report file	
1	3.4	Integrated system design complete	3/31/2015		Bench-Scale System Design Topical report	on track to meet planned completion date

## BP1 Success Criteria

- ✓ Unit operations are built and operational
- ✓ 90% CO<sub>2</sub> Capture, <\$50/tonne CO<sub>2</sub>



# BP1 Budget Status



	BP1 (k\$)
Budget	\$1277
Total through Week 59	\$1155
% of BP1 schedule	92%
% of BP1 cost	90%

On track to meet BP1 plan

# BP2 Project Schedule and Budget

	Budget Period 2			
	Q2 / 15	Q3 / 15	Q4 / 15	Q1 / 16
<b>Task 4 Perform bench-scale testing on unit ops</b>				
4.1 Procure solvent				
4.2 Determine operating parameters for unit ops				
4.3 Determine scale-up effects				
4.4 Determine suitable materials of construction				
4.5 Assemble components into continuous system				
<b>Milestones:</b>				
- Absorber parameters established				
- Extruder parameters established				
- Desorber parameters established				
- Continuous system assembled				
<b>Task 5 Perform technology assessments</b>				
5.1 EH&S Risk Assessment				
5.2 Update capture cost model				
5.3 Update Process Model to include integrated system performance				
5.4 Determine Solvent Manufacturability				
<b>Milestones:</b>				
-Technology EH&S risk assessment				
- Go /no go decision based on predicted performance of 90% CO2 capture with \$45/tonne CO2 capture cost				

	BP2 (k\$)
DOE Share	\$652
GE Share (20%)	\$163
<b>Total</b>	<b>\$815</b>



# BP2 Milestones and Success Criteria

Budget Period	Task	Milestone Title/Description	Planned Completion Date	Actual Completion Date	Verification Method	Comments
2	4.2	Absorber Parameters Established	3/31/2016		Unit Operations Testing Topical report	
2	4.2	Extruder Parameters Established	3/31/2016		Unit Operations Testing Topical report	
2	4.2	Desorber Parameters Established	12/31/2015		Unit Operations Testing Topical report	
2	4.5	Continuous System Assembled	3/31/2016		Research Performance Progress Report file	
2	5.1	Technology EH&S Risk Assessment	3/31/2016		EH&S Risk Assessment Topical report	
2	5.2	Preliminary cost study completed	3/31/2016		Preliminary Cost Study report	

## BP2 Success Criteria

- >90% GAP-0 conversion in absorber, reactor T < 90°C
- <5% solids lost from absorber solids collection
- >90% of carbamate conversion dictated by isotherms at T, P in pressurized desorber
- >95% of carbamate conversion in atmospheric desorber (polisher)
- 90% CO<sub>2</sub> Capture, <\$45/tonne CO<sub>2</sub>

# Thank You

- NETL
  - David Lang
- GE GRC Project Team
  - Mike Bowman, Joel Caraher, Wei Chen, Rachel Farnum, Mark Giammattei, Terri Grocela-Rocha, Robert Perry, Gosia Rubinsztajn, Surinder Singh, Irina Spiry, Paul Wilson, Benjamin Wood
- Coperion
  - Paul Andersen, Eberhard Dieterich

**Acknowledgement.** The information, data, or work presented herein was funded in part by the Advanced Research Projects Agency – Energy (ARPA-E), U.S. Department of Energy, under Award Number DE-AR0000084 and DOE- NETL under Award Number DE-NT0005310.

**Disclaimer.** The information, data, or work presented herein was funded in part by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.