



NETL Life Cycle Inventory Data

Process Documentation File

Tracked Input Flows:

Tree Harvester Chipper, 440 Horsepower
Propelled, Construction [Installation]

*Total number of harvester
chippers needed over the lifetime
of the energy conversion facility
(plant), normalized to the
reference flow*

Pushoff Trailer, 60m³, Tractor
Propelled, Construction [Installation]

*Total number of trailers needed over the
lifetime of the energy conversion facility
(plant), normalized to the reference flow*

Tracked Output Flows:

Equipment Assembly per kg Biomass [Installation]

*Amount of SRWC biomass
produced (reference flow)*

Section II: Process Description

Associated Documentation

This unit process is composed of this document and the data sheet (DS) *DS_Stage1_C_Assembly_SRWC_Harvesting_2010.02.xls*, which provides additional details regarding relevant calculations, data quality, and references.

Goal and Scope

The scope of this unit process covers the elements required for the components used in the harvesting of short rotation woody crops (SRWC) under Life Cycle (LC) Stage #1, as described below and in **Figure 1**. Harvest chippers and pushoff trailers are needed during the harvest to cut, chip, and transport the SRWC on the farm before it is transported during LC Stage #2 to the energy conversion facility (LC Stage #3). This unit process determines the fraction of each machine that should be allocated to each kilogram of SRWC biomass produced.

Construction data, including the mass of raw materials required to construct each piece of equipment, are calculated in separate unit processes. Therefore, the following unit processes are considered to be embedded in this assembly unit process: *DF_Stage1_C_Tree_Harvester_Chipper_440_HP_2010.01.doc* and *DF_Stage1_C_Pushoff_Trailer_60m3_Tractor_Propelled_2010.01.doc*. For a discussion of environmental emissions associated with the manufacture of raw materials used in the construction of SRWC harvesting components, as well as other pertinent information, please refer to these separate unit processes.

Boundary and Description

Figure 1 provides an overview of the boundary of this unit process. As it shows, the harvest chipper and trailer are constructed in separate, embedded unit processes. All emissions and environmental effects are accounted for upstream from this unit process, as discussed in greater detail in the documentation for each embedded unit process.

This unit process has three adjustable parameters, which can be adjusted to match the scenarios being examined. Both the harvest chipper and pushoff trailer have an assumed lifetime of 15 years, based on the assumptions presented in the DS. Depending upon the intensity of usage for these items, or based on additional data, the assumed lifetime may be increased or decreased. NETL currently suggests a yield of 6,214 kg/acre-year of SRWC for this LCA. This value may be adjusted based on study assumptions and recent or more relevant biomass production data.

Relevant properties of SRWC harvesting equipment used for the calculation of input and output flows for this unit process are shown in **Table 1**. **Table 2** provides a summary of the modeled input and output flows. Additional details showing calculation methods for input and output flows, and other relevant information, are contained in the associated DS.

Figure 1: Unit Process Scope and Boundary




Table 1: Properties for Assembly of SRWC Harvesting Equipment

Machine	Value	Unit	Source
Lifetime of Tree Harvester Chipper, 440 HP	15	years	NETL Engineering Judgment
Lifetime of Pushoff Trailer, 60m ³ , Tractor Propelled	15	years	NETL Engineering Judgment
Farm Size	500	acres	NETL Engineering Judgment
SRWC Yield	6,214 (13,700)	kg/acre-yr (lb/acre-yr)	NETL Engineering Calculation

Table 2: Unit Process Input and Output Flows

Flow Name*	Value	Units (Per Reference Flow)
Inputs		
Tree Harvester Chipper, 440 HP, Construction	2.14569E-08	pcs
Pushoff Trailer, 60m³, Tractor Propelled, Construction	2.14569E-08	pcs
Outputs		
Equipment Assembly per kg Biomass [Installation]	1	pcs

* **Bold face** clarifies that the value shown *does not* include upstream environmental flows. See also the documentation for embedded unit processes, as shown below.

Embedded Unit Processes

DF_Stage1_C_Tree_Harvester_Chipper_440_HP_2010.01.doc

DF_Stage1_C_Pushoff_Trailer_60m3_Tractor_Propelled_2010.01.doc

References

None.

Section III: Document Control Information

Date Created: January 18, 2010

Point of Contact: Timothy Skone (NETL), Timothy.Skone@NETL.DOE.GOV

Revision History:

13JUNE2012 Updated to revised parameter values.

How to Cite This Document:

This document should be cited as:
 NETL (2010). NETL Life Cycle Inventory Data – Process Data Sheet File: SRWC Harvesting Assembly, Construction. U.S. Department of Energy, National Energy Technology Laboratory. Last Updated: June 2012 (version 02).
www.netl.doe.gov/energy-analyses (<http://www.netl.doe.gov/energy-analyses>)

Section IV: Disclaimer

Neither the U.S. Department of Energy (DOE) National Energy Technology Laboratory (NETL) nor any person acting on behalf of these organizations:

- A. Makes any warranty or representation, express or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this document, or that the use of any information, apparatus, method, or process disclosed in this document may not infringe on privately owned rights; or
- B. Assumes any liability with this report as to its use, or damages resulting from the use of any information. Apparatus, method, or process disclosed in this document.

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by NETL. The views and opinions of the authors expressed herein do not necessarily state or reflect those of NETL.