



Upcycled “CO₂-negative” concrete for construction functions

Prepared by: Gaurav N. Sant, Ph.D.

Associate Professor and Henry Samueli Fellow

University of California, Los Angeles (UCLA)

420 Westwood Plaza, Boelter Hall: 5731-J, Los Angeles, CA 90024

Phone: (310) 206-3084, Email: gsant@ucla.edu

Collaborators: E. Callagon, S. Castano, R. Diwa, R. Minkara, D. Rajagopal, N. Neithalath, L. Pilon

Developed for: Project Kick-off Meeting at the National Energy Technology Laboratory (NETL), Pittsburgh, PA, June 9, 2017



Presentation outline

- Background
- Project objectives
- Team
- Scope of work (Tasks)
- Risks
- Project timeline
- Milestones
- Success criteria and decision points
- Budget



Background

- Electricity generation from coal-fired power plants represents 25% of total CO₂ emissions in U.S. (1.4 B tons CO₂ in 2015)
- Identify routes for large-scale utilization of CO₂ as a precursor in beneficial products and processes, while yielding a carbon capture and storage (CCS) solution of permanence
- Utilize CO₂ by mineralizing stable carbonate compound with cementitious character
- Rapidly source light metal cations, and accomplish material processing without generating additional CO₂ emissions



Project objectives

Upcycling industrial wastes and CO₂

- To utilize coal combustion and iron/steel processing wastes as precursors/reactant for scalable CO₂ mineralization

Process design

- To develop an integrated, 'bolt-on' technology/process solution for upcycled concrete production incorporating aspects of *Ca-leaching*, *Ca(OH)₂ precipitation*, *mixture formulation*, and *structural shape-stabilization*, while maximizing CO₂ uptake


OPC concrete replacement

- To develop a novel CO₂-negative *upcycled concrete* that is performance-equivalent or superior to OPC-based concrete while maintaining functional and utility equivalence



Process diagram


- Securing reclaimed solid reactants
- Ca-extraction (leaching) within a leaching reactor
- Concentration of leaching solution by capacitive concentrator, followed by $\text{Ca}(\text{OH})_2$ precipitation
- Formulation of a rheology-optimized slurry






Process diagram

- Shape-stabilization of slurry into the form of a structural section (beam, column, etc.)
- Contacting structural section with flue-gas borne CO₂ within a carbonation chamber → “upcycled concrete” section
- Low-grade heat sourced from flue gas prior to, and following, desulfurization to optimize kinetics






Upcycled concrete production process





Team structure and management






Team: Roles and responsibilities

Role	Responsibilities
<p><u>PI: G. Sant</u></p>	<ul style="list-style-type: none"> • Develop the project’s risk register based on project time duration, complexity of the technical tasks, and milestones • Promote and ensure risk management for the project • Ensure proactive responses to all risks and opportunities to ensure beneficial outcomes of the project • Communicate risks and their management to the partners and DOE • Monitor and update risk/threat matrix • Track and monitor the effectiveness of risk response actions and retire risks
<p><u>Faculty Co-PIs:</u> L. Pilon, N. Neithalath D. Rajagopal</p>	<ul style="list-style-type: none"> • Identify and assess risks • Develop response to risks • Communicate risks and response action to the PI, and contribute to the risk management plan
<p><u>Project Scientist:</u> B. Wang, E. Callagon</p>	<ul style="list-style-type: none"> • Implement risk management activities • Look out for new risks and devise minimization strategies • Monitor and update risks for specific activities or milestones
<p><u>Graduate Students:</u> TBD</p>	<ul style="list-style-type: none"> • Communicate issues in a timely manner to supervisors • Categorize risks and devise priorities for management • Report the mitigation strategies and document their effectiveness



Scope of work (Tasks)





Task 1: Project management and planning

- Periodic reports to DOE/NETL as well as manage informal correspondence and collaboration
- Technical briefings to DOE/NETL, and present project results jointly with other project partners at several industry- and DOE-sponsored conferences
- Monitor the project's progress against plan, review and, if necessary, update the project management plan on a frequent basis and report on budget and schedule variances to DOE/NETL



Task 2: Portlandite production by leaching of crystalline iron and steel slags

- Setup a laboratory-scale leaching reactor and establish the leaching kinetics of air-cooled, crystalline slags under different conditions
- Construct and evaluate a capacitive concentrator
- Deliver compiled data on leaching characteristics of the crystalline slags, and process parameters and throughput of the portlandite production process



Subtask 2.1: Slag characterization

- Chemical and mineralogical characterizations (e.g., using XRF, SEM-EDS, XRD) of the following slag types:
 - Crystalline iron
 - Carbon steel
 - Stainless steel
- Leachability and carbonation potential will be assessed based on total alkaline simples oxide contents (e.g., CaO, MgO, Na₂O, etc.)
- Surface area of the granulated slag particles will be measured by BET




Subtask 2.2: Slag leaching kinetics

- Slag leaching kinetics will be evaluated as a function of slag particle size and leaching temperature
- Leaching kinetics will be analyzed based on a diffusion-controlled model (from leachant analyses and surface area)
- Kinetics will be measured at 3 leaching temperature between 25 and 90 °C to establish an Arrhenius-type model



Subtask 2.3: Optimizing capacitive concentrator

- Fabricate porous carbon electrodes and characterize the capacitive concentrator with leachant solutions from Subtask 2.2 at 20 to 40 °C.





Task 3: CO₂ mineralization by accelerated carbonation

- Construct custom-built carbonation reactors and identify the appropriate process parameters to maximize the throughput of the CO₂ mineralization process.
- Carbonation characteristics of relevant coal-derived fly ash and leached slag granules, as well as the process conditions for carbonation of the *upcycled concrete* mortar will be delivered as a compiled dataset.



Task 3: CO₂ mineralization by accelerated carbonation

- **Subtask 3.1:** Fly ash particulates will be characterized using XRF and SEM-EDS (composition) and XRD (mineralogy), as in **Subtask 2.1**
- **Subtask 3.2:** Carbonation studies on blended fly ash, leached slag, and portlandite mixtures to assess their carbonation potential. Proportions may be adjusted by increasing precipitated portlandite content



Task 3: CO₂ mineralization by accelerated carbonation

- **Subtask 3.3:** Custom-built carbonation reactors to establish the carbonation kinetics of fly ash, portlandite, and slag, as a function of temperature (45-90 °C) and CO₂ concentration (6-18%). Carbonation level will be determined by TGA.
- **Subtask 3.4:** Carbonation studies on *upcycled concrete* (equivalent mortars), with blend design and at carbonation conditions from **Subtasks 3.2 and 3.3**. Optimal proportions (i.e., from a carbonation perspective) will be established.




Task 4: Upcycled concrete fabrication and properties

- Determine the mixture proportions that optimize the rheology and workability of fresh upcycled concrete formulations (i.e., “mixing ratios” between the fly ash-portlandite-slag particulate blends, additional fine aggregates, water and chemical admixtures (as needed)).
- Develop and identify and optimal shape stabilization process for fabrication of prismatic upcycled concrete geometries
- Mechanical performance of upcycled concrete will be evaluated using standard ASTM protocols



Subtask 4.1: Rheology characterization and optimization of upcycled concrete mortars

- Rheology of mortars from **Task 3** will be characterized in terms of yield stress, plastic viscosity, suspension stability
- Dispersants to ensure suitable workability and shape stability
- Suitable shape stabilization process (e.g., extrusion forming, molding, or pressing) will be selected





Rheology characterization and optimization of upcycled concrete mortars


- Slurry rheology
 - On binder proportions designed to achieve target carbonation levels
 - Yield stress and plastic viscosity as the target parameters
 - Mini slump for rapid assessment

$$\text{Flow Coefficient } (\kappa) = \sqrt{\frac{A_{ms}}{\tau_y \times \mu_p}}$$
$$\kappa_i \geq$$



Linking particle characteristics to rheology


- Suspensions at solid loadings close to maximum packing are very sensitive to operating conditions
- Packing of particles and packing characteristics (e.g., number density, SSA) related to rheology
- Provides a means to design particle characteristics (e.g., careful size distribution of components, grinding) for desired rheology that help form construction elements





Subtask 4.1: Rheology characterization and optimization of upcycled concrete mortars


- Low workability (stiff mixtures)
 - Stabilization by compaction/pressing into the molds (e.g., concrete blocks)
- Intermediate workability
 - Extrusion into structural shapes (e.g., beams, pipes, poles)
- Highly flowable mixtures
 - Casting
 - Rheology control to prevent segregation






Subtask 4.2: Concrete formulation, shape stabilization, property characterization

- Develop formulations and material proportions for optimal upcycled concrete mixtures
- Mortars will be formed into prismatic samples using shape stabilization method in **Subtask 4.1**



Laboratory tests




Shape stabilization based on application



Forming structural shapes using


- Mixtures with desired rheology used as binders in the formation of structural shapes for carbonation
- Fine and coarse aggregates for volumetric stability
- Determination of adequate paste volume fraction (film thickness on particles) to ensure binding capacity
- Mixing procedure to ensure homogeneity and molding into structural shapes






Stabilizing structural shapes

- Rheology modification of binders so as to obtain desired workability
- Workability dictates the stabilization method
- Relating the flow coefficient to the method of shape stabilization



Laboratory tests






Shape stabilization method based on application





Subtask 4.2: Concrete formulation, shape stabilization, property characterization

- Mechanical property analyses (e.g., flexural strength) following ASTM
- Engineering properties of upcycled concrete
 - Compressive strength
 - Flexural strength
 - Modulus of elasticity
 - Fracture properties





Mixture refinement and optimization

- Mechanical properties to refine the mixture
- A target flexural strength > 7 MPa for the carbonated pastes
- If needed, strength enhancement procedures will be employed
 - Better particle packing
 - Additives such as sodium silicate
 - Refining carbonation parameters to increase carbonation efficiency



Task 5: Process design and scalability assessment

- Establish process design for laboratory-scale, integrated *upcycled concrete* production system, and for its industrial scale-up
- Detailed design for the laboratory-scale demonstrated system to be constructed and tested in **Task 6** will be delivered



Task 5: Process design and scalability assessment

- **Subtask 5.1 (Component selection and design):** Identify the characteristics and specification of each component, with focus on the design and performance of capacitive concentrator and leaching reactor. Equipment required for assembling a laboratory-scale system is identified.
- **Subtask 5.2 (System design and process optimization):** Create a system design that integrated the individual components of the *upcycled concrete* process



Task 6: System evaluation

- Construct a laboratory-scale system to demonstrate the integrated *upcycled concrete* process.
- Report of all performance data collected during experimental test runs, including CO₂ uptake, mass flow rate, production throughput, energy consumption, etc. will be delivered.



Subtask 6.1: System procurement/construction

- Procure required equipment components from **Subtask 5.1**, and assemble a laboratory-scale test system from **Subtask 5.2**.
- Procure simulated coal-fired power plant flue gas.
- Establish operating procedures and test plan



Subtask 6.2: Integrated laboratory-scale tests

- Conduct test runs with the laboratory-scale system to evaluate the integrated *upcycled concrete* process
- Perform 3 test runs using simulated coal-fired power plant flue gas (e.g., typical concentration on the order of: 14 +/- 2% CO₂, 6.2 +/- 1% H₂O, 3.4 +/- 0.5% O₂, 20-120 ppm SO₂, 75-250 ppm NO_x, 74.5 +/- 2% N₂) for a 12-24 h duration
- Produce upcycled concrete with 3 different (target) CO₂ uptake levels



Subtask 7.1: Scalability assessment and economic feasibility study

- Technical and economic feasibility study to provide detailed accounting of capital costs, operation and maintenance costs and RSP relative to existing markets for the scaled-up process
- Conceptual design for coupling the upcycled concrete production process with coal-fired power plant
- Market assessment, including all revenue streams, assumed unit costs, current and projected market volume and value, and estimated quantity of CO₂ utilized.
- Deliver compiled results of the techno-economic feasibility study, including a high-level, return-on-investment (ROI) analysis based on experimental and modeling results.



Subtask 7.2: Lifecycle analysis

- Lifecycle analysis (LCA) that considers both material and process aspects.
- System design from **Subtask 5.2** will be further optimized for minimizing the LCA impacts
- LCA considering both materials and processing aspects will be conducted to identify environmental benefits
- Quantify net CO₂ avoidance offered



Subtask 7.3: Technology gap analysis

- Technology Gap Analysis to review the state of upcycled concrete process development.
- Estimations of performance, cost, emission, market, safety metrics per NETL's guidelines for carbon utilization and storage technologies
- Technology Readiness Level (TRL) of critical process components (portlandite production by leaching and precipitation, CO₂ mineralization), upcycled concrete fabrication)
- Summarize commercially-available equipment components and potential vendors



Risk management approach

- Close monitoring of scientific/financial aspects by PI and a project manager
- *Risk register* will help identification and mitigation of risks





Technical risks

Description of Risk	Probability	Impact	Risk Management Mitigation and Response Strategies
Slags show characteristics of slow leaching kinetics	Low	Moderate	Improve the kinetics by increasing interfacial surface area between slag particles and leachant, and dilution ratios, and slightly acidifying the leachant.
Unsatisfactory throughput or output concentration level from the capacitive concentrator	Moderate	Low	Construct a multi-concentrator system with concentrators in series (to improve concentration performance) or in parallel (to improve throughput). Further, use waste heat from power plant to accelerate precipitation by actively evaporating the concentrated solution.
Fly ash shows slow carbonation kinetics and/or low carbonation potential due to low calcium content	Moderate	Low	Increase the Ca(OH)_2 /fly ash ratio, and/or secure calcium-rich fly ash (i.e., higher CaO content)



Technical risks (cont.)

Description of Risk	Probability	Impact	Risk Management Mitigation and Response Strategies
Concrete slurry shows unsatisfactory workability	Moderate	Moderate	Adjust workability with rheology modifiers (e.g., viscosity modifiers, and dispersants)
Carbonated concrete shows unsatisfactory strength	Low	Moderate	Enhance strength by pre-carbonation densification to reduce porosity reduction, and/or add inorganic binders to the formulation



Resource risks

Description of Risk	Probability	Impact	Risk Management Mitigation and Response Strategies
Budget shortfalls	Moderate	High	Closely monitor project costs and scope, and set spending priorities based on timelines and milestones.
Inexperienced staff	Low	Low	Schedule sufficient time for training of new staff and technicians
Losing critical staff at crucial point of the project	Low	Moderate	Training multi-skilled, cross-trained students and staff and establish clear standard operating procedures
Delayed delivery of supply	Moderate	Low	Anticipate supplies, front order, and plan for potential delays



Management risks

Description of Risk	Probability	Impact	Risk Management Mitigation and Response Strategies
Scope creep	Low	High	Set clear priorities and assign resources based on timelines and milestones defined in project management plan. Maintain clear communications between teams and DOE.
Intellectual property risks	Moderate	Moderate	Ensure that the project participants are knowledgeable of relevant IP agreements, and uniqueness of the research outcomes
Delayed finish of earlier activities	Moderate	Moderate	Closely track project progress and develop alternative pathways when delays emerge. Ensure timely delivery of independent research activities when delays emerge.



Project timeline

Tasks	Budget Period 1					Budget Period 2				Budget Period 3		
	4/1/17 - 6/30/18					7/1/18 - 6/30/19				7/1/19 - 3/31/20		
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12
Task 1.0 – Project Management and Planning	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active
Subtask 1.1 - Project management and planning	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active
Subtask 1.2 - Briefing and reports	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active	Active
Task 2.0 – Portlandite production by leaching of crystalline iron and steel slags	Active	Active	Active	Active	Active							
Subtask 2.1 - Slag characterization	Active	Active										
Subtask 2.2 - Slag leaching kinetics		Active	Active									
Subtask 2.3 - Optimizing capacitive concentrator			Active	Active								
Subtask 2.4 - Portlandite precipitation characteristics				Active	Active							



Project timeline (cont.)

Tasks	Budget Period 1					Budget Period 2				Budget Period 3		
	4/1/17 - 6/30/18					7/1/18 - 6/30/19				7/1/19 - 3/31/20		
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12
Task 3.0 – CO₂ mineralization by accelerated carbonation	█	█	█	█	█							
Subtask 3.1 - Characterization and carbonation potential assessment of fly ash	█	█										
Subtask 3.2 - Carbonation potential of blended fly ash and portlandite		█	█									
Subtask 3.3 - Carbonation kinetics in simulated flue gas mixture			█	█								
Subtask 3.4 - Carbonation of upcycled concrete mortars (optimized blends)				█	█							



Project timeline (cont.)

Tasks	Budget Period 1					Budget Period 2				Budget Period 3		
	4/1/17 - 6/30/18					7/1/18 - 6/30/19				7/1/19 - 3/31/20		
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12
Task 4.0 – Upcycled concrete fabrication and properties						█	█	█	█			
Subtask 4.1 - Rheology characterization and optimization of upcycled concrete mortars						█	█					
Subtask 4.2 - Concrete formulation, shape stabilization, property characterization								█	█			
Task 5.0 – Process design and scalability assessment						█	█	█	█			
Subtask 5.1 - Component selection and design/modifications						█	█					
Subtask 5.2 - System design and process optimization								█	█			



Project timeline (cont.)

Tasks	Budget Period 1					Budget Period 2				Budget Period 3		
	4/1/17 - 6/30/18					7/1/18 - 6/30/19				7/1/19 - 3/31/20		
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12
Task 6.0 – System demonstration												
Subtask 6.1 - Component procurement and system construction												
Subtask 6.2 - Integrated laboratory-scale testing												
Task 7.0 – Final Technology Assessment												
Subtask 7.1 - Scalability assessment and economic feasibility study												
Subtask 7.2 - Lifecycle analysis												
Subtask 7.3 - Technology Gap Analysis												



Milestones

Milestones	Budget Period 1					Budget Period 2				Budget Period 3		
	4/1/17 - 6/30/18					7/1/18 - 6/30/19				7/1/19 - 3/31/20		
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12
a. Updated Project Management Plan	■											
b. Kickoff meeting	■											
c. Establish the leaching characteristics (i.e., rate and extent) for 3 unique slag types				■								
d. Achieve 3 different CO ₂ uptake levels (between 0.06-0.12 grams of CO ₂ per gram of solid reactants) with blended fly ash and portlandite formulations					■							
e. Establish the rheology characteristics for upcycled concrete formulations with 3 different fly ash-portlandite blends								■				
f. Establish shape-stable, upcycled concrete formulation with compressive strength ≥ 15 MPa									■			



Milestones (cont.)

Milestones	Budget Period 1					Budget Period 2				Budget Period 3		
	4/1/17 - 6/30/18					7/1/18 - 6/30/19				7/1/19 - 3/31/20		
	Q1	Q2	Q3	Q4	Q5	Q6	Q7	Q8	Q9	Q10	Q11	Q12
g. Establish process design for lab-scale test unit with production throughput between 10-to-100 kg of upcycled concrete per day												
h. Complete construction of lab-scale test unit with production throughput between 10-to-100 kg of upcycled concrete per day												
i. Achieve production throughput between 10-to-100 kg upcycled concrete per day, with CO ₂ uptake between 0.06-0.12 grams of CO ₂ per gram of reactants												
j. Establish scalability, lifecycle CO ₂ footprint and techno-economic feasibility												
k. Technology Gap Analysis												
QR. Quarterly RPPR report												



Success criteria and decision points

Completion of BP 1

- Successful completion of all work proposed in Budget Period 1
- Carbonation characteristics of relevant coal-derived fly ash and leached slag granules, and the process conditions for carbonation of upcycled concrete mortar
- The critical steps (leaching, portlandite production, and carbonation) can be carried out such that the process can complete in 24-to-168 hours or less

Completion of BP 2

- Successful completion of all work proposed in Budget Period 2
- Achievement of a target upcycled concrete compressive strength of 15 MPa
- Resulting construction material has a lifecycle footprint that is >75% smaller than OPC-concrete of equivalent performance grade (preliminary assessment)
- Design of laboratory-scale, integrated concrete production system with production throughput between 10-to-100 kg of upcycled concrete per day

Completion of BP 3

- Successful completion of all work proposed
- Real-time CO₂ uptake of the lab-scale test unit is accurate within 20% of the estimated “carbonation potential”
- Resulting construction material has a lifecycle footprint that is >75% smaller than OPC-concrete of equivalent performance grade (final assessment)
- Conceptual scaled-up process design and the completion of then required technical and economic feasibility study, market assessment, lifecycle analysis, and technology gap analysis



Project Funding Profile

	Budget Period 1		Budget Period 2		Budget Period 3		Total Project	
	04/01/17-06/30/18		07/01/18-06/30/19		07/01/19-03/31/20			
	Gov't Share	Cost Share	Gov't Share	Cost Share	Gov't Share	Cost Share	Gov't Share	Cost Share
UCLA	\$344,436	\$155,533	\$274,142	\$119,467	\$181,421	\$25,000	\$799,999	\$300,000
ASU	\$75,155	\$18,480	\$66,541	\$15,583	\$58,304	\$15,937	\$200,000	\$50,000
Total	\$419,591	\$174,013	\$340,683	\$135,050	\$239,725	\$40,937	\$999,999	\$350,000
Cost Share	71%	29%	72%	28%	85%	15%	74%	26%



Budget Period/Fiscal Year Project Costing Profile

Budget Period	Fiscal Year	Performing Organization	Planned Costs	
			Federal Share	Non-Federal Share
1	FY17	UCLA	\$156,819	\$56,382
1	FY18	UCLA	\$187,618	\$99,151
2	FY18	UCLA	\$76,568	\$20,492
2	FY19	UCLA	\$197,574	\$98,975
3	FY19	UCLA	\$83,177	\$-
3	FY20	UCLA	\$98,244	\$25,000
1	FY17	ASU	\$30,062	\$4,620
1	FY18	ASU	\$45,093	\$13,860
2	FY18	ASU	\$16,635	\$-
2	FY19	ASU	\$49,906	\$15,583
3	FY19	ASU	\$19,435	\$5,312
3	FY20	ASU	\$38,869	\$10,625