Ultra High Temperature Anode Recycle Blower for Solid Oxide Fuel Cell

> Department of Energy Award No. DE-FE0031148

Prepared for DOE Kickoff Meeting By Mohawk Innovative Technology, Inc.



#### Principal Investigator: Hooshang Heshmat, PhD DOE Program Manager: Jason T. Lewis, Program Director

DE-FOA-0001735 "Solid Oxide Fuel Cell Prototype System Testing and Core Technology Development" Dec 1 2017

#### Project Team



#### MITI

- Hooshang Heshmat, PhD
  - Principal Investigator
- Jose Luis Cordova, PhD
  - PM/Thermal Management
- James F. Walton II
  - Rotordynamics
- Garrett M. Davis
  - Aerodynamic Design




#### Team Background



MITI Specializes in High-Speed, High-Temperature Oil-Free Rotating Machinery Technology

- Blowers
- Compressors
- Turbo-alternators
- Gas-Turbine Engines
- Flywheel Energy Storage
- And more



#### MITI's Completely Oil Free Blower & Compressor Technology




### MITI's Compliant Foil Bearings Gen-V

**Completely OIL FREE Technology** 


- High Load & High Temperature
- Sizes from 6 to 200 mm Diameter
- DN to over 6 Million
- Speeds greater than 700,000 RPM





# Project Overall Objective

- Develop ultra-high temperature anode recycle blower (UHT-ARCB) prototype that uses *uncooled* Solid Oxide Fuel Cell (SOFC) anode gas
  - Demonstrate successful operation of UHT-ARCB
  - Demonstrate that design can achieve TRL5
  - Determine fabrication methods to achieve commercial cost of < \$110 per SOFC kWe
- Increase Efficiency and Reduce BOP
  - Recycle anode off-gas
  - Reduce external water supply used for fuel reforming
  - Elimination of heat exchangers
  - Reduce BOP footprint




#### Leverage Precursor 180°C SOFC ARC


- Developed a 180°C Anode Recycle Blower for 100 kWe SOFC
  - DOE Award No.: DE-FE0027895
  - The prototype is currently undergoing performance testing
  - Eventual goal of that program is to test in an actual 100 kWe SOFC demonstrator by FuelCell Energy, Inc. (FCE)
- All the know-how obtained, particularly with regard to design for manufacturability and cost for commercialization will be leveraged.



#### Advantage of UHT-ARCB vs. 180°C ARCB




#### Advantage of UHT-ARCB vs. 180°C ARCB



- Benefits of using UHT-ARCB
  - Reduced BOP by elimination of HXs and supporting piping, insulation.
  - Reduced pressure drop
  - Reduced thermal losses by ~6kW

# Technical Appl



### Project Structure

- Task 1: Project management and planning
  - Report Preparation
  - Kickoff and Annual Review Meetings
- Task 2: Definition of requirements
- Task 3: Design Proof-of-Concept System
  - Preliminary design
  - Detailed design and analysis
- Task 4: Hardware Fabrication and Assembly
  - Checkout tests
- Task 5: UHB-RCB Testing
  - Dynamic and high temperature test data
- Task 6: Final report and assessment of outcomes

# Task 2: Definition of Requirements

- Operating conditions specified with input from FuelCell Energy Inc.
  - For this program, FCE has provided specifications and operating regimes at no-cost.
- Three operating regimes to consider
  - Start Up Transient
  - Nominal Operation
  - Rated Operation


			Operating Regime								
Property	Ui	nits	Nominal	Rated	Start-Up						
Temperature	Т	[°C]	621	650	700						
Inlet Pressure	Р	[kPa]	103.9	103.9	103.9						
Mass Flow	m	[kg/s]	0.033	0.036	0.22						
Pressure Increase	$\Delta \mathbf{P}$	[kPa]	7.2	8.7	Unspecified						

Anode Recycle Gas Composition:

• Mixture of Water Vapor, Methane, Carbon Dioxide, Carbon Monoxide, Hydrogen

### Task 2: Design Considerations


- Net Power Input < 3 kW
- Oil-Free Foil Bearing Design
  - No Lubricant Contamination
  - Low Power Loss Bearings
- Process gas (CH<sub>4</sub>) for secondary gas path
- Process gas for housing cooling, with option for forced water/glycol loop necessary
- Economical Design
  - Low Capital Cost
  - Low Maintenance Cost
  - Low Operating Cost



#### Task 3: Design Process

**Oil-Free System Design Elements** 


- Motor/Power Electronics
- Fluid/Thermodynamic Analysis
- Aerodynamic Design
- Rotor-Dynamic Analysis
- Foil Bearing Design
- Thermal Management



#### Task 3: General Layout

#### **180°C Precursor Anode RCB**


#### **UHT-RCB**




### Task 3: Aerodynamic Design Summary


#### **Preliminary Sizing Results**

- Type = Centrifugal
- Diameter = 75 mm
- Operating Speed Range
  - 55 krpm < N < 80 krpm
- Adiabatic Efficiency > 70%
- Material: Rene 41







#### Task 3: Aerodynamic Design Performance



#### Task 3: Aerodynamic Design Performance



#### Task 3: Aerodynamic Design Performance




#### Task 3: Motor Selection

- Permanent Magnet Motor
- Encapsulated Samarium Cobalt
- Permits Larger Air Gap
- Higher Efficiency




#### 3 kW design based on previous 1.5 kW version

#### Task 3: Preliminary Rotordynamic Analysis



### Task 3: Secondary Flow and Cooling Scheme

- A 100 kW fuel cell stack uses 3.14 g/sec of fresh CH<sub>4</sub>.
  - Available CH<sub>4</sub> Conditions: T<sub>i</sub> ~ 20°C, P<sub>i</sub> ~ 205 kPa
- The CH<sub>4</sub> can be used in the secondary flow for thermal management.
- Available CH<sub>4</sub> flow can remove up to up to 1.2 kW thermal an maintain motor in a safe temperature zone.




#### Task 3: Work in Progress

- Complete Preliminary Layout
- Detailed Design
  - Rotating Components
  - Housing
  - Bearings
  - Thermal Management
- Manufacturing & Assembly Drawings

# Task 4: Hardware Fabrication and Integration

- Fabricate and Instrument Prototype
  - Vibration/Displacement Probes
  - Thermocouples/Pressure Transducers
- Preliminary and Checkout Tests
  - Validate Instrumentation Operation
  - Verify Motor/Controller Operation
  - Confirm Rotor Lift-Off Speed
  - Leak Check



### Task 5: UHT-ARCB Testing

- Demonstrate ability to achieve full design speed
- Measure flow rate and pressure/temperature rise with room temperature air and high temperature (up to 700°C) similitude gas and map performance characteristics
- Compare measured and design performance

### Task 6: Assessment of Outcomes

- Objectives:
  - Compare results to requirements
  - Assess scalability of technology
    - Explore design scalability up to flows for SOFCs with power output in the 10 MWe range and higher
  - Assess economic performance and compare to cost target of \$110 per SOFC generated kWe
    - Estimated cost for 1 MW load meets or is less than the targeted cost of \$40 per SOFC generated kWe

#### Task 6: Cost Considerations and Scalability

#### Projected Cost After Product Development:

- Estimated Cost for First 10 Units
  - 3 kW: \$12k \$15k / unit
  - 50 kW: \$40k \$60k / unit

#### Project Schedule

		2017		2018									2019						
Tasks	Q1		Q2		Q3		Q4		Q5			Q6							
	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
Task 1: Project Management and Planning																			
Task 1.1: Report Preparation					Quarte Prog. F	ry eports											Final	Report	
Task 1.2: Meetings and																			
Presentations		Kick-off	Meeting					Annual M	lerit										
Task 2: Definition of	•							Reveiew											
Requirements	Commun	ication w	th FCE												Mile	Milestones			
Task 3: Design of Proof of Concept				]	]														
System															📙 Quarterly Reports 🏼 🖌				
Task 3.1: Preliminary Design					Prelim Design	inary Review										-	•		
Task 3.3: Detailed Design							Detaile Reviev	ed Design v											
Task 4: Hardware Fabrication and Integration													Hardwa	re Comple	ete				
Task 5: Blower Performance Test																	End of T	esting	
Task 6: Assesment of Outcome and Plan Forward																			

#### Project Budget

#### Total Estimated Cost: \$373,819.00

- 80% Government Share: \$ 299,055.00
- 20% Recipient Share: \$ 74,764.00

#### Risk Management

Main Risks Identified (R) and Planned Mitigation Strategies (M):

- R: Thermal management: CH<sub>4</sub> cooling scheme may be insufficient
  - M: Additional closed loop water/glycol (with stock radiator and pump)
- R: Schedule of long lead items: Motor Magnet procurement may cause prototype fabrication delay
  - M: Handle motor set component procurement as a critical path step.
  - M: Secure quotes from multiple vendors
- R: Prototype Fabrication Cost: Initial prototype low-volume cost may be high.
  - M: Minimize part count
  - M: Casting of as many parts as possible
  - M: Material substitution where thermally possible

### Technology Readiness Level

#### • TRL Definitions

- <u>TRL 5</u> System/subsystem/component validation in relevant environment:
- <u>TRL 6</u> System/subsystem model or prototyping demonstration in a relevant end-to-end environment
- Prototype will be a high TRL 5 at end of Phase I
- Will achieve TRL 6 at end of an eventual Phase II

#### Status Summary

- Design Requirement Reviewed
- Preliminary Design and Layout Underway
- Detailed Design to Begin in Feb 2018
- Manufacturing to Begin Apr 2018

#### Thank You For Your Attention

