



**Progress in SOFC Development at FuelCell
Energy**

**13th Annual SECA Workshop
Pittsburgh, PA
July 24-25, 2012**

Hossein Ghezel-Ayagh, *FuelCell Energy, Inc.*



FuelCell Energy



Versa Power
Systems

■ Introduction

- FCE SECA Program Team Members
- SECA Coal-Based SOFC Program Overview

■ Progress in SOFC Technology

- Cell Development and Manufacturing

■ Stack Development

- Scale-up and Tower Tests

■ Proof-of-Concept Module (PCM) Development

- Stack Module
- 60 kW PCM System

■ Baseline System Design and Cost Analyses

- Integrated Gasification Fuel Cell (IGFC) System Configuration
- Updated Baseline Power Plant Cost Estimate

■ Conclusion and Future Plans





- Premier developer of stationary fuel cells with >40 years of experience
- Delivering Direct FuelCell® (DFC®) power plants to commercial and industrial customers
 - 182 MW installed and in backlog (>80 power plants), plus 120 MW MOA
- Established commercial relationships with major distributors in the Americas, Europe, and Asia
- Developing large-scale coal-based power plants as well as natural gas distributed generation (DG) systems utilizing planar SOFC

Delivering ultra-clean baseload distributed generation globally



600 kW plant at a food processor



1.4 MW plant at a municipal building



2.4 MW plant owned by an independent power producer



2.8 MW DFC3000 Wastewater Treatment Plant



Large Scale Power Plants

Experience in large scale power plants will be utilized in design, fabrication, and operation of Coal-Based SOFC Plants



**10.4MW Plant
(Yeosu, S. Korea)**



**11.2 MW Plant
(Daegu City, S. Korea)**



**60MW System in Development
(Hwaseong, S. Korea)**





**Proposed 15 MW fuel cell park
(Bridgeport, CT)**



SOFC Cell and Stack Technology Background

- Planar anode supported cells (up to 1000 cm²)
- Capable of operating from 650 C to 800°C
- Ferritic stainless steel sheet metal interconnect
- Cross-flow gas delivery, with integrated manifolding
- Standardized stack blocks configurable into stack towers for various power applications



Versa Power Systems (VPS)

- **Privately held company**
 - > Founded as joint venture of Solid Oxide Fuel Cell Consortium in 2001
 - > Headquartered in Littleton, Colorado, United States
 - > Established SOFC development facility in Calgary, Alberta, Canada
- **Planar solid oxide fuel cell technology**
 - > Achieved high electrical power densities and long life using low-cost materials
 - > Developed manufacturing processes scalable to high volume production rates
 - > Established standardized SOFC stack products
 - > Extended R&D for defense and regenerative fuel cell applications



32,000 ft² research & pilot manufacturing Facilities in Calgary, CA



17,000 ft² facility in Littleton, Co



Coal-Based SECA Program Status

Phase I


- Cell & stack scale-up
- Validation testing of 64-cell stack block (10 kW)
- Pilot manufacturing process development and yield increase



10 kW Stack

Phase II


- Increased cell performance and endurance combined with cost reduction
- Standardization of 96-cell stack block
- Demonstration of 2-stack tower (30 kW) operation
- Configuration of an IGFC system achieving DOE's performance and cost targets



30 kW Stack Tower

Phase III

- Increased cell and stack robustness and reliability
- Development of a >50kW Stack Module design
- Validation testing of 60 kW module non-repeat hardware in preparation for upcoming 60kW Stack Module testing



60 kW Stack Module



Presentation Outline

■ Introduction

- FCE SECA Program Team Members
- SECA Coal-Based SOFC Program Overview

■ Progress in SOFC Technology

- Cell Development and Manufacturing

■ Stack Development

- Scale-up and Tower Tests

■ Proof-of-Concept Module (PCM) Development

- Stack Module
- 60 kW PCM System


■ Baseline System Design and Cost Analyses

- Integrated Gasification Fuel Cell (IGFC) System Configuration
- Updated Baseline Power Plant Cost Estimate

■ Conclusion and Future Plans



Cell Development Accomplishments



◆ Cathode Development

- ☑ Enhanced Performance and Endurance
- ☑ Reduced Operating Temperature
- ☑ Increased Operating Window

◆ Anode Development


- ☑ Reduced Cell Thickness
- ☑ Enhanced Performance at Higher Fuel Utilization and at Lower Temperature
- ☑ Enhanced Cell Mechanical Properties and Robustness

◆ Scale Up & Manufacturing Development

- ☑ Scaled up from 121 cm² → 550 cm² → 1000 cm²
- ☑ Established Manufacturing Processes for Baseline 550cm² Cells
- ☑ Completed Process Integration and Validation in Transitioning from TSC2 → TSC3 technology



Cell Technology Evolution




➔ Significant progress has been made toward enhancing cell performance and endurance.



Development of Hydrothermal Stable Cell


- **Hydrothermal stability issues for thin cells**

- > 3YSZ was initially used in anode substrate for thin (0.6 mm) TSC3 cells
- > The anode made with 3YSZ exhibited hydrothermal stability issues due to monoclinic phase formation at 100 to 400 C with humidity
- > Phase changes resulted in cell cracking due to anode substrate volume increase (up to 7%)




Development of Hydrothermal Stable Cell

- Over 20 anode substrate formulations were explored and tested
- A preferred solution was found and validated in stack testing
- Cell manufacturing process was re-developed to implement the changes




Interconnect Alloy and Coating Development

- **Baseline alloy with high quality MCO spinel coating has shown excellent results in cell and stack endurance tests**
 - ~ 0.3% / 1000 hrs in the single cell test over 18,000 hours
 - ~ 0.4% / 1000 hrs in the stack test over 20,000 hours
- **Alternative low cost steels (alloy A and alloy B) were coated and tested in a parametric stack test with the baseline alloy and coating**
- **Coated low cost alloy A delivered better results than the baseline alloy**



Cell Scale-Up Development

- VPS' established **Tape casting/Screen Printing/Co-firing (TSC)** process proved flexible enough to allow a > 8x increase in cell active area (121 → 1000 cm²)
- Cell thickness was reduced from 1 mm to 0.6 mm
- 25 cm x 25 cm cells (550 cm² active area) are the focus for large area stack development



Tape Casting



Screen Printing



Co-sintering



■ Introduction

- FCE SECA Program Team Members
- SECA Coal-Based SOFC Program Overview

■ Progress in SOFC Technology

- Cell Development and Manufacturing

■ Stack Development

- Scale-up and Tower Tests

■ Proof-of-Concept Module (PCM) Development

- Stack Module
- 60 kW PCM System


■ Baseline System Design and Cost Analyses

- Integrated Gasification Fuel Cell (IGFC) System Configuration
- Updated Baseline Power Plant Cost Estimate


■ Conclusion and Future Plans



Stack Development Accomplishments




- **Improved stack performance**
 - > Higher power density
 - > Higher fuel utilization
 - > Higher direct internal reforming
- **Enhanced stack endurance**
 - > Improved stack thermal and flow management
 - > Incorporated TSC3 cells
 - > Incorporated advanced metallic coating technology, contact and flow media
- **Reduced stack cost to meet SECA cost targets**




3-5 kW Module for Short-Stack Testing

- **Objective:** Provide a platform for testing short stacks under various process conditions with reduced technical risk relative to large modules
- **Benefits:**
 - > Enables rapid stack change-out (less than 1 day)
 - > Test stacks under expected system conditions
 - > Study stack/module design alternatives under a thermally self-sustaining environment
 - > Investigate thermal cycling, start-up and shut-down procedures.
- **Design Features:**

Stack Change-out without the need for piping removal





- Power Take-Off (PTO)
- Easily-removed top enclosure (aluminum)
- Instrumentation pass-through (2x)
- SS shell





3-5kW Module Test Results Using 16-cell Stack

- Preferred system operating procedures and controls were identified using Sub-scale testing platform.
- Performance and thermal profiles were evaluated as function of fuel composition, extent of internal reforming, and fuel/air utilizations.
- System level heat-up/shut down procedures were tested with acceptable results.

Air Utilization = 13.5%
Maximum On-cell $\Delta T = 77^{\circ}\text{C}$
Average Cell Temp. = 753°C



Air Utilization = 25%
Maximum On-cell $\Delta T = 77^{\circ}\text{C}$
Average Cell Temp. = 760°C



Stack Fabrication

Stack Size	Phase I Quantity	Phase II Quantity	Phase III Quantity	Total
Short Stacks 6 - 32 Cells	39	43	16	98
Full Size Stacks > 64 cells	6	9	15	30
Total Quantity	45	52	31	128
Total kW	126	255	262	643



Phase III stack block (96-cell)



6-cell short stack



16-cell short stack



Phase I stack block (64-cell)



Phase II stack block (92-cell)



Standard 96-Cell Stack Block Development and Fabrication




4x 96-cell stacks to be integrated in a 60 kW module as shown on a shipping crate

- > Reduced stack heights through component reduction
- > Reduced on-cell thermocouples
- > Improved production tooling
- > Implemented additional QA and QC steps for stack components
- > Refined stack acceptance criteria
- > Accomplished factory acceptance testing of 14 x 96-cell stacks with consistent results




Stack Acceptance Tests Before and After Thermal Cycle



➔ **Stack Displays stable performance, even at high fuel utilization, after thermal cycling**




Performance Consistency of 96-cell Stacks



➔ **Ten 96-cell TSC3 stacks have been built, displaying consistently higher performance than previous TSC2 technology**



96-Cell Stack Endurance Testing



➔ **Recent stacks have been shown improved stability and reliability utilizing advanced components and materials developed in Phase III**




Stack Tower Testing



- **Thermally self-sustaining test environment (gas preheated only)**
- **Provisions for simulated anode gas representative of both coal-derived syngas and natural gas fueled systems**
- **Simulates commercial system operation: Providing valuable lessons for future larger stack module designs**



30kW-5 Stack Tower Test Results



➔ Tests of the 30 kW stack (30-5) tower is being continued under system operating conditions.



■ Introduction

- FCE SECA Program Team Members
- SECA Coal-Based SOFC Program Overview

■ Progress in SOFC Technology

- Cell Development and Manufacturing

■ Stack Development

- Scale-up and Tower Tests

■ Proof-of-Concept Module (PCM) Development

- Stack Module
- 60 kW PCM System

■ Baseline System Design and Cost Analyses

- Integrated Gasification Fuel Cell (IGFC) System Configuration
- Updated Baseline Power Plant Cost Estimate

■ Conclusion and Future Plans



60 kW Stack Module Design Development



Complete Module



Compression Plate



Hot Buss Bars



Internal Fuel Pre-Heater




Module Integration and Instrumentation



High Temp. Flanges



Quad Base



Conductive Stack Gasket






60 kW Module Hardware Testing

Objective: Validate all non-repeat module components in hot operation with inexpensive mock (non-real) stacks

- **Flow:**
 - > Validate CFD models for flow uniformity
 - > Verify pressure drop
- **Thermal:**
 - > Thermal balancing
 - > Symmetrical heat loss among stacks
 - > Vessel thermal performance
- **Electrical:**
 - > Determine hot buss bar IR losses
 - > Characterize conductive gasket performance
 - > Ensure dielectric isolation of key components
- **Mechanical:**
 - > Verify high-temperature integrity of ducting and mechanical connections
 - > Validate stack compression components
 - > Validate alloy selections and differential thermal expansions




60 kW Stack Module Flow Uniformity



Cathode-Out Collector

- CFD analysis utilized during design process to achieve uniform flow distribution
- **Cold Flow** testing performed to characterize flow distribution and validate CFD models and correct issues prior to Hot Testing
- **Hot** testing verified acceptable flow variation (+0.45% to -0.35% from the mean)



Cold-Flow Test Setup



60 kW Stack Module Assembly




➔ **60 kW SOFC Module Assembly with Live Stacks is in Progress for August 2012 Test Start**



400 kW Power Plant Facility


➔ 60 kW module is planned to be tested in the existing 400 kW Power Plant Facility.



- 400 kW Power Plant Facility is equipped for testing of full scale fuel cell modules integrated in an actual system configuration:
 - Fully Automated Process Control
 - Anode & Cathode High Temperature Blowers (700 °C)
 - High Temperature Recupertors (750 °C)
 - Catalytic Oxidizer, Desulfurizers, and Reformer
 - DC-AC Inverter and Switch Gear for Utility Tie-In



60 kW PCM System Performance



System Performance Summary

SOFC Gross Power	
DC Power	70.1 kW
Energy & Water Input	
Natural Gas Fuel Flow	6.3 scfm
Fuel Energy (LHV)	103.4 kW
Water Consumption @ Full Power	0 gpm
Consumed Power	
AC Power Consumption	3.3 kW
Inverter Loss	3.2 kW
Total Parasitic Power Consumption	6.5 kW
Net Generation	
SOFC Plant Net AC Output	63.6 kW
Available Heat for CHP (to 120°F)	22.6 kW
Efficiency	
Electrical Efficiency (LHV)	61.6 %
Total CHP Efficiency (LHV) to 120°F	83.4 %

➔ PCM system is designed to lay the foundation for market entry 60 kW SOFC product operating on natural gas and biogas.



■ Introduction

- FCE SECA Program Team Members
- SECA Coal-Based SOFC Program Overview

■ Progress in SOFC Technology

- Cell Development and Manufacturing

■ Stack Development

- Scale-up and Tower Tests

■ Proof-of-Concept Module (PCM) Development

- Stack Module
- 60 kW PCM System

■ Baseline System Design and Cost Analyses

- Integrated Gasification Fuel Cell (IGFC) System Configuration
- Updated Baseline Power Plant Cost Estimate

■ Conclusion and Future Plans



Coal-Based SOFC System with Catalytic Gasification

POWER GENERATION SUMMARY

	kW	% Q input	% MW gross
Fuel Gas Expandors Gross Power @ 20 kV	49,750	7.04%	10.96%
Fuel Cell Inverter AC Gross Power @ 20 kV	362,134	51.28%	79.78%
WGPU Off Gas Expander Gross Power @ 20 kV	7,024	0.99%	1.55%
Steam Turbine Gross Power at Generator Terminals @ 20 kV,	35,019	4.96%	7.71%
Total Gross Power Generation @ 20 kV	453,927	64.27%	100.00%
Total Auxiliary Load	39,342	5.57%	8.67%
Net Power Output at 345 kV	414,585	58.70%	91.33%

Net Efficiency Excluding CO₂ Compression & Thermal Input


Coal feed, lb/h	202,980		
Coal HHV (AF), Btu/lb	11,872		
Coal Thermal Input, kWth	706,255	100.00%	155.59%
Net Plant Efficiency (HHV)	58.70%		

➔ Combined with high methane producing gasification, coal based atmospheric-pressure SOFC systems are capable of achieving ~ 59% efficiency and 99+% carbon capture.




Factory Equipment Cost Estimate


Phase I Estimate:
597 \$/kW (2002 USD)




Phase II Estimate:
372 \$/kW (2000 USD)



Phase III Estimate:
635 \$/kW (2007 USD)



- From 2002 to 2007, stainless steel prices increased 97%, Ni increased 125%, and zirconia increased 118%
- Due to cost reduction efforts, cost estimate only increased 6% (38 \$/kW) from 2002 to 2007.



Stack Cost Reduction

Cost Reduction Focus Areas

1. Stack Performance Increase


- Peak Power Increase
- Improved thermal management

2. Material Reduction:

- Thinner cells and stack components
- Interconnect material reduction
- Eliminated intermediate plates

3. Manufacturing Process Changes & Optimization

- Interconnect manufacturing development
- Improved material utilization
- Automation
- Elimination of process steps





➔ The fuel cell stack cost have decreased substantially mainly due to the R&D activities in the SECA project.



Stack Cost by Components and Category



43,008 units/per year production



- Majority of stack cost is driven by the cost of materials.
- Manufactured cell cost is < 25% of total stack cost.



■ Introduction

- FCE SECA Program Team Members
- SECA Coal-Based SOFC Program Overview

■ Progress in SOFC Technology

- Cell Development and Manufacturing

■ Stack Development

- Scale-up and Tower Tests

■ Proof-of-Concept Module (PCM) Development

- Stack Module
- 60 kW PCM System

■ Baseline System Design and Cost Analyses


- Integrated Gasification Fuel Cell (IGFC) System Configuration
- Updated Baseline Power Plant Cost Estimate

■ Conclusion and Future Plans



Summary of Key Accomplishments


- ▶ Hydrothermally stable thin anode was developed and incorporated in 3rd generation TSC cells.
- ▶ Ten 96-cell stacks with advanced TSC3 cell technology were fabricated
 - ▶ TSC3 stacks achieved a 6% performance improvement over TSC2 stacks
 - ▶ Progress observed in increasing the reliability and robustness of stacks with each stacks built.



- ▶ Stack tower suitable for large-scale SOFC modules was successfully demonstrated by achieving power output of ~30 kWdc
- ▶ Validation testing of 60 kW module non-repeat hardware successfully completed in preparation for upcoming 60kW Stack Module testing (August 2012)



SOFC Commercialization Timeline



- ▶ FCE's long-term plan is development of SOFC power plants capable of using a variety of fuels such as natural gas, biogas, and coal syngas.



Acknowledgements

- Support for FCE's SECA Coal Based Program provided by the US Department of Energy (DOE) through the co-operative agreement DE-FC26-04NT41837
- Support and guidance by the management team at NETL

Thank You!

