



# CO<sub>2</sub> Capture from IGCC Gas Streams Using the AC-ABC Process

2012 NETL CO<sub>2</sub> Capture Technology Meeting  
July 8-12, 2012 Pittsburgh, PA.

# SRI- Who We Are

*A world-leading independent R&D organization*

- Founded by Stanford in 1946
  - Non-profit corporation; became independent in 1970
  - Name changed to SRI International in 1977
- 2,100 staff members; more than 20 locations worldwide
- 2011 revenues: ~\$585 million.

## CO<sub>2</sub> Capture Programs at SRI




Pilot Unit for Capture of  
CO<sub>2</sub> from Air  
© 2012 SRI International



Advanced Carbon Sorbent Process  
Field Demonstration at U. Toledo



250 kW Chilled Ammonia Process  
Mini-pilot System



50 kW High Temperature PBI  
Membrane Skid.

# Project Overview



- **Project Participants:**
  - SRI International.
  - Bechtel Hydrocarbon Treatment Solutions, Inc.
  - EIG, Inc.
  - National Carbon Capture Center
  - U.S. Department of Energy (National Energy Technology Center)
- **Funding:**
  - U.S. Department of Energy: \$3,428,309
  - Cost Share (SRI and BHTS): \$897,660
  - Total: \$4,325,969
- **Performance Dates:**
  - September 2010 through September 2013.

# Project Objectives

- Overall objective:
  - To develop an innovative, low-cost CO<sub>2</sub> capture technology based on absorption on a high-capacity and low-cost aqueous ammoniated solution with high pressure absorber and desorber.
- Specific objectives:
  - Test the technology on a bench scale batch reactor,
  - Determine the preliminary optimum operating conditions,
  - Design and build a small pilot-scale reactor capable of continuous integrated operation,
  - Perform tests to evaluate the process in a coal gasifier environment,
  - Perform a technical and economic evaluation on the technology.


# Process Fundamentals

- Uses well-known reaction between carbon dioxide and aqueous ammonia :



- Reactions are reversible
  - Absorption reactions at lower temperature
  - Desorption reactions at higher temperature
- High pressure operation enhances absorption of  $\text{CO}_2$ .
- A similar set of reactions occur between  $\text{H}_2\text{S}$  and ammoniated solution.
- $\text{H}_2\text{S}$  from the regenerated gas is converted to elemental sulfur at high pressures.

# Process Block Flow Diagram



# Process Highlights

- Concentrated ammoniated solution is used to capture CO<sub>2</sub> and H<sub>2</sub>S from syngas at high pressure.
- Absorber operation at 40°-60° C temperature; No refrigeration is needed.
- CO<sub>2</sub> is released at high pressures (40 bar) at <200°C:
  - The size of CO<sub>2</sub> stripper, the number of stages of CO<sub>2</sub> compression, and the electric power for compression of CO<sub>2</sub> to the pipeline pressure are reduced.
- High net CO<sub>2</sub> loading, up to 20% by weight.
- The stripper off-gas stream, containing primarily CO<sub>2</sub> and H<sub>2</sub>S, is treated in the BPSC process to remove the sulfur

# Process Advantages

- Low cost and readily available reagent (aqueous ammonia).
- Reagent is chemically stable under the operating conditions.
  - Ammonia does not decompose under the operating conditions.
- High efficiency for CO<sub>2</sub> capture
  - Reduces water-gas shift requirements - Reduced steam consumption.
- No loss of CO<sub>2</sub> during sulfur recovery
  - High pressure conversion; No tail gas treatment
- Low heat consumption for CO<sub>2</sub> stripping (<600 Btu/lb CO<sub>2</sub>).
- Extremely low solubility of H<sub>2</sub>, CO and CH<sub>4</sub> in absorber solution
  - Minimizes losses of fuel species.
- Absorber and regenerator can operate at similar pressure.
  - No need to pump solution cross pressure boundaries. Low energy consumption for pumping.
- Process can be applied to existing and new IGCC power plants.



# Project Tasks

## Task 1: Bench-scale Batch Tests:

Results were presented at 2011 NETL Carbon Capture Technology Conference

## Task 2: Pilot-Scale Integrated, Continuous Tests


Focus of the current effort (July 2012 through September 2013)

## Task 3: Project Management

# Project Schedule

Task	Activity	Month From the Start														
		FY10			FY11					FY 12				FY13		
		3	6	9	12	15	18	21	24	27	30	33	36	39	42	
<b>Task 1</b>	Bench Scale Testing	[Blue bar from month 3 to 18]														
1.1	Batch test Unit Construction	[Blue bar from month 3 to 4]														
1.2	Test Plans	[Blue bar from month 4 to 5]														
1.3	Absorber Tests	[Blue bar from month 6 to 7]														
1.4	Regenerator Tests	[Blue bar from month 9 to 10]														
1.5	Bench-Scale Test Data Analysis	[Blue bar from month 12 to 13]														
1.6	Preliminary Process Modeling	[Blue bar from month 15 to 16]														
1.7	Preliminary Economic Analysis	[Blue bar from month 18 to 19]														
	Continuation Application Review	[Blue bar from month 21 to 27]														
<b>Task 2</b>	Pilot-Scale Continuous, Integrated Tests	[Orange bar from month 30 to 42]														
2.1	Design of the Pilot-Scale Continuous, Integrated Test System	[Orange bar from month 30 to 31]														
2.2	Construction of the Pilot-Scale Integrated Test System	[Orange bar from month 33 to 34]														
2.3	Pilot Scale Test Plans	[Orange bar from month 36 to 37]														
2.4	Pilot-Scale Tests	[Orange bar from month 39 to 42]														
2.5	Process Modeling	[Orange bar from month 40 to 41]														
2.6	Economic Analysis	[Orange bar from month 41 to 42]														
3	Project Management and Planning	[Blue bar from month 3 to 27]														

# Bench-Scale Regenerator Testing




T: 100 - 170 C

P: 10-40 bar


Feed CO<sub>2</sub> Loading: 10-20 wt%

# CO<sub>2</sub> Capture Efficiency vs Solution Composition


CO<sub>2</sub> Capture Efficiency Exceeds 90%




# No Significant Decrease in the Rate of Absorption at Elevated Temperatures




# Rapid Rate of Reactions Approaching Equilibrium



# High Efficiency of H<sub>2</sub>S Capture




# Measured CO<sub>2</sub> Attainable Pressure Function of Temperature






# High Levels of Solvent Regeneration at Moderate Temperatures



Target R Value: >4


# Technical and Economic Analysis

- Compare the AC-ABC process with a similar-size plant using CO<sub>2</sub> capture with Selexol subsystem.
- Base case is an IGCC plant (750 MW nominal) with no CO<sub>2</sub> capture.
- Generate the equipment sizing, heat and material flows using Aspen and GT-Pro modeling .
- Use DOE spread sheet to generate cost.




Process Energy Requirements: CO<sub>2</sub> stripping, solution pumping, and CO<sub>2</sub> compression

# Bechtel High-Pressure Claus Process



# AC-ABC and BPSC Process Changes to IGCC Reference Case





# DOE Economic Analysis

Presented at 11<sup>th</sup> Annual Conference on CCUS

Economic Analysis (June 2011\$)	IGCC with SRI AC-ABC and BPSC	Reference Case
Total Plant Cost, before Owner's Costs, million	\$1,676	\$1,785
Total Plant Cost, before Owner's Costs	\$2,962/kW	\$3,286/kW
Initial Chemical Fill Cost, million	\$4.3	\$15.9
Annual Fixed O&M Cost, million	\$64.5	\$68.0
Annual Variable O&M Cost, million	\$42.4	\$45.9
Total Annual O&M Cost, million	\$106.9	\$113.9
FY COE* without TS&M**	\$108.28	\$118.85
FY COE with TS&M	\$113.33	\$124.04

\*FY COE = First Year Cost of Electricity

\*\*TS&M = Transport, Storage, and Monitoring

# Plant Performance Summary

*DOE Presentation at 11<sup>th</sup> Annual Conference on CCUS*

Plant Performance	Units	IGCC with SRI AC-ABC and BPSC	Reference Case
Gas Turbine Power	MWe	464.0	464.0
Syngas Expander Power	MWe	5.7	6.5
Steam Turbine Power	MWe	246.2	263.5
Auxiliary Load	MWe	150.0	190.8
Net Plant Power	MWe	565.9	543.3
Net Plant Efficiency (HHV)	-	33.7%	32.6%
Net Plant Heat Rate (HHV)	kJ/kWh	10,679	11,034
	Btu/kWh	10,122	10,458

# Anticipated Benefits, if Successful

- We estimate a 22.7 MW improvement in Net Plant Power and a 1.1 percentage point increase in Net Plant Efficiency (HHV basis) than a reference plant (GE gasifier with Selexol AGR and conventional Claus).
- The capital cost is ~6% less expensive than the reference plant on an absolute basis.
- The COE is 9% lower for the SRI AC-ABC and BPSC plant relative to the reference case.
- The process configuration is economically viable per this analysis.
- The project will be tested in this Budget Period in an operating gasifier environment that will lead to further system improvements.



# Acknowledgement

- SRI International
  - Gopala Krishnan – Associate Director (MRL) and Principal Investigator
  - Indira Jayaweera, Jordi Perez, Anoop Nagar, Daniel Steel and Esperanza Alavarez
  - Angel Sanjurjo – Materials Research Laboratory Director and Project Supervisor
- EIG: Eli Gal
- Bechtel Hydrocarbon Treatment Solutions:
  - Lee Schmoe and Martin Taylor
- National Carbon Capture Center: Frank Morton and Tony Wu
- DOE-NETL
  - Elaine Everett, Megan Napoli, Susan Maley, Jenny Tennent, James Black, Peter Kabateck

# Thank You



*Headquarters: Silicon Valley*

**SRI International**

333 Ravenswood Avenue  
Menlo Park, CA 94025-3493  
650.859.2000

*Washington, D.C.*

**SRI International**

1100 Wilson Blvd., Suite 2800  
Arlington, VA 22209-3915  
703.524.2053

*Princeton, New Jersey*

**SRI International Sarnoff**

201 Washington Road  
Princeton, NJ 08540  
609.734.2553

*Additional U.S. and  
international locations*

**[www.sri.com](http://www.sri.com)**