

# Radiocarbon as a Reactive Tracer for Tracking Permanent CO<sub>2</sub> Storage in Basaltic Rocks

DE-FE0004847

Jennifer Hall

Columbia University in the City of New  
York

---

U.S. Department of Energy  
National Energy Technology Laboratory  
Carbon Storage R&D Project Review Meeting  
Developing the Technologies and Building the  
Infrastructure for CO<sub>2</sub> Storage  
August 21-23, 2012

# Presentation Outline

---

- Benefit to the Program
- Project Overview
- Technical Status
- Conservative and Reactive Tracer Techniques
- Accomplishments to Date
- Summary

# Benefit to the Program

---

- The goal of the project is to develop and test novel geochemical tracer techniques for quantitative monitoring, verification and accounting of stored CO<sub>2</sub>. These techniques contribute to the Carbon Storage Program's effort of ensuring 99% storage permanence.

# Benefit to the Program cont.

---

- This research project is developing and testing the feasibility of carbon-14 ( $^{14}\text{C}$ ) as a reactive tracer for quantitative monitoring and accounting of geological  $\text{CO}_2$  storage. None of the currently applied  $\text{CO}_2$  monitoring approaches are able to provide a surveying tool for **dissolved** or **chemically transformed**  $\text{CO}_2$ . The technology, when successfully demonstrated, will provide an improvement over current monitoring practices. This technology contributes to the Carbon Storage Program's effort of ensuring 99%  $\text{CO}_2$  storage permanence in the injection zone.

# Project Overview:

## Goals and Objectives

---

- Testing carbon-14 ( $^{14}\text{C}$ ) as a reactive tracer for geochemical reactions (including mineral carbonation) caused by  $\text{CO}_2$  injection at the CarbFix pilot injection site, Iceland.
- Monitor subsurface  $\text{CO}_2$  transport with trifluormethylsulphur pentafluoride ( $\text{SF}_5\text{CF}_3$ ) and sulfurhexafluoride ( $\text{SF}_6$ ).
- Drilling small diameter coreholes into injection zone for mineral carbonation study on core samples.
- Quantify the extent of mineral carbonation in the CarbFix basalt  $\text{CO}_2$  storage reservoir.
- This research leads to advanced monitoring and accounting of geologic  $\text{CO}_2$  storage.

# Project Overview:

## Success criteria

---

- Complete collection and analysis of fluid and gas samples for  $^{14}\text{C}$  and  $\delta^{13}\text{C}_{\text{DIC}}$  analysis under reservoir conditions in the injection and monitoring wells.
- Complete collection and analysis of fluid and gas samples for  $\text{SF}_5\text{CF}_3$  and  $\text{SF}_6$  analysis under reservoir conditions in the injection and monitoring wells.
- Complete set of breakthrough curves established for monitoring wells.
- Successful drilling of small diameter wells and core recovery at injection reservoir depth with wireline coring.
- Complete quantitative characterization of  $\text{CO}_2$ -rock reactions caused by  $\text{CO}_2$  injection. Determination of in situ mineralization rates.

# Technical Status – CarbFix Project



- In situ CO<sub>2</sub> mineralization in basaltic rocks
- Advanced monitoring, verification and accounting of stored CO<sub>2</sub>

Target zone for CO<sub>2</sub> sequestration identified at 400-800 m depth

Groundwater

Gas injected fully dissolved in water into target zone

2 kg/s of CO<sub>2</sub> from Condensers  
0.07 kg/s 2.2 thousand tons per year

800 kg/s of steam, gas and water from deep and hot (>240 °C) geothermal wells

Hellisheidi geothermal power plant



# CarbFix Partners

---

- Orkuveita Reykjavíkur (Reykjavik Energy), Iceland
- University of Iceland, Iceland
- CNRS, University of Toulouse, France
- Columbia University, New York, USA

# Injection Phases

---


## **Phase I**

pure CO<sub>2</sub> injection of ~200 tons  
(January 2012- March 2012)


## **Phase II**

CO<sub>2</sub>+H<sub>2</sub>S injection (80% CO<sub>2</sub>, 20% H<sub>2</sub>S)  
1800 tons of CO<sub>2</sub>,  
(June 2012 – ?)

# Injection Process




# Monitoring/Verification Approach



## LEGEND



# Monitoring/Verification Infrastructure



# SF<sub>6</sub> Monitoring Results

- Goal: Monitor advective and dispersive transport of injected solution
- Labeling injected CO<sub>2</sub> with SF<sub>6</sub> in Phase I
- Breakthrough curve at HN4 initial peak after 63 days
- Decrease in concentration for a further 38 days
- Continue to monitor SF<sub>6</sub> throughout and beyond Phase II
- No SF<sub>6</sub> at HK-34 or other wells
- Sample analysis with gas chromatography


# SF<sub>6</sub> Monitoring Results cont.



# Carbon-14 Monitoring

- Goal: distinguish stored CO<sub>2</sub> from natural CO<sub>2</sub> sources

- Labeling injected CO<sub>2</sub> with carbon isotopic tracer:




- NaH<sup>14</sup>CO<sub>3</sub> stock solution for labeling with an <sup>14</sup>C activity of 20 mCi (7.4x10<sup>8</sup> Bq) for 12 months injection
- <sup>14</sup>C activity in injected CO<sub>2</sub> saturated solution is 320 PicoCi/L (12 Bq/L)
- Sample analysis with accelerator mass spectrometry



# Carbon-14 Monitoring


HN4 monitoring well during pure CO<sub>2</sub> injection



- Input concentration of <sup>14</sup>C tracer in the injection well was 6 x too high due to a malfunction of the tracer input microprocessor pump.
- <sup>14</sup>C in fraction modern in HN4 monitoring well is 2 x too high.
- Tracer microprocessor pump was replaced and successful <sup>14</sup>C labeling is ongoing.

# $\delta^{13}\text{C}$ Monitoring

HN4 monitoring well during pure  $\text{CO}_2$  injection



- Trend to less negative  $\delta^{13}\text{C}$  values indicate  $\text{CO}_2$ -rock reactions (calcite dissolution)
- We need more geochemical data from the injection and monitoring wells to quantify the degree of these reactions.

# Accomplishments to Date

---

- Tracer injection and monitoring infrastructure including monitoring plan established.
- Pure CO<sub>2</sub> injection completed.
- Continuous sampling in injection and monitoring wells for tracer analysis was initiated.
- First set of gas and fluid samples for SF<sub>6</sub>, <sup>14</sup>C and δ<sup>13</sup>C analysis collected and analyzed.
- CO<sub>2</sub> + H<sub>2</sub>S injection was initiated.
- Monitoring the CO<sub>2</sub> + H<sub>2</sub>S injection with SF<sub>5</sub>CF<sub>3</sub>, <sup>14</sup>C and δ<sup>13</sup>C was initiated.
- The developed technology has the capability to detect and quantify in situ geochemical reactions (see tracer breakthrough curves).


# Summary

---

- Currently injecting gas from the power plant
- Successful and ongoing collection and analysis of tracer samples
- Observed breakthrough curves
- Identified that reactions are occurring
- Next Steps:
  - Continuation of Phase II injection
  - Continuation monitoring through  $\text{SF}_6$ ,  $\text{SF}_5\text{CF}_3$ ,  $^{14}\text{C}$  and  $\delta^{13}\text{C}$  analysis
  - Plan drilling of well for core samples
  - Quantify  $\text{CO}_2$ -water-rock reactions

# Appendix

## Organization Chart



# Gantt Chart

Tasks	BP I					BP II				BP III			
	Qt1	Qt2	Qt3	Qt4	Qtr5	Qt1	Qt2	Qt3	Qt4	Qt1	Qt2	Qt3	Qt4
<b>Task 1.0 Project Management, Planning and Reporting</b>													
<b>Task 2.0 Monitoring the CO<sub>2</sub> movement with SF<sub>5</sub>CF<sub>3</sub> in the basalt formation</b>							E						
Subtask 2.1 Monitoring the SF <sub>5</sub> CF <sub>3</sub> concentration in target injection interval and overlying shallow aquifer		A						F		I			
Subtask 2.2 SF <sub>5</sub> CF <sub>3</sub> Data Analysis			C					G		I			
<b>Task 3.0 Monitoring of geochemical reactions and in situ mineral carbonation with <sup>14</sup>C</b>							E						
Subtask 3.1 Monitoring the <sup>14</sup> C concentration in target injection interval and overlying shallow aquifer			B					F		I			
Subtask 3.2 Carbon-14 and d <sup>13</sup> C Analysis					D			G		I			
<b>Task 4.0 Mineral carbonation studies on core samples</b>													
Subtask 4.1 Wireline core drilling										J			
Subtask 4.1.1 Drilling plan								H					
Subtask 4.1.2 Drilling and coring													
Subtask 4.2 Mineralogical and geochemical analysis of core samples												K	
<b>Task 5.0 Quantification of mineral carbonation in the CarbFix basalt storage reservoir</b>												L	

Major milestones: bold capital letters