Characterization of Pliocene and Miocene Formations in the Wilmington Graben, Offshore Los Angeles, for Large-Scale Geologic Storage of CO<sub>2</sub> Project Number (FE0001922)

> Michael Bruno, PhD, PE GeoMechanics Technologies



U.S. Department of Energy National Energy Technology Laboratory Carbon Storage R&D Project Review Meeting Developing the Technologies and Infrastructure for CCS August 20-22, 2013

# **Background and Motivation**

- The Los Angeles Basin provides a unique combination of significant need and significant opportunity for large scale CO2 sequestration
- Has numerous large power plants & oil refineries which produce more than 5 million MT of fossil fuel related CO2 emissions each year
- Prolific oil & gas producing basin with thick sediments (several billion barrel fields)





# **Background and Motivation**

- Precedent and history for large scale injection (>3000 injection wells)
- Precedent and history for large scale gas storage (5 fields)

• But, siting large scale CO2 storage beneath a highly populated area is technically and politically impractical



#### Oil Fields in LA Basin



### **Background and Motivation**

The offshore Wilmington Graben presents significant advantages, including:

• Geologically isolated, yet accessible from onshore with existing oil and gas infrastructure;

 Very thick sediments nearly identical to those located onshore;

• Fewer existing wells to reduce leakage risk (11 wells).





# Goal and Objective

- The objective of this research project is to fully characterize Pliocene and Miocene sediments in the Wilmington Graben, offshore Los Angeles, for high volume CO2 storage, to evaluate risks, and to evaluate logistics for transport from local sources
  - The effort contributes to the Carbon Storage Program's goal to develop technologies to predict CO2 storage capacity in geologic formations to within 30%.
  - The effort also contributes to the Program's goal to develop technologies to demonstrate 99% of injected CO2 remains within the injection zones.
- One key goal is to confirm CO2 storage capacity in the Wilmington Graben exceeds 100 million metric tons.
  - Contributes to the understanding of injectivity, containment mechanisms, and storage capacity of the Wilmington Graben for large scale CO2 sequestration.
  - One of only two projects focused on offshore storage formations. Only project focused on turbidite geologic settings (common in Western US).



# Benefits to the Program

- This project is contributing to the understanding of injectivity, containment mechanisms, and storage capacity of the Wilmington Graben basin.
- Broadens the experimental knowledge base of best practices for site characterization and approving storage site selection with the ultimate goal of developing practical guidelines for future commercially developed CO<sub>2</sub> storage sites.
- This effort contributes to the Carbon Storage Program's effort of conducting field tests to support the development of Best Practices for site selection, characterization, and operations.
- Unique evaluation of offshore storage in a turbidite geologic setting



# **Project Team and Participants**

**California Energy Commission** 

#### DOE NETL









Legg Geophysics (seismic interpretation) Don Clarke (geologic evaluation and modeling)



USGS, Dr. Dan Ponti (cores and samples repository)

City of Los Angeles, Department of Public Works

Southern California Gas Company (transport infrastructure)

Cal State Long Beach, Dr. Dan Francis (seismic acquisition)

**GeoMechanics Technologies (geology, geomechanics, reservoir engineering and drilling contract management)** 



#### **Team Contributions**

- Partnership with the City of LA (Renewable Energy Project) provided drilling site and existing EPA drilling permit in the North Wilmington Graben, expediting drilling DOE#1.
- Partnership with USGS provides a repository for all the cores and drill cutting samples
- Partnership with California State University, Long Beach provided seismic surveying capability and interest in better understanding the Palos Verdes Fault system
- Don Clarke and Mark Legg are the top geology and geophysics experts on Wilmington Area
- Beta Offshore operating and exploring on offshore edge of Graben, providing cost share for DOE#3
- GeoMechanics Technologies has successfully managed about 10 DOE projects over 15 years. We hold a drilling contractors license and are experienced and active in gas storage engineering and injection operations



## Work Plan: Scope of Work

- 1) Detailed log evaluation of existing exploration wells in the area
- 2) Improved evaluation and interpretation of existing 2D and 3D seismic data plus new seismic data acquisition within a "data gap" area
- 3) Drilling and coring three new evaluation wells into the Graben (Pliocene and Miocene)
- Development of 3D geologic models, geomechanical models, and CO<sub>2</sub> injection and migration models for the region – update with data from new DOE wells
- 5) Analysis of top 20 industrial sources in the LA Basin
- 6) Transport Infrastructure Study: engineering study of existing and new pipeline systems to transport CO<sub>2</sub> from significant local sources to sequestration sites
- 7) Risk analysis



## Project Status Accomplishments to date

- Detailed log evaluation of existing exploration wells in the area
- Improved evaluation and interpretation of existing 2D and 3D seismic data
- Acquisition and interpretation of additional 2D seismic lines
- DOE#1 (onshore Pliocene) well drilled and analyzed, DOE#2 (onshore Miocene) state permit approved July 31, 2013, w drilling planned for 4<sup>th</sup> qtr 2013, DOE#3 (offshore Miocene) BSEE permit submitted, with approval expected in September 2013, and drilling planned for 1<sup>st</sup> qtr, 2014.
- Complete initial development of 3D geologic models, geomechanical and CO<sub>2</sub> injection and migration models. Currently revising and improving based on Peer Review recommendations.
- Completed analysis of top 20 industrial sources in the LA Basin and transportation infrastructure. Developed interactive map/atlas (www.socalcarb.org)
- Risk analysis. 60% completed



#### Long Beach



1.300.000

320.00

Collect log data from about 12 exploration wells located in State and Federal waters

Evaluate sand, silty-sand, and shale sequences

Combine into common database

Supplement with 3 new wells





Easting (ft)

1 280 00

1 260 00

#### Seismic Data Analysis and Acquisition

Collect new seismic data in "gap area"

Combine and reinterpret existing data

Establish horizons for 3D geologic model





### Seismic Data Analysis and Acquisition

New seismic data collected over 175km of lines inside and outside breakwater, with ties to previous data





Shot Point Map for 175km of new seismic lines

CA State Long Beach Seismic Acquisition Boat



#### Seismic Data Analysis and Acquisition

Top Miocene structure map





## Top Basement structure map





### New well drilling, logging, core analysis

•DOE#1 well drilled to a depth of 5400ft, penetrating to near base of Pliocene

•200 ft of viable Pliocene age storage formation and 500 ft of caprock identified

•Sand porosity 24-31%, permeability 50-353 md.

•Shale porosity 23-29%, permeability <2 md

•DOE#2 well permit application approved 7/31/13

•DOE#3 permit application submitted to BSEE 6/21/13



DOE#1 well



#### New well drilling, logging, core analysis

Formation evaluation data from new wells used to update geologic, geomechanical and gas migration models.

**Results for well 1:** 

•200 ft of viable Pliocene age storage formation and 500 ft of caprock identified

•Sand porosity 24-31%, permeability 50-353 md.

•Shale porosity 23-29%, permeability <2 md







### 3D Geologic Model Development

Using acquired seismic data, well log data, assembled a 3D geologic earth model

Four lithology types: sand, sand-shale, silt, shale

Apply geologic model to:

- 1. Estimate storage capacity
- 2. Develop geomechanical model and simulation
- 3. Develop CO2 injection and migration model and simulation





Geologic Model of Wilmington-Graben





GeoMechanics Technologies

#### **NW-SE Cross Section**



Red line: Top Repetto Unconformity

#### **Preliminary Storage Capacity**

Apply geologic model to:

- 1. Estimate storage capacity
- 2. Develop geomechanical model and simulation
- 3. Develop CO2 injection and migration model and simulation

Preliminary minimum storage capacity estimate is 258 million MT for the Pliocene and 177 million MT for the Miocene

Miocene estimates to be improved with new well data





#### New Extends of Tough2 Model Area

Focus on center of Graben

3D model 20,000 x 20,000ft

Apply TOUGH2/ECO2N, use Shell\_OCS\_P293-1 as injection well over an interval of 150m





#### Comparison between Porosity Log & Core Porosity







#### **Reservoir Layering for Simulation Model**



#### Porosity and Permeability Correlation

#### Porosity – permeability correlation

#### Core samples available (NOTE small # of samples for entire Graben available!)

Available data at well:	Confining pressure (PSI)	# of sand	# of shale	# of silt	# of sand/shale
SFI01	300	5	1	0	0
SFI02	400	6	0	0	0
SFI02	1500	6	0	0	0
SFI03	250	14	6	0	5
others	n/a	Not used	Not used	Not used	23

Kozeny-Carman equations established using best fit between  $perm_{meas}$  and  $porosity_{meas}$  term:

Sand:

Shale:

Sand/Shale interbed:

Silt:



$$\begin{split} & \text{Perm}_{\text{sand}}(\text{mD}) = 9408 \ \text{*n^3} \\ & \text{Perm}_{\text{shale}} \ (\text{mD}) = 71.044 \text{*n^2/(1-n)^2} \\ & \text{Perm}_{\text{sa/sh}} \ (\text{mD}) = 367 \text{*n^2/(1-n)^2} \\ & \text{Perm}_{\text{silt}}(\text{mD}) = 9408 \ \text{*n^3} \end{split}$$



#### Revised Lithology with Heterogeneity Modeled

Heterogeneity modeled in RW, mapped to Tough2 model

Injection cell size: 6m3

Multiple characterizations for alternative risk scenarios





### 3D Geomechanical Model Development

**Develop Geomechanical Model to assess:** 

- 1. Induced seafloor deformations
- 2. Induced stresses
- 3. Fault activation risks

Apply FLAC3D code for two areas in the Graben (north and central)





#### Vertical displacement at seafloor



Develop Geomechanical Model to assess:

- 1. Induced seafloor deformations
- 2. Induced stresses
- 3. Fault activation risks

Apply FLAC3D code for two areas in the Graben (north and central)



### **Risk Analysis and Practical Logistics**

#### **Risk Assessment Includes:**

- Lateral Migration to Poorly Cemented Offset Wells
  - Detailed well record review
  - Reservoir scale fluid and migration modeling
- •Injection Well Failure and Transmission
  - Stress analysis, near-well migration modeling
- Caprock Integrity Study
  - Geomechanical analysis of fracture and fault activation risk
- Natural Seismicity Risks
  - Historical review of impacts on O&G and Gas Storage operations
- Induced Seismicity Risks
  - > Analog review, geomechanical analysis, microseismic monitoring
- CO2 Migration to Sea Floor
  - Analog review, rate assessment, and biologic impact estimate



### **Risk Analysis and Practical Logistics**

#### Logistics Evaluation Includes:

- 1. Identify and characterize top 20 sources in LA Basin
  - Include on Interactive Google Earth Map
  - Contribute to NATCARB Atlas and Database
- 2. Evaluate pipeline and storage field infrastructure in LA Basin
  - Location and design of existing oil and gas lines
  - Location of existing storage fields
  - Requirements for transport from major sources to Graben area
  - Typical design and cost for CO2 transmission lines



#### Search Fly To Find Businesses Directions Fly to e.g., Hotels near JFK - Q Places My Places Sightseeing Tour Make sure 3D Buildings layer is checked Sections.kmz Main Group Faults.kmz Temporary Places Sources With Names.kmz

SoCalCarb.kmz

Sinks With Pore Volume.kmz





# Next Step

- Drill and complete DOE#2 and DOE#3 wells
- Establish revised material properties for the different lithologies, based on revised porosity data and permeability estimation and rerun gas migration modeling
- Rerun geomechanical modeling using revised material properties
- Complete risk assessment and documentation



#### Challenges Permitting 3 wells for Wilmington Graben

Dealing with multiple locations (city, state lands, and federal waters) diverse organizations, and regulations:

- City of Los Angeles
- US EPA
- State Division of Oil and Gas and Geothermal Resources
- BSEE
- CEQA compliance (state implementation of NEPA)
- DOE#1 : Onshore well, CLA partner, permitted by EPA
- DOE# 2 : Onshore well, CLA partner, permitted by DOGGR and EPA
- DOE#3 : Offshore well, BOC partner, permitted by BSEE



## Summary

- Significant Accomplishments
  - DOE#1 well drilled and completed
  - 175km of new seismic acquired, analyzed, and interpreted
  - 3D Geologic Model developed for entire graben
  - Interactive map of sources, sinks, pipeline completed
- Key Findings
  - About 500 million metric tons storage capacity available (at ~ 3% saturation); Not all accessible due to offset wells, Additional deep capacity likely
  - Injection pressures remain less than 1.1 x initial reservoir pressure if injection limited to 250,000 MT/Y per well
  - CO2 gas plume migrates 1000m horizontally and 350m vertically after 5 years of injection and 50 years of observation if injection limited to 150m interval.



# Appendix

These slides will not be discussed during the presentation, but are mandatory



# **Organization Chart**

- Principal Investigator
  - Dr. Mike Bruno
- Project Manager & Sr Geologist
  - Jean Young
- Sr Research Engineer
  - Julia Diessl
  - Kang Lao
  - Claudia Gruber
- Research Engineer
  - Jing Xiang
- Research Geologist
  - Nicky White
  - Bill Childers



- Contractors
  - Dr. Mark Legg
  - Dr. Dan Francis
  - Don Clarke
  - Drilling crew
  - Logging crew
- Partners
  - City of Los Angeles
  - California Energy Commission
  - CA State University, Long Beach
  - USGS

## Gantt Chart

•	last harne	
	Task 1. Project Mgmt & Planning	
T	1.1 Kickoff mtgs and planning discussions w/ DOE	
ГÌ	Document links between project and RCSPs and	
-1	1.2 RCSP and NATCARB Coordination and Data Sharing	
- 1	1.3 Project Management and Oversight	
- 1	1.4 Coordinate, communication, participation w/CEC	
-i	Updated Project Management Plan	
- 1	Submit Site Characterization Plan	
-	Task 2. Seismic Data Analysis and Interpretation	
- 1	2.1 Existing 2D/3D Data Processing and Analysis	
- 1	2.2 New Data Acquisition	
-	2.3 Analysis and interpretation	
-	Seismic Data Analyzed and Interpretated	• • • • • • • • • • • • • • • • • • •
-	Task 3. Well Data Review and Formation Evaluation	
-	3.1 Data sharing & collaboration /USGS and CSLB	45 hrs
-	Notification to Project Manager that reservoir data	
	collection has been initiated	
• 1	3.2 Existing offshore well data assembly and review	
- 1	3.3 Tie-in to seismic data and Wilmington field data	
- i	3.4 Analysis and Interpretation	
• 1	3.5 Quantify Pliocene and Miocene targets and seals	
- 1	3.6 Additional wells & saline fms evaluation surrounding	
	Wilmington Graben	
•	Well Data Reviewed and Formation Evaluated	
"	Task 4. New well drilling, logging, and core analysis	
"	DOE#1 well completed	• #14
"	Preliminary Estimate of Storage Vollume, Seals Risks:	• 59
_	GO-NO-GO decision point 4.6 DOE#2 well design and drilling contractor selection	
_		
~	Notification to Project Manager that subcontractors have been identified for drilling/field service operations	
-	Notification to Project Manager that field service	
	operations have begun at the project site	l l l l l l l l l l l l l l l l l l l
-	4.7 Drill, log and core DOE#2 well (engineering oversight)	1 1 1 1 1
- 1	Notification to Project Manager that characterization wells have	
-	4.8 DOE#2 well Log analysis and Core analysis	
•	Notification to Project Manager that well logging has	
	been completed	
"	4.9 DOE#2 well injection testing and interpretation	
-	4.9.1 Comprehensive fluid and gas sampling and analysis	
° į	4.10 Update geologic interpretation with DOE#2 well data	
۳j	4.11 Depth Extension to DOE#2 well to identify more CO2	
	storage capacity	
•	DOE#2 well done	
• ]	4.12 DOE#3 well design and drilling contractor selection	
٦	Notification to Project Manager that subcontractors have been identified for drilling/field service operations	
_		
	DE-FOA-0000003 2010 db 05 Task Progress	Summery Description Creating 3

## Gantt Chart

Ð	Task Name	2010	2011	8212	2013	2014
1	Task 1. Project Mgmt & Planning					
2	1.1 Kickoff mtgs and planning discussions w/ DOE				i (	
- 2	Document links between project and RCSPs and				1	
4	1.2 RCSP and NATCARB Coordination and Data Sharing	-1 <sup></sup>				
5	1.3 Project Management and Oversight					1
	1.4 Coordinate, communication, participation w/CEC	-			1	1
	Updated Project Management Plan			i .		i.
18	Submit Site Characterization Plan	- ×	ľ	ľ	ři	ľ
17	Task 2. Seismic Data Analysis and Interpretation				1 1	1
-10	2.1 Existing 2D/3D Data Processing and Analysis		•		1 1	1
19	2.2 New Data Acquisition	- <u> 1</u>		İ	i i	i
20	2.3 Analysis and interpretation	- <u>-</u>			1 1	1
21	Seismic Data Analyzed and Interpretated	-	◆ 521		1 1	
22	Task 3. Well Data Review and Formation Evaluation	-	<b>•</b> ••••	i	<u>i i</u>	i
23	3.1 Data sharing & collaboration /USGS and CSLB	40 hrs				
24	Notification to Project Manager that reservoir data				i i	i
1	collection has been initiated	1 T'	1	1		1
25	3.2 Existing offshore well data assembly and review	1 📥 🛛			1 1	
28	3.3 Tie-in to seismic data and Wilmington field data		1	i i	i i	i
20	3.4 Analysis and Interpretation	1			1 1	1
28	3.5 Quantify Pliocene and Miocene targets and seals	1				
25	3.6 Additional wells & saline fms evaluation surrounding	1			i	
	Wilmington Graben		1		1	1
30	Well Data Reviewed and Formation Evaluated				1 1	-
31	Task 4. New well drilling, logging, and core analysis	,			÷	
30	DOE#1 well completed	@ 1014			1 1	
	Preliminary Estimate of Storage Vollume, Seals Risks:		+ 1/B		1 1	1
- 28	GO-NO-GO decision point 4.6 DOE#2 well design and drilling contractor selection	-			1 1	1
36	Notification to Project Manager that subcontractors have	_			- <b>-</b> }	
	been identified for drilling/field service operations				i (****)	i
30	Notification to Project Manager that field service	-			! ! <b>i</b>	
	operations have begun at the project site				1 1	
- 24	4.7 Drill, log and core DOE#2 well (engineering oversight)	1			i i 4	<b>,</b> i
38	Notification to Project Manager that characterization wells have	1				6 1070
39	4.8 DOE#2 well Log analysis and Core analysis	1			1 1	
•	Notification to Project Manager that well logging has	1		1	1	
	been completed			1		
-	4.9 DOE#2 well injection testing and interpretation	_			i i	
~	4.9.1 Comprehensive fluid and gas sampling and analysis					
-	4.10 Update geologic interpretation with DOE#2 well data	_				
-44	4.11 Depth Extension to DOE#2 well to identify more CO2	1	i i	İ	i i =	a ii
-	storage capacity DOE#2 well done	-1			1	1 I
-	4.12 DOE#3 well design and drilling contractor selection	-1				* <sup>5</sup> n
	4.12 DOE#3 well design and drilling contractor selection	1		1	i i	ř,
*	Notification to Project Manager that subcontractors have been	1				
$\vdash$	identified for drilling/field service operations				1	
Deale	at DE-FOA-0000033_2010_08_05 Task Progress	Summery C	External Tasks Canadime	0		
Date	tr De FCAR-DOUBDIDE_2010_DB_05 Mileatone	Project Summary U	External Milestone @	-		
	•		Page 1			

## Gantt Chart

8	ack Name	2000				2011			2112			1.00	÷				2014	
	8.6 Detailed Engineering Review and Analysis of Existing and New Pipeline and Gas Storage System in LA Basin Final Risk Assessment and Characterization	Γ	 22	628					0		1 (3							
	Task 9. Project Documentation and Reporting	⊢			_							-					<u> </u>	d 600
-	9.1 Quarterly and Annual Reports						Ε.			E	3	- Þ.			1	•	<u>ب</u> با	
1.0	9.2 Best Practices Manual Development 9.3 Technical Workshop Participation														1 - I		i	
	9.4 DOE mtgs and presentations	1					7					٦.		5		- 0	<b>.</b> .	
120	Notification to Project Manager that activities on the	I –		-		F I	-				-	- [		_	1		[	-
121	lessons learned document on site characterization have 9.5 Final Report and Lessons Learned	1			į			i				- i			į –		i i	
122	Final document submitted																1	

Project: DE-RCA-0008033_2010_08_05 Date: Web 7/31/13	Task         Progess         Summary         External Tasks         Deadline
	Page 1