


# Evaluation of Solid Sorbents as a Retrofit Technology for CO<sub>2</sub> Capture

July 8, 2013 ADA-ES, Inc. DE-FE0004343

### Advanced Emissions Solutions, Inc.







### CO<sub>2</sub> Project Funding and Goals

- The overall objective of this funding stage is to validate solid sorbent-based post combustion CO<sub>2</sub> capture through slipstream pilot testing.
- Project Goals:
  - Achieve 90% CO<sub>2</sub> Capture
  - Reduce costs of carbon capture
     Progress towards <35% LCOE Goal</li>
  - Generate a high purity CO<sub>2</sub> stream
  - Successfully scale sorbents



\$15,000,000

\$5,500,000

Cooperative Agreement (Award No. DEFE0004343)

American Recovery and Reinvestment Act of 2009

Administered by DOE-NETL: Project Manager Bruce Lani



# Project Budget Period Overview

Phase I: 18 months

- 500 MW Concept and Sorbent Selection
- Design 1 MW pilot

Scale down to 1 MW

Oct '10 - Mar '12

Manufacture and Construction

- Manufacture Sorbents
- Fabricate and Install 1 MW pilot

Phase III: 15 months

- 1 MW Testing
- Develop 500 MW Preliminary Design
- Conduct Technoeconomic analysis

Demonstration Phase

Phase II: 18 months

Apr '12 - Sep '13

Oct '13 - Dec '14

# Project Team



• DOE - NETL

- o Project Sponsor
- ADA-ES, Inc.



- Project Management
- o Developed Process Concept
- Sorbent Eval & Selection
- Process Validation Testing
- o Techno-Economic Assessment
- Technip Stone and Webster **Process Technology** 
  - Detailed Engineering Services Significant Experience with Fluidized Bed Reactor Design



Stantec Consulting, Ltd.





Owners Engineer Perspective

- McAbee Construction
  - Pilot fab and installation





- Technical Advisor
- o Cost Share
- o Independent Performance **Evaluation and Techno-**Economic Assessme
- Southern Company
  - o Host Site, Cost Share
- Luminant
  - o Cost Share






### Fundamentals of Adsorption

- Solids functionalized with amines react with CO<sub>2</sub> at "low" temperatures
- Solids are heated to reverse reaction with CO<sub>2</sub>
  - Temperature swing adsorption (TSA)


### Sorbent Capacity for CO<sub>2</sub>





# ADAsorb™ Process Conceptual Design ADA







### **Advantages of Solid Sorbents**

- Energy Penalty -Sensible heat\* and latent heat of evaporation are lower
- Non-corrosive Less expensive materials of construction, no corrosion inhibitors required
- Low volatility Reduced emissions of amines
- Water savings Less cooling water required, minimal liquid waste, no process makeup requirements
- Process Flexibility and Operability
  - Can be applied to cycling plant "load following"
  - No risk of foaming or other solvent-related challenges
  - Reactions with SO<sub>2</sub> may be reversible

<sup>\*</sup>Heat recovery developed for liquid systems



# ADAsorb™ CO<sub>2</sub> Capture Process

#### **Advantages**


- Heat transfer Isothermal operation
- Mass transfer favorable
- Proven at the industrial scale
- Approaches countercurrent gas/solids contacting

#### **Challenges**

- Pressure drop
- Solids circulation
- Sorbent attrition
- Water adsorption
- Heat recovery



### Project Status



- Detailed characterization of sorbent
- 500 MW concept completed
- Design of 1 MW pilot completed

- Sorbent has been manufactured
- Detailed engineering of pilot completed
- Fabrication of pilot is underway




### **BP1 Pre-Engineering Activities - Examples**

- CO₂ uptake
- → H<sub>2</sub>O uptake
- Specific heat capacity
- $ightharpoonup \Delta H_{rxn}$
- Cyclic Stability
- Attrition
- Heat transfer coefficient
- Hydrodynamics






#### **BP1: Lab Characterization - Results**



#### Attrition Resistant

#### Slow kinetics for H<sub>2</sub>O





#### Pilot Construction Activities

- Pilot designed in "modules"
- Off-site fabrication









### ADA

#### **Construction Status**

- Engineering design complete
- Major procurement complete
- Module Fabrication
   Module Fabrication ~ 50% complete
- Site Preparation
   Steam Line 70% complete, foundation work started







Project Schedule Forecast

<u>Task</u>	<u>Date</u>
Modules Installed	Sept '13
Substantial Completion of Mechanical and Electrical Installation	Dec '13
Field Testing	2014







# ADA

# **Process Validation Pilot Testing**

- Host Site: Southern Company Alabama Power Co. Plant Miller
  - Flagship Plant
  - 4 EGUs (~2,640 MW<sub>e</sub>)
  - PRB Coal
  - WFGD
- Pilot Designed for
  - 90% CO<sub>2</sub> Capture
  - $\sim 2,100 \text{ lb CO}_2/\text{hr}$
  - Flue Gas Flow Rate
     ~ 3,500 ACFM








# Barge Access Area at Miller



# ADA

# Module Arrival and Routing




### 1 MW Pilot Location







#### 1 MW Pilot Location





# **Upcoming Activities**

- Complete construction, installation, and startup of pilot
- Operate 1 MW<sub>e</sub> pilot continuously for 60 days
- Use data from 1 MW<sub>e</sub> pilot to update 500 MW design and complete a techno-economic analysis
- Provide a roadmap of future technology improvements based on sorbents and process



# Key Areas for Improvement

- ProcessHeat RecoveryHeat Integration
- Sorbent Fast Kinetics

- Use pilot to evaluate process improvements
- Use pilot to test advanced sorbents
- Scale-up technology

Larger CO<sub>2</sub> Working Capacities
Higher Heat Transfer Coefficient
Improved Heat Tolerance
Lower Specific Heat Capacity
Lower Water Uptake
Lower Cost (including replacement)



# Questions?

Sharon Sjostrom Chief Technology Officer sharons@adaes.com