



DE-FE0025959

NETL CO₂ Capture Technology Project Review Meeting

August 25, 2017

Principal Investigator: Dr. Andrew Maxson

> Presenter: Dr. Jeff Phillips

Project Overview

Project Objectives

 Design and cost coal power plants with CO₂ capture and storage (CCS) that combine oxy-combustion with an indirect-fired, supercritical CO₂ (sCO₂) power cycle and compare the benefits against conventional steam-Rankine cycle coal plants with CCS

Funding

- Federal Share: \$1,838,062; Non-Federal Share: \$459,516
- Project Performance Dates
 - 10/1/2015-9/30/2017 (request for 3/31/2018)
- Project Participants
 - Prime: Electric Power Research Institute, Inc. (EPRI)
 - Subs: Babcock and Wilcox Company (B&W), Doosan ATS America, LLC (Doosan), Dresser-Rand (Siemens), Echogen Power Systems, LLC (EPS); GE Power, Inc., (GE), and Howden Group Ltd. (Howden)



Technology Background



sCO₂ Power Cycle Deployments



Developer	Location	Funding	Size, net MW	Configuration	First Fire
Echogen Power Systems	U.S. (OH)	Private	0.25	Indirect, low temperature	2010
Sandia National Laboratories	U.S. (NM)	Public	0.2	Indirect, low temperature	2011
Bettis Atomic Laboratories	U.S. (PA)	Public	0.15	Indirect, low temperature	2012
Echogen Power Systems	U.S. (NY)	Private	7.3	Combustion turbine bottoming cycle, low temperature	2013
Southwest Research Institute	U.S. (TX)	Public	10	Indirect, high temperature (partial flow)	2017
NET Power	U.S. (TX)	Private	20	Direct, oxy-natural gas, high temperature	2017
STEP Program, Gas Technology Institute	U.S. (TX)	Public	10	Indirect, high temperature	2020



sCO₂ Power Cycle Technology Gaps



Big Picture

- Overall sCO₂ power cycle design that maximizes efficiency and minimizes cost (dependent on thermal resource used)
- Field confirmation of sCO₂ power cycle viability
- Better understanding of operations (e.g., dynamic operation)

Can Durable Components Be Built at Acceptable Cost?

- Fired heater (interface with thermal resource): pressure drop, corrosion, and high heat fluxes
- Recuperators (higher duty than fired heater): are printed circuit heat exchangers the answer?
- sCO₂ turbines: suitable materials for high-turbine inlet temperatures

Fired heater design identified as a major gap; focus of this project



Technical Approach/Project Scope



Task Descriptions

Task 1 – Project Management and Planning

Task 2 – Develop Power Block Design Basis and Baseline

- Develop design basis and identify baselines for six cases that vary:
 - Net Power Out: 550 MWe (oxy-fired) and 90 MWe (air-fired)
 - Oxy-combustion Technologies: atmospheric pressure oxy-pulverized coal (PC) and chemical looping combustion (CLC)
 - Turbine Inlet Temperatures: 593°C and 730°C

Task 3 – Optimize Thermal Integration between Fired Heater and Power Cycle

- Develop flow sheets integrating fired heater and sCO₂ power cycle to maximize efficiency

Task 4 – Conduct Cost Estimates

- Conduct AACE Class-5 cost estimates for each case and compare to base cases

Task 5 – Process Design and Cost Review

 Review cost estimates to identify high-cost items and assess the impact on plant performance and costs of using a lower-cost item



Test Cases

Case	Net Power, MWe	Coal	Combustion Technology	Base Case/Test Case Turbine Inlet conditions	Base Case Reference
1	550	PRB	Oxy/PC	Base: 593°C / 24.1 MPa Test: 593°C / 24.1 MPa	1
2	550	PRB	Oxy/PC	Base: 730°C / 27.6 MPa Test: 730°C / 27.6 MPa	1
3	550	Illinois Basin	CLC	Base: 593°C / 24.1 MPa Test: 593°C / 24.1 MPa	2
4	550	Illinois Basin	CLC	Base: 730°C / 27.6 MPa Test: 730°C / 27.6 MPa	2
5	90	PRB	Air/PC	Base: 538°C / 10.6 MPa Test: 593°C / 24.1 MPa	3
6	90	PRB	Air/PC	Base: 538°C / 10.6 MPa Test: 730°C / 27.6 MPa	3

References:

1. Cost and Performance of Low-Rank Pulverized Coal Oxycombustion Energy Plants: Final Report. DOE/NETL-401/093010. September 2010.

- 2. Alstom's Chemical Looping Combustion Technology with CO₂ Capture for New and Retrofit Coal-Fired Power Plants. Task 2 Final Report, DOE/NETL Cooperative Agreement No. DE-FE0009484. June 2013.
- 3. B&W internal project files.

Apples-to-apples comparison to existing base cases



Progress and Current Status of Project



Summary of Progress

Task Summary

- Task 2 was completed in May 2016
- Task 3 was completed in March 2017
- Task 4 is underway and is scheduled to be completed by December 2017
- Task 5 will begin in January 2018 and finish in March 2018
- Focus of this presentation will be on Task 3 results, which provide the design for each test case and compare the performance against the base cases



Test Case 1 Power Island





Test Case 3 Power Island





Test Case 5 Power Island





Test Cases 1, 2, 5, and 6 Fired-Heater Design

- B&W completed the design of four (4) PC-fired heater concepts: Test Cases 1 and 2 (oxy) and 5 and 6 (air)
- All concepts based on inverted heater configuration
 - Minimizes pipe lengths to/from upstream/downstream equipment
 - Reduces pipe lengths from convection banks to radiant platen and furnace tube arrays
 - Improvement in particle removal





Design Highlights

- Low sCO₂-Side Pressure Drop Requirement
 - sCO₂ volumetric flows 4–6 times higher than equivalent steam systems
 - High sCO₂ pressure drop decreases cycle efficiency
 - Results in deep tube banks with many tubes and lower CO₂ mass fluxes
- High sCO₂ Inlet Temperature
 - sCO₂ inlet temperature 28–56°C higher than equivalent steam systems for Test Cases 1 and 5; 140–195°C higher for Test Cases 2 and 6
 - Higher sCO₂ temperatures result in high tube temperatures, limiting material choices
- Potential design measures to address high tube temperatures
 - Tighter control on CO₂ fluid temperatures
 - Use of higher strength materials
 - Use of additional flue gas recycle
 - Combination of different measures



Test Case 1 Fired-Heater Design





Test Case 5 Fired-Heater Design





Test Cases 1, 2, 5, and 6 – Summary

In all cases, nickel alloys were used for the furnace, platens, and first intermediate banks, stainless steel for the second intermediate banks, and croloy steel for the final bank

Test Case	Coal	Fuel Rate, kg/sec	Furnace Dimensions, m	Heat Transferred to CO ₂ , MWth	Total Pressure Drop, MPa ¹	Heater Efficiency, % ²
1	Rosebud	83.8	19.8 x 14.9 x 33.5	1433	2.81	86.0
2	Powder	72.6	18.3 x 13.7 x 33.5	1261	3.83 ³	87.1
5	River	12.5	7.6 x 7.9 x 27.4	211	1.96	84.4
6	Basin	11.0	7.6 x 7.9 x 27.4	187	2.65 ³	85.2

Notes:

- 1. Total pressure drop includes estimate of header pressure losses.
- 2. Heater efficiency defined as heat input to CO_2 divided by fuel heat input on an HHV basis.
- 3. Current design does not fully address local tube temperature variations in furnace and platens. Measures necessary to address local tube temperatures may increase pressure drop above the cited values.



Test Cases 3 and 4 Fired-Heater Design

 GE completed the design of 2 CLC fired-heater concepts: Test Cases 3 and 4





Design Highlights

- CLC fired heater is comprised of transport reactors, cyclones, convective backpasses, and external moving-bed heat exchangers (MBHEs), but the sCO₂ heat exchanger tube bundles are only arranged in the latter two locations
- Finishing sCO₂ heater section is at a lower elevation to shorten piping length to the turbine, saving material cost
- As pressure drop is the most significant parameter impacting efficiency, the design minimized pressure drop by:
 - -Using refractory-lined, instead of fluid-cooled, walls
 - -Designing tube bundles wider with more assemblies
 - -Selecting larger tubing sizes
 - -Selecting higher-grade materials to reduce tubing wall thickness



Test Case 3 Fired Heater Design





Test Cases 3 and 4 – Summary

- Test Case 3 is designed with conventional austenitic and ferritic materials
- Test Case 4 has nickel-based alloy in the oxidizer MBHE (tubing, outlet header, and piping)

Parameter	Test Case 3	Test Case 4
CO ₂ Total Heat Absorption, MWth	1302	1164
Coal Flow, kg/s	53.37	47.73
Fuel Heat Input, MWth HHV	1447	1294
CLC Fired Heater Island Efficiency, % HHV	90	90
CLC sCO ₂ -side HT Feed DP, MPa	2.4	2.4
CLC sCO ₂ -side LT Feed DP, MPa	3.1	3.1
Final sCO ₂ Delivery Temperature, °C	593	730



Summary of Results

			Test (sCC	2) Case	Base Case	
		Net	Turbine Inlet	Net Plant	Net Plant	
		Power,	Conditions,	Efficiency,	Efficiency,	Improvement,
Case	Туре	MWe	°C / MPa	% HHV	% HHV	% points
1	Оху	550	593 / 24.1	33.0	31.0	2.0
2	Оху	550	730 / 27.6	38.0	34.3	3.7
3	CLC	550	593 / 24.1	38.0	35.8	2.2
4	CLC	550	730 / 27.6	42.5	40.0	2.5
5	Air	90	593 / 24.1	36.0	33.0	3.0
6	Air	90	730 / 27.6	41.0	33.0 ¹	8.0

Notes:

1. Base Case 6 efficiency was not updated since the steam cycle employed represents common commercial practice for this size power plant.

Further improvements in efficiency possible, but might be costly



Future Plans



Next Steps: Tasks 4 and 5



sCO₂ power cycle costs look promising, but fired heaters are expensive



Disclaimer

This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.





Together...Shaping the Future of Electricity

