## WABASH RIVER ENERGY LTD. 2003 PROJECT UPDATE

# Operating Experience at the Wabash River Repowering Project

**CLIFTON G. KEELER** 

**Director Plant Operations** 

Wabash River Energy Ltd.




#### Wabash River Energy Ltd. Project Update

- 2003 Operating Statistics & Milestones
- Update of Fuel Cell Installation
- ConocoPhillips Acquisition

#### Wabash Plant Configuration / Rating

- 2,500 tons/day coal or 2,000 tons/day petcoke; all 2003 operation was on petcoke
- Single train gasification unit
- Rated capacity is 1,780 mmbtu/hr or 200 mmscf/day (22% moisture)
- Spare gasifier, not on-line & not required

#### 2003\*Gasification Unit Operating Statistics



\*Data through September 30, 2003



#### **2003\* Gasification Downtime Causes**

<b>Downtime Cause</b>	% of Year
Remaining 8 average <5 hrs each	0.61%
Gasket failure at instrument nozzle	0.35%
Overfilled slag hopper	0.37%
Fuel supply interruption	0.53%
Slurry mixer replacement	0.60%
SRU plant upsets	0.72%
Cracked derime header in ASU	0.85%
Refractory breach	0.95%
Syngas cooler tube leaks	1.10%
Sodium contamination – ash deposition	6.93%
Total of all downtime	13.01%

\*Data through September 30, 2003



#### **Sodium Ash Deposition**

- 80% of pipe diameter was obstructed
- Deposition occurred in less than 24 hours

- Over 50% of syngas cooler tubes were plugged
- Remaining tubes were severely fouled





**alo≥**al Ene

#### **2003**\* Gasification Unit Performance

- **Availability** = **74.0%** 
  - Availability = On-stream % + Product not required % \* [1-(Forced outage rate/100%)]
- Forced outage rate = 17.51%


Forced Outage Rate =  $\frac{\text{Unplanned outage hours}}{\text{Unplanned outage hours} + \text{on-stream hours}} \times 100\%$ 

- Annual Loading Factor = 56.1% (Product not required for 15% of year)
  Loading Factor = Yearly production / rated capacity
- YTD\* Production = 6,543,502 mmbtu or 30,635 mmscf

\*Data through September 30, 2003



#### Wabash Availability for the Last 4 Years



#### Wabash 4 Year\* Reliability by Sub-System

Reliability = 1 -  $\frac{\text{Forced Outage Hours}}{\text{Period Hours}}$  x 100%


Sub-System	Reliability	Sub-System	Reliability
Raw Syngas Conditioning	100.00%	Sour Water Treatment	99.94%
Rod Mill & Hopper	100.00%	Particulate Removal	99.80%
COS Hydrolysis	100.00%	Low Temp Heat Recovery	99.56%
Chloride Scrubbing	100.00%	Slurry System	99.32%
Syngas recycle compressor	100.00%	Slag Removal System	99.20%
2nd Stage Gasifier	100.00%	Sulfur Recovery	99.17%
Cooling Tower System	100.00%	1st Stage Gasifier	98.70%
Syngas Moisturization	99.98%	Air Separation	98.63%
Acid Gas Removal	99.95%	Syngas Cooling	97.48%
		Overall	92.3%

<sup>\*</sup> Data from 1/1/00 thru 9/30/03



#### Wabash Availability

(Plant available when product not required.)



\*Assumes no ash deposition



#### 2003 Operational Milestones


- 4,100 hour mixers and counting
- Processed 1 millionth ton of petcoke in July
- Over 50 trillion btus of gas produced
- Over 30,000 hours of coal/petcoke operation
- Fuel Cell dedication
- ConocoPhillips acquires E-Gas<sup>™</sup> technology

#### Fuel Cell Demonstration Objective

To demonstrate the significant improvement in efficiency and environmental performance of carbonate fuel cell technology in coal based power generation systems.



#### **Environmental Impact Comparison**





## Two Fuel Cell Modules at FCE Conditioning Facility in Danbury, CT







#### Wabash River Energy Ltd. Project Update

## DFC 3000 BOP SKIDS BEING INSTALLED AT WABASH



#### Fuel Cell Dedication – August 13, 2003



#### **Summary of Project Status**

- All four balance of plant (BOP) skids are installed and their commissioning is in progress.
- The two Fuel Cell modules are built and are being prepared for delivery.
- Formal dedication of the project was held August 13<sup>th</sup>, 2003.
- Commissioning of the power plant is planned for first quarter of 2004.



#### ConocoPhillips Acquisition

- COP acquires E-Gas<sup>™</sup> technology, patents and 23 technical personnel
- Services Agreement
  - Technical and management support for Wabash
  - 15 COP personnel at Wabash
  - Seamless operation
- Access Agreement
  - Technology advances / DOE Projects
  - Slipstream testing
  - E-Gas<sup>™</sup> marketing
  - Operator training ground for future plants







Advancing Clean Energy with E-Gas<sup>TM</sup> Technology from

### ConocoPhillips

and Fuel Cell Technology from

