#### Intelligent Monitoring Systems and Advanced Well Integrity and Mitigation Project Number DE-FE-00026517

<sup>1</sup>**Julia Correa**, <sup>1</sup>Barry Freifeld, <sup>1</sup>Jonathan Ajo-Franklin, <sup>1</sup>Michael Commer, <sup>2</sup>Scott McDonald

> <sup>1</sup>Lawrence Berkeley National Lab <sup>2</sup>Archer Daniels Midland

> > U.S. Department of Energy

National Energy Technology Laboratory Addressing the Nation's Energy Needs Through Technology Innovation – 2019 Carbon Capture, Utilization, Storage, and Oil and Gas Technologies Integrated Review Meeting August 26-30, 2019

## Collaborators

- Scott McDonald (Project PI), Archer Daniels Midland Company
- Michael Commer, Michelle Robertson, Todd Wood, Barry Freifeld and Jonathan Ajo-Franklin, Lawrence Berkeley National Laboratory
- Joern Kaven, United States Geological Survey
- Nick Malkewicz, Schlumberger
- Sallie Greenberg, Illinois State Geological Survey
- Thomas Coleman, Silixa LLC
- David Larrick, Richland Community College


## **Presentation Outline**

- Technical overview
- Project highlights
- Latest accomplishments
- Project Summary
  - Key Finding
  - Next Steps

## SOV and DAS technology



#### **DAS Seismic**



#### New vs. Conventional Technology

Seismic surveys are considered the backbone technique for CO2 storage monitoring programs.

Stringing thousands of cables and running thumper trucks every few years can test the limits of good neighbors. Costs are high.

Permanent reservoir monitoring offers a way to obtain higher quality information with minimal intrusion into surrounding lands –

- DAS provides high spatial and temporal resolution.
- Installation can be in horizontal directionally drilled boreholes beneath bodies of water, existing infrastructure.
- Excitation of DAS cables can be achieved through permanent fixed rotary sources for continuous monitoring.

Streams &






Lawns &

Landscaping Other Ob

4

#### **Distributed Acoustic Sensing**

- Standard optical fibre acts as the sensor array
  - Typical sampling at 10kHz on 10,000m fibre
  - Standard gauge length of 10m
  - Spatial sampling of 25cm
  - DAS measures change in average elongation per 10m gauge length per 0.1ms acoustic time sample, sampled every 0.25 m in distance




Parker et al., Distributed Acoustic Sensing – a new tool for seismic applications, *first break* (32), February 2014

$$\left[u\left(z+\frac{dz}{2},t+dt\right)-u\left(z-\frac{dz}{2},t+dt\right)\right]-\left[u\left(z+\frac{dz}{2},t\right)-u\left(z-\frac{dz}{2},t\right)\right]$$


Ż,

#### ADM IMS cable contains new Silixa Ltd. Carina technology – significantly lower noise floor

CO2CRC Otway – SP0, 700 m offset, 5 sweeps, data courtesy R. Pevzner




#### Surface Orbital Vibrator (SOV) – Controlled AC Motor




#### SOV for permanent reservoir monitoring

Sweep-based: controlled release of seismic energy




Not phase-controlled: simpler system


DAS records before deconvolving source sweeps ( $t_{shift}$  up to 20 ms)




Same records after deconvolving source sweeps ( $t_{shift} < 1 \text{ ms}$ )



#### ADM site in Illinois IMS Fiber Optic and SOV Layout



## SOV sweep recorded by the permanent N/E DAS surface array




SOV4 sweep recorded by the northeast DAS surface array.

SOV5 sweep recorded by the northeast DAS surface array.

## Lessons Learned at ADM


- Testing different set-ups in order to increase signal response:
  - Changed fiber length and adjusted laser repetition rate
  - Changed depth of the geophone that records the SOV
  - Increased different force of the SOV source
  - Tested different sweeps designs




#### **Lessons Learned at ADM** Increased the force of the SOV to 100%

70% force

100% force




## Fiber deployment




HWC SMF HWC Constellation Splice





#### FOC cable depth=10 meters


## Fiber deployment SM vs Carina



|             | /             | J             |             |
|-------------|---------------|---------------|-------------|
| Single-mode | Constellation | Constellation | Single-mode |
| fiber       | fiber         | fiber         | fiber       |
| NW line     | NW line       | NE line       | NE line     |


# Well tie to 2D seismic – SOV4 on NW line

- Migrated stack was used for well tie
- There strong reflections along the area of interest
- After well tie, the reflections in the seismic could be associated with the monitoring zone and seal



# Well tie to 2D seismic – SOV4 on NW line

- Migrated stack was used for well tie
- There strong reflections along the area of interest
- After well tie, the reflections in the seismic could be associated with the monitoring zone and seal





Maquoketa shale (460ms)


St. Peter (530ms) Shakopee Dolomite (570ms)

Eau Claire (740ms)


Eau Claire shale (760ms) Mt. Simon (780ms)

Mt. Simon C (890ms) Mt. Simon B (890ms) Mt. Simon A up (930ms) Mt. Simon A low (970ms) Argenta

#### Outlook: Joint inversion of flow and seismic




#### Flow-data inversion using a radial model



#### Flow-data inversion using a radial model

- a. Data fits
  produced by
  6-layer
  permeability
  model
- Injection rate and pressure in VW#2-Zone 2
- c. RMS data fitting error over inversion iterations



300

20

## Accomplishments to Date

- Design and specification DAS cable, SOV, instrumentation, data acquisition and associated subsystems
  - Horizontal directional drilling (HDD) for fiber deployment to minimize disturbance on the land
- Development of an IMS architecture and the demonstration of its operation using synthetic data feeds
- Detail real-time DAS cross-correlation and stacking algorithm and provide analysis of synthetic data evaluation with different levels of synthetic noise
- Testing engineered fiber as an alternative in order to increase sensitivity of DAS measurements

## Lessons Learned

- The use of engineered fibers increase signal sensitivity, being an alternative to projects where single-mode fibers provides low signal-to-noise ratio
  - Major potential for imaging deep reflectors in projects where only surface fibers can be used
- Larger SOV that will provide higher force can increase signal strength and improve reflections continuity
- The geophone installed deeper showed a ghost reflection in the pilot signal, which degraded the final deconvolution result
- Challenges with data transfer and network latency

## Synergy Opportunities

- Initial trialing of DAS helical wound cables supported by Otway Project
- -Further testing of novel Constellation optical fiber
- Development of surface cable DAS data processing flows and HDD. Linkages to the CO2CRC Otway Project Stage 3, CMC CaMI, and PTRC Aquistore

## **Project Summary**

- Key Findings.
  - We are making steady progress on the operation of the DAS-SOV network. Our latest tests with the engineered fibers gives us hope that we can monitor the injection interval
- Next Steps
  - Installation of larger SOVs to improve signal
  - Operation of IMS equipment and related controls
  - Optimization of system with respect to data quality and processing speed
  - Comparison of real time IMS data with state of the art detailed models
  - DAS data feed integration into the passive seismic monitoring system and system optimization

## Appendix

These slides will not be discussed during the presentation, but are mandatory.

## Benefit to the Program

- Carbon Storage Program Goal Support:
- Goal (1) Develop and validate technologies to ensure 99 percent storage permanence by reducing leakage risk through early detection mitigation.
- Goal (2) Develop technologies to improve reservoir storage efficiency while ensuring containment effectiveness by advancing monitoring systems to control and optimize CO2 injection operations.
- Goal (4) Contributing to the Best Practice Manuals for monitoring, verification, and accounting (MVA) with regard to IMS.

## Benefit to the Program

- Reduce overall storage cost.
- Increase monitoring sensitivity.
- Increase monitoring reliability by using an integrated system.
- Optimize operation and maintenance activities.
- Reduce project risk during and after the injection of CO2.

#### **Project Overview** Goals and Objectives

- Develop an integrated IMS architecture that utilizes a permanent seismic monitoring network, combines the real-time geophysical and process data with reservoir flow and geomechanical models.
- Create a comprehensive monitoring, visualization, and control system that delivers critical information for process surveillance and optimization specific to the geologic storage site.
- Use real-time model calibration to provide reservoir condition forecasts allowing site optimization.

#### **Project Overview** Specific Project Objectives

- 1. Design an IMS using a real-time multi-technology architecture that fully integrates and enhances the site's existing monitoring infrastructure that includes multi-level 3D seismic arrays, distributed acoustic sensing (DAS), multi-level pressure/temperature sensors, distributed temperature sensing (DTS), borehole seismometers, and surface seismic stations
- 2. Augment the sites monitoring capabilities by installing several rotary seismic sources and integrating a network of surface DAS with the existing seismic system to create a continuous active source seismic monitoring (CASSM) array covering over two square kilometers and extending to a depth of 6,300 feet.
- 3. Develop terabyte level data processing solutions for real time monitoring of reservoir conditions and time lapse imaging of the CO2 plume.

#### **Project Overview** Specific Project Objectives


- 4. Commission and operate the monitoring system in an industrial setting under actual conditions.
- 5. Validate and document the economic and environmental benefits of the monitoring system.
- 6. Update the monitoring verification and accounting best practices guide to include IMS and CASSM monitoring systems.
- 7. Incorporate DAS channels in routine location of microseismicity using the combination of borehole and surface seismic stations.
- 8. Develop near real-time data processing techniques to overcome passive seismic monitoring limitations of low signal-to-noise ratio on DAS array.

## **IMS Organization Chart**

- ADM has overall project responsibility and is accountable for:
  - Task 1 Project management and planning
  - Task 3 IMS Installation
  - Task 4 IMS Commissioning and Operation
- LBNL's team will be accountable for:
  - Task 2 IMS Design
  - Subtask 3.3 IMS DAS Surface Cable and Rotary Sources CASSM
  - Subtask 3.4 IMS Control, Monitoring, and Data Acquisition Software
  - Subtask 4.2 Function test of IMS DAS Surface Cable and Rotary Sources CASSM
  - Subtask 4.5 Validate IMS real-time reduced order models



- USGS's team will be accountable for:
  - Subtask 2.4 Design of Passive Microseismic Monitoring System
  - Subtask 4.6 Operation Passive Microseismic Monitoring System



## **IMS Organization Chart**

- Silixa's team will be accountable for:
  - Subtask 2.1 IMS Data Acquisition and Processing Equipment,
  - Subtask 3.2 IMS Data Acquisition and Processing Equipment,
  - Subtask 4.1 IMS Instrumentation, Controls, and Data Network,
- RCC's team will be accountable for:
  - Subtask 1.4 Project Outreach and Education.
- ISGS's team will participate in:
  - Subtask 1.4 Project Outreach and Education,
  - Subtask 2.4 Design of Passive Microseismicity Monitoring System
  - Subtask 4.6 Operating Passive Microseismicity Monitoring System
- SLB's team will participate in:
  - Subtask 2.1 Data Acquisition and Processing Equipment
  - Subtask 4.5 Validate IMS real-time reduced order models









Schlumberger Carbon Services


#### IMS Organization Chart General Task Overview




#### IMS Organization Chart Task 1.0 - Project Management




#### IMS Organization Chart Task 2.0 - IMS Design



#### IMS Organization Chart Task 3.0 - IMS Installation



#### IMS Organization Chart Task 4.0 - IMS Operation



#### **IMS Gantt Chart**

|    | Task Name   | Resource  |            |            |          | 2015            |                     | 2016                        |                         | 2017                  |                 | 2018                |                   |                     | 2019                    |
|----|---|-----------|------------|------------|----------|-----------------|---------------------|-----------------------------|-------------------------|-----------------------|-----------------|---------------------|-------------------|---------------------|-------------------------|
| ID |   | Names     | Start      | Finish     | Duration | Sep Oct Nov Dec | Jan Feb Mar Apr May | Jun Jul Aug Sep Oct Nov Dec | Jan Feb Mar Apr May Jun | Jul Aug Sep Oct Nov G | Dec Jan Feb Mar | Apr May Jun Jul Aug | g Sep Oct Nov Dec | Jan Feb Mar Apr May | Jun Jul Aug Sep Oct Nov |
| 1  | Task 1.0 – Project Management and Planning  |           | 10/01/2015 | 10/1/2015  | Od       | •               |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 2  | Subtask 1.1: Project Management Plan  | ADM       | 10/01/2015 | 03/31/2016 | 183d     | +               |                     | Renew Application BP2 (0    | 7/31/16)                | Renew Application BP3 | 3 (07/31/17)    |                     |                   |                     |                         |
| 3  | Subtask 1.2: Reporting  | ADM       | 10/01/2015 | 09/30/2019 | 1461d    |                 | Ŷ Ŷ                 | <u>\$</u>                   | ê ê                     | <b>\$</b>             | Ŷ               | <u>ê</u>            | Ŷ                 | ý ý                 | <u>\$</u>               |
| 4  | Subtask 1.3: Kickoff Meeting  | ADM       | 10/01/2015 | 12/31/2015 | 92d      | ÷ (             |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 5  | Subtask 1.4: Project Outreach and Education   | RCC       | 10/01/2015 | 09/30/2018 | 1096d    |                 |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 6  | Complete Project Prerequisites  |           | 04/01/2016 | 04/01/2016 | Od       |                 |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 7  | Task 2.0 – IMS Design   |           | 10/01/2015 | 10/01/2015 | Od       | •               |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 8  | Subtask 2.1: IMS Data Acquisition and Processing<br>Equipment   | LBNL      | 01/01/2016 | 09/30/2016 | 274d     | ×               |                     | <u>•</u>                    |                         |                       |                 |                     |                   |                     |                         |
| 9  | Subtask 2.2: Design CASSM   | LBNL      | 01/01/2016 | 09/30/2016 | 274d     | ÷               |                     | <b>Q</b>                    |                         |                       |                 |                     |                   |                     |                         |
| 10 | Subtask 2.3: IMS Software Design and<br>Development   | LBNL      | 01/01/2016 | 09/30/2016 | 274d     | +               |                     | 0                           |                         |                       |                 |                     |                   |                     |                         |
| 11 | Subtask 2.4: Design Passive Microseismicity<br>Monitoring system  | USGS      | 03/01/2016 | 03/31/2017 | 396d     |                 | <b>→</b>            |                             | <b>(</b> )              |                       |                 |                     |                   |                     |                         |
| 12 | Subtask 2.5: IMS Final Design Review  | ALL       | 10/03/2016 | 10/19/2016 | 17d      |                 |                     | ÷ <b>_</b> ∳                |                         |                       |                 |                     |                   |                     |                         |
|    | Subtask 2.6: IMS Equipment Procurement  | ADM       | 07/22/2016 | 03/31/2017 | 253d     |                 |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 14 | Subtask 2.7: Construction and Environmental<br>Permits  | ADM, RCC  | 08/01/2016 | 09/30/2016 | 61d      |                 |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 15 | Complete IMS Design   |           | 10/20/2016 | 10/20/2016 | Od       |                 |                     | *                           |                         |                       |                 |                     |                   |                     |                         |
| 16 | Task 3.0 – IMS Installation   |           | 10/20/2016 | 10/20/2016 | Od       |                 |                     | *                           |                         |                       |                 |                     |                   |                     |                         |
| 17 | Subtask 3.1: Develop Construction Plans   | ADM       | 10/20/2016 | 11/17/2016 | 29d      |                 |                     | ÷⊒∳                         |                         |                       |                 |                     |                   |                     |                         |
| 18 | Subtask 3.2: IMS Data Acquisition and Processing<br>Equipment Installation  | ADM, LBNL | 11/18/2016 | 03/31/2017 | 134d     |                 |                     | +                           | <u> </u>                |                       |                 |                     |                   |                     |                         |
| 19 | Subtask 3.3: IMS DAS Surface Cable and Rotary<br>Sources CASSM Installation   | ADM, LBNL | 11/18/2016 | 06/30/2017 | 225d     |                 |                     | <b>→</b>                    |                         | <u>¢</u>              |                 |                     |                   |                     |                         |
| 20 | Subtask 3.4: IMS Control, Monitoring, and Data<br>Acquisition, Software Installation                                | LBNL, ADM | 04/03/2017 | 06/30/2017 | 89d      |                 |                     |                             |                         | <u>\$</u>             |                 |                     |                   |                     |                         |
| 21 | IMS Installation Complete   |           | 07/01/2017 | 07/01/2017 | Od       |                 |                     |                             | կ                       | •                     |                 |                     |                   |                     |                         |
| 22 | Task 4.0 – IMS Commissioning and Operation  |           | 07/01/2017 | 07/01/2017 | Od       |                 |                     |                             | L,                      | •                     |                 |                     |                   |                     |                         |
| 23 | Subtask 4.1: Commissioning of DAS, SOV,<br>Instrumentation, Controls, & Data Acquisition                            | ADM       | 07/01/2017 | 09/30/2017 | 92d      |                 |                     |                             | ÷                       | • <b>\$</b>           |                 |                     |                   |                     |                         |
| 24 | Subtask 4.2:Commissioning of CASSM System<br>and Joint Inversion Module   | ADM       | 07/01/2017 | 12/31/2018 | 549d     |                 |                     |                             | ÷                       |                       |                 | Ŵ                   |                   | 5                   |                         |
| 25 | Subtask 4.3: Commission of Passive Seismic<br>Monitoring Network  | ADM       | 07/01/2017 | 09/30/2017 | 92d      |                 |                     |                             | L,                      | ¢                     |                 |                     |                   |                     |                         |
| 26 | Subtask 4.4: Operation of IMS Equipment and<br>Data Acquisition System<br>Subtask 4.5 Operation of integrated CASSM | ALL       | 10/01/2017 | 09/30/2019 | 730d     |                 |                     |                             |                         | *                     |                 |                     |                   |                     | <u> </u>                |
| 27 | System with Joint Inversion Module  |           | 01/01/2019 | 09/30/2019 | 273d     |                 |                     |                             |                         |                       |                 |                     | Ļ                 | \$                  | ¢                       |
| 28 | Subtask 4.6 Operation of Passive Seismic<br>Monitoring Network  | USGS, ADM | 10/01/2017 | 09/30/2019 | 730d     |                 |                     |                             |                         | <b>→</b>              |                 |                     |                   |                     | •                       |
| 29 | IMS Commissioning and Operation Complete  |           | 10/01/2019 | 10/01/2019 | Od       |                 |                     |                             |                         |                       |                 |                     |                   |                     | 38 🔺                    |
| 30 | Final Project Reporting   |           | 10/01/2019 | 10/31/2019 | 31d      |                 |                     |                             |                         |                       |                 |                     |                   |                     |                         |
| 31 | PROJECT COMPLETE  |           | 11/01/2019 | 11/01/2019 | Od       |                 |                     |                             |                         |                       |                 |                     |                   |                     |                         |

## Bibliography

- Commer M., McDonald S., Correa J., Freifeld B., Ajo-Franklin J., 2018, An integrated CO2 monitoring system: First inversion results, Exp. Abstract, TOUGH2 Symposium 2018, Lawrence Berkeley Nat'l Lab.
- Correa, J., Cheng, F., Freifeld, B. M., Ajo-Franklin, J., Pevzner, R., Tertyshnikov, K., Yavuz, S., Wood, T., Robertson, M., Daley, T., McDonald, S., Guerra, D. and Hill, D., 2019, Continuous on-demand reservoir monitoring using DAS and permanent surface vibrators: case studies and preliminary results. Presentation in SEG International Conference 2019 Post-Convention Workshop

## BACKUP

## CCS#2 synthetic seismogram

- Use density and sonic logs to generate reflectivity series
- Convolved the reflectivity series with a synthetic wavelet
  - Zero phase wavelet
  - Ormsby filter with
    frequencies 10 15-70-80 Hz

