



EERC



UNIVERSITY OF
NORTH DAKOTA



Critical Challenges. Practical Solutions.



Energy & Environmental Research Center (EERC)

Improving EOR Performance Through Data Analytics and Next-Generation Controllable Completions (DE-FE0031790)


U.S. Department of Energy National Energy Technology Laboratory
Oil & Natural Gas

2020 Integrated Review Webinar
October 13, 2020

Nicholas A. Azzolina
Principal Hydrogeologist & Statistician

Conceptual Pilot Test Design

- Field-test controllable completion for active well control during carbon dioxide (CO₂) enhanced oil recovery (EOR).
- One lateral injection well with ICV system.
- Two offset lateral production wells with openhole completion.
- Rigorously monitored field test.
- Use offset patterns as a reference case to assess performance.
- Combine field and simulation data to develop business case scenarios.



Red River Fm. Cedar Creek Anticline

Project Partners

Lead Organization

- Energy & Environmental Research Center



U.S. DEPARTMENT OF
ENERGY



Project Partners

- U.S. Department of Energy
- North Dakota Oil & Gas Research Program
- Denbury Onshore LLC
- NCS Multistage LLC
- North Dakota Geological Survey
- Schlumberger
- Computer Modelling Group Ltd.



Funding and Project Performance Dates



Funding Profile by Budget Period (BP) (October 1, 2019 – September 30, 2024)

	BP1 (\$) (10/01/2019 - 01/31/2021)			BP2 (\$) (02/01/2021 - 01/31/2023)			BP3 (\$) (02/01/2023 - 09/30/2024)			Total (\$)		
	Federal	Nonfederal	Total	Federal	Nonfederal	Total	Federal	Nonfederal	Total	Federal	Nonfederal	Total
DOE	2,671,594	–	2,671,594	3,297,845	–	3,297,845	2,027,638	–	2,027,638	7,997,077	–	7,997,077
NDIC OGRP	–	133,000	133,000	–	200,000	200,000	–	167,000	167,000	–	500,000	500,000
Schlumberger	–	475,580	475,580	–	128,810	128,810	–	128,914	128,914	–	733,304	733,304
CMG	–	508,350	508,350	–	137,691	137,691	–	120,602	120,602	–	766,643	766,643
Total	2,671,594	1,116,930	3,788,524	3,297,845	466,501	3,764,346	2,027,638	416,516	2,444,154	7,997,077	1,999,947	9,997,024
Total Cost Share %	70.5%	29.5%		87.6%	12.4%		83.0%	17.0%		80.0%	20.0%	

*Note: **Denbury** is providing additional contributions in the form of field support, infrastructure development, CO₂ supply, and injection/production operations. **NCS Multistage** is providing additional contributions in the form of field activities: multizone completions and injection well tracer testing.*

Technology Background: Qumulus™ Ultimate Recovery System

- Packers provide isolation between zones.
- Injection valve control at each zone.
- Pressure and temperature at each zone.
- Single wire for all valves and gauges.
- Operate from anywhere using a cloud-based supervisory control and data acquisition (SCADA) system.
- Slim dimensions, suitable for common onshore wells.




Technical Approach/Project Scope


- **Task 1.0 – Project Management and Planning**
 - **Task 2.0 – ICV Pilot Systems Design**
 - 2.1 – Screening and Selection of Test Pattern
 - 2.2 – Characterization ← *DP1: Go/no-go decision for the candidate injection well 12/31/20*
 - 2.3 – Baseline Modeling
 - 2.4 – Pilot Design
 - **Task 3.0 – Operation and Monitoring**
 - 3.1 – Install and Test Systems
- DP2: Go/no-go decision for successful ICV system in the injection well 3/31/22*

Technical Approach/Project Scope (cont.)

- **Task 3.0 – Operation and Monitoring (cont.)**
 - 3.2 – System Operation and Monitoring
- **Task 4.0 – Active Control System Development**
 - 4.1 – Database and User Interface Development
 - 4.2 – Active Control System Development, Testing, and Optimization
- **Task 5.0 – Business Case Development**
 - 5.1 – Long-Term Pilot Test Pattern Performance Simulation
 - 5.2 – Business Case Development

Budget Period 1												Budget Period 2												Budget Period 3																							
Year 1						Year 2						Year 3						Year 4						Year 5																							
2019			2020						2021						2022						2023						2024																				
Q1			Q2		Q3		Q4		Q5		Q6		Q7		Q8		Q9		Q10		Q11		Q12		Q13		Q14		Q15		Q16		Q17		Q18		Q19		Q20								
Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep





- ✓ Pilot test pattern and candidate injection well have been selected.
- ✓ Rock core laboratory analyses complete.
- ✓ Full-field geologic model complete.
- ✓ Initiated numerical reservoir simulations.
- ❑ Wireline logging in early October 2020.
- ❑ Baseline three-component, 3D seismic acquisition planned for November 2020.
- ❑ Preliminary ICV system design complete and pending field data.

Expected Results

- Demonstrate performance and reliability of ICV deployment for CO₂ EOR in horizontal injection and production wells (*first application*).
- Evaluate perceived risks of deploying ICVs in horizontal wells. Inform ICV system design, installation practices, and operational practices.
- Develop/improve active control systems for ICV operation.
- Quantify performance metrics: 1) net CO₂ utilization, 2) oil recovery and sweep efficiency, and 3) operating costs.
- Evaluate business cases for the implementation of ICVs for improving EOR performance for a range of reservoirs, fields, and operational scenarios (including potential application for conformance control for Bakken EOR).

Benefits

- Demonstrate the reliability and performance to enable broad adoption of controllable completions in horizontal wells.
 - Current state: Limited demonstration of reliability and performance.
 - Path forward: Validate a potential pillar technology for unlocking EOR in unconventional tight oil plays, where conformance is a known challenge.
- Techno-economic assessments indicate horizontal wells are a key to enabling economical EOR in conventional fields.
- Controllable completions may allow horizontal wells to be managed like a series of vertical wells and drive efficiency, reduce CO₂ net utilization rates, and increase oil recovery with fewer wells.

¹“Techno-Economic Assessment of Implementing Lignite Based CO₂ EOR in North Dakota” Final Report, submitted to North Dakota Department of Commerce, Grant Agreement No. 1867.


Denbury Statement Regarding Benefits

- Piloting next-generation controllable completions offers an attractive value proposition to Denbury.
- This pilot test will provide new insights on reservoir performance prior to and during CO₂ EOR. Additionally, it will give us operational experience deploying advanced completions in horizontal wells. Furthermore, this pilot will allow us to leverage data analytics to optimize well and reservoir performance.
- The pilot's well-thought-out design will streamline our ability to interpret results. Our findings will be used to evaluate the business case for applying this technology at Cedar Creek Anticline and in other fields.



Summary

- This project has adapted to the 2019–2020 operating conditions and is on track to complete the modified scope of work and project timeline.
- Field work is under way, which will inform the ICV design and reservoir simulations.
- The expected installation date for the ICV system is Q3-2021.





Nicholas A. Azzolina, Ph.D.
Principal Hydrogeologist & Statistician

nazzolina@undeerc.org

701.777.5120 (phone)

**Energy & Environmental
Research Center**

University of North Dakota
15 North 23rd Street, Stop 9018
Grand Forks, ND 58202-9018

www.undeerc.org

701.777.5000 (phone)

701.777.5181 (fax)

A wide-angle photograph of a university campus at sunset. The sun is low on the left, casting a warm glow over the scene. In the foreground, there are trees with yellowing leaves. In the background, there are several large, multi-story brick buildings, likely university halls or administrative buildings, and a parking lot filled with cars.


THANK YOU

Critical Challenges. Practical Solutions.


Improving EOR Performance Through Data Analytics and Next-Generation Controllable Completions (DE-FE0031790)

APPENDIX




Project Organizational Chart



Project Gantt Chart



★ Definitized Amendment Finalized (1/27/20)

Milestones (M) 	Deliverables (D) 	Decision Points (DPs) 
M1 – Screening and Selection of Pilot Test Pattern Complete (1/31/20)	D1 – Project Management Plan (2/26/20)	DP1 – Go/No-Go decision for the candidate injection well (12/31/20).
M2 – Field Characterization Activities Complete (12/31/20)	D2 – Workforce Readiness Plan (11/1/20)	DP2 – Go/No-Go decision for successful ICV system in the injection well (3/31/22).
M3 – Laboratory Characterization Activities Complete (10/31/20)	D3 – Data Management Plan (1/27/20): Revised for Definitized Agreement	
M4 – ICV Installation and Initial Testing Complete (3/31/22)	D4 – Interim Field Performance Summary Report (1/31/23)	
M5 – Tracer Study Initiated (8/1/22)	D5 – Business Cases for Commercial Deployment of ICV Systems for Managing EOR Performance (9/30/23)	
M6 – Initial Active Control System Design Complete (1/31/22)	D6 – Development Strategy Plan (7/31/24)	
M7 – Active Control System Design Complete (1/31/23)	D7 – Data Submitted to NETL EDX (9/30/24)	
M8 – Geologic Model Complete (1/31/23)		
M9 – Transfer of Operational Ownership of ICV Pilot to Field Operator Initiated (11/1/23)		
M10 – Numerical Simulation Complete (1/31/24)		



EERC



U N I V E R S I T Y O F
NORTH DAKOTA



Critical Challenges. Practical Solutions.