Demonstration of Proof of Concept of a Multi-Physics Approach for Near Real-Time Remote Monitoring of Dynamic Changes in Pressure and Salinity in Hydraulically Fractured Networks©

DE-FE0031785

PI: Mohsen Ahmadian

UT Austin – Bureau of Economic Geology Subcontractors: UNC and Duke University

U.S. Department of Energy National Energy Technology Laboratory Oct, 14, 2020

BUREAU OF ECONOMIC GEOLOGY Virtual Annual Review Meeting

Research Challenges and Project Objectives



Problem Statement: Current geophysical methods are weakly sensitive to identifying stimulated reservoir volume (SRV) and dynamic changes that occurs in SRV during life time of a hydraulically-fractured (HF) reservoir.

Project Objectives:

- 1. To demonstrate Electromagnetic (EM) and Acoustic Contrast Agent (CA)-based method for <u>direct *in situ*</u> monitoring of relative physio-chemical changes that are commonly encountered during HF production <u>remotely</u>
- 2. Advance utility of high sampling rate, surface-deployable tools to achieve objective #1 in near real time at the UT/BEG's Devine Field Test Site (DFTS)



Persistence Pays Off

• Current project was first proposed to DOE/NETL in May 2016:

Project Narrative - Area of Interest 2

AOI2: Demonstration of Proof of Concept of Coupled Geophysical Methods for High Resolution Illumination of Fracture Networks

May, 4, 2016

SUBMITTED UNDER FUNDING OPPORTUNITY ANNOUNCEMENT

DE-FOA-0001445



Unique Aspects of Current Work

- It leverages the AEC's previous investment in contrast agents for fracture and water flood mapping, payload delivery and micro-sensor research programs, as well as a well-characterized testbed at the UT's DFTS
- The scale of the proposed demonstration is large enough to be representative of the reservoir scale but still allow us to perform verification of the proposal economically
- It combines multiple geophysical techniques, configurations, and models
- It lays the foundation for future consideration in an actual HF field



AEC Prototypes and Applications



Energy

U.S. DEPARTMENT OF

OFFICE OF OIL & NATURAL GAS

Bureau of

Economic

JEOLOGY



Sensors and materials will be used individually or combined to interrogate • the subsurface and other inaccessible environments



Leveraging Prior Work by UT's/AEC/BEG Developed Validated Methods to Accurately Map SRV at DFTS





Ahmadian et. al. SPE 2018 **SPE-189858-MS** *Ahmadian et. al. SPE 2019* **SPE-196140-MS**

Project Partners













THE UNIVERSITY of NORTH CAROLINA at CHAPEL HILL

RGY











Funding (DOE and Cost Share)

| | FY 2019 | | FY | 2020 | Total | |
|---|---------------|---------------|---------------|---------------|-----------------|-------------------|
| | DOE | Cost Share | DOE | Cost Share | DOE | Cost Share |
| | Funds | | Funds | | Funds | |
| Applicant-UT Includes Services for Field Work | \$ 414,841.00 | \$ 105,030.78 | \$ 535,551.00 | \$ 149,629.90 | \$ 950,392.00 | \$ 254,660.68 |
| Sub-recipient A- UNC | \$ 99,999.00 | \$ 20,075.00 | \$ 100,000.00 | \$ 20,075.00 | \$ 199,999.00 | \$ 40,150.00 |
| Sub-recipient B- Duke | \$ 172,485.00 | \$ 43,121.00 | \$ 177,122.00 | \$ 44,281.00 | \$ 349,607.00 | \$ 87,402.00 |
| Total (\$) | \$ 687,325.00 | \$ 168,226.78 | \$ 812,673.00 | \$ 213,985.90 | \$ 1,499,998.00 | \$ 382,212.68 |
| Total Cost Share % | | 20% | | 21% | | 20% |



Technical Approach/Project Scope



BP1

9

Progress and Current Status of Project

3.0: Core and Material Characterization

DFTS Site

Economic

Geology



Energy

OFFICE OF OIL & NATURAL GAS

• Described 249 ft (76 meters) of core for DFTS

Stratigraphy

- Selected intervals from the DMW1 and DMW3 cores were slabbed and photographed to document lithology and stratification
- Facies and depositionalsystems interpretations have been made
- Based on stratification and vertical facies relationships, a tidally influenced deltaic interpretation has been proposed.

3.0: Electrical Measurements in the Lab*- Salinity

Measurement models built to mimic scale down version of the Devine test site



OFFICE OF OIL & NATURAL GAS

GEOLOGY

% Relative Change in Conductivity vs. Salinity as a Function of Electrode Separation



• Relative change in conductivity is large for all electrode configurations probed when salinity is changed:

• <u>All passes the Go-No-Go criteria for BP1</u>

3.0: Electrical Measurements in the Lab*- Pressure

Two pressure dependent properties of CA probed











- Relative change in conductivity is large when either lithostatic or hydrostatic pressure is applied to the CA in a confined space
- Hypothesis:
 - a) Lithostatic Pressure causes CA grain to compact,
 - b) Hydrostatic Pressure caused CA grain separation

All passes the Go-No-Go criteria for BP1

Field Study Plan-Expected Results



Proposed Study Leverages the Existing Infrastructure at the UT/BEG's Devine Test Site



| Well ID | Distance to Inj well (ft) | Total Depth (ft) | Screen /Perf Depth (ft) | Completion Type- Equipment |
|----------|---------------------------------|------------------------|-------------------------------|-------------------------------|
| lnj well | 0 | 267 | 175 | Steel/4"/Perf |
| DMW1 | 10 | 267 | 170-77 | PVC/2"-ERT |
| DMW2 | 20 | 190 | 170-180 | PVC/2" |
| DMW3 | 45 | 190 | 130-135 | PVC/2" |
| DMW4 | 75 | 190 | 130-135 | PVC/2" |
| DMW5 | 107 | 190 | NA | PVC/2" |
| DMW6 | 91 | 190 | NA | PVC/2" |

- Injection via Huff-n-Puff from existing injection well
- Fluid migration and pressure will be validated by downhole Pressure/Salinity gauges in DMW1-2 and possibility in a new monitoring well at distal end of the HF



5.1: Fluid Flow Modeling-Field Test Plan



5.1: Fluid Flow Modeling

180 BPD Injection Case- Movie

Aqueous Salinity 2020-07-02 K layer: 8



- Simulation start date: July 1st.
- Injection Start Date: July 4th 0:00 am
- Resting time start after 4 hours of injection, and lasting 12 hours.
- Extraction started at July 4th 16:00 pm.
- The video ends at July 11th, 0:00 am







mini Pilot: 9/21-9/26/20 at DFTS







Fluid Flow Modeling Calibration –Pilot #1:9/21-9/26/20



Monitoring Dilation, Closure and Compaction Mapping **Fracture Dilation**



Will be correlated to real time geophysics



Flow rate mapping with EM Contrast Agents

OFFICE OF OIL & NATURAL GAS

DE-FE0031785 Q4BP1/BP2 Work and Beyond

Q1-Q4 BP2

- Calibration of Fluid Modeling
- Design of Field Experiments,
- Field Work, Construction
- Surveys
- Data Processing/Interpretation
- Publication and Reporting

CY2021:

Collaborate with the NETL and the AEC to perform a reservoirs scale demo:

- Field test partner has been identified to demo CA based HF mapping ASAP
- Material, tool, validated models are available
- Well is pre-drilled and available
- Commercial partner has been identified
- We will be combining multiple CA properties (acoustic, EM) and microsensors to build more resolution for subsurface monitoring



Summary and Future Plans

- A patent-pending sensor system for remote monitoring of *in situ* properties of HF has been proposed, developed and is being demonstrated
- We have successfully passed the major Go-no-Go milestones for BP1
 - CA-based sensors system displays a significant and measurable change under both pressure and salinity
- A machine learning based inversion approach is under development, which promises to reduce analysis time from days to minutes
- Fluid flow modeling and recent injections at DFTS is informing a number of injection scenarios to enable perturbations of the HF at DFTS for the proposed study
- Various geophysical modalities (EM, Acoustic, Seismic) and detection configurations will be combined to monitor the extent and geophysical properties of subsurface HF environment dynamically in near real time





Appendix

These slides will not be discussed during the presentation, but are mandatory.

Organization Chart



Confidential Slide

Tasks and Status as of 7/30/20

| Task | Subtask/Milestone Description | Planned Completion Date | Percent Complete as of 6/30/2020 | Verification Method/ Deliverables | | Comments |
|------|---|-------------------------------|--|--|----------------|---|
| 1.0 | Project Coordination and Communication and Reporting | 9/30/2020 | 75% | PMP, DMP, TMP Quarterly Reports, Continuation Application | 1. 2. 3. | PMP and DMP was updated. TMP will be updated and will be submitted in BP2 Q2 BP1 reports were submitted to DOE. Two more reports remain. |
| 2.0 | Workforce Readiness for Technology Deployment | 10/31/2020 | | Presentation file BP2 deliverable | 1. | BP2 deliverable will be submitted in Q1BP2. |
| 3.0 | 1. Initial Lab Studies for HP/HS Responsive EAP | 09/30/2020 | 75% | Q2 & 3 Reports | 1. | Initial lab studies have demonstrated that both pressure and salinity cause a marked impact on electric response. |
| | 2. Lithology and Cores Studies | 07/30/2020 | 95% | Q1, 2, & 3 Reports | 2. | We completed an extensive core characterization report describing 249ft (76m) of core from the DFPS. |
| 4.0 | 1. VSP/seismic RTM Validation | 06/30/2020 | 6/30/20 | Year 1 Topical Report | 1. | RTM code has been validated. |
| | 2. Joint VSP/Seismic and EM Inversion | 09/30/2020 | 75% | | 2. | We tested our seismic modeling software for generating synthetic data for assessing the feasibility of the proposed workflow using a 12.5- to 2 - cm fracture. Fracture is detectable at 200 Hz. |
| 5.0 | Field Design: Fluid Flow Modeling EM Sensitivity Analysis VSP or Seismic Sensitivity Analysis | 09/30/2020 | 80% | Year 1 Topical Report | 1. 2. 3. | A fluid flow model has been built and refined using prior fluid injection history from DFPS. Multiple simulations will be completed for different field injection scenarios. Our EM sensitivity analysis has shown that even a 5% change in conductivity of the EAP-filled fracture can result in >1% contrast in the signal. We created velocity and density models for seismic modeling and examined the seismic response to the fracture. |

Confidential Slide



Fossil

Energy