

Design and costing of ION's CO₂ capture plant retrofitted to a 700 MW coal-fired power plant

2021 NETL CO₂ Capture Technology Project Review Meeting

August 3, 2021

Project: Commercial Carbon Capture Design and Costing: Part 2 (C3DC2) - DE-FE0031840

Andy Awtry, Ph.D. – VP Engineering

ION Clean Energy, Boulder, CO, USA

ION's CO₂ Capture Technology Development

Accelerated development path leveraging existing research facilities



2010

**ION Engineering
Lab-pilot**
0.001 MWe
Boulder, CO, USA



2012

**Univ. of N. Dakota
EERC**
0.05 MWe
Grand Forks, ND, USA



2015

**National Carbon
Capture Center**
0.5 MWe
Wilsonville, AL, USA



2016 - 2017

**CO₂ Technology
Centre Mongstad**
12 MWe
Mongstad, Norway




2018 - 2021

**Design & Costing
Commercial Retrofit**
300 & 700 MWe
Sutherland, NE, USA

ION Technology Overview

- Proprietary Solvent-based Technology
 - Liquid absorbent-based capture
 - Low aqueous
 - Worldwide Patents
- Established Engineering Process
 - Learnings from Boundary Dam
 - Learnings from Petra Nova
- Basis of Performance
 - Fast kinetics (on par or faster than MEA)
 - Working capacity (higher than MEA)
 - Low heat capacity (much lower than MEA)
 - < 1,090 Btu/lb CO₂ (2.5 MJ/kg CO₂)



ION Technology Overview

Value Added

- High Capture Efficiency
 - Up to 96% CO₂ Capture
- Design System for CAPEX/OPEX savings
 - Smaller absorber column(s) vs higher carrying capacity
 - Pumps/HEXs are smaller due to lower liquid flow rates
- Low regeneration energy requirement
 - Low parasitic load
 - Low steam demand – reduction in plant de-rate if integrated into the steam cycle
- Demonstrated lower corrosion rates than MEA
- Demonstrated lower total emission rates than MEA

Nebraska Public Power District

Host Site – Gerald Gentleman Station

- Located in Sutherland, Nebraska
- Largest generating station in Nebraska
- Two units with total capacity of 1,365 MW
 - Unit 1 – 1979 – 665 MW
 - Unit 2 – 1982 – 700 MW
- Burns Powder River Basin Coal




Commercial Carbon Capture Design & Costing

(C3DC) DE-FE0031595 – Previous Award, Completed Q4 2019

- Objective: Retrofit a Carbon Capture System at a power station
 - Nebraska Public Power District's (NPPD) Gerald Gentleman Station (GGS)
 - 300 MWe Slipstream for carbon capture
 - Ownership model: NPPD owns and operates the capture island
 - Design Basis: CO₂ product for enhanced oil recovery (not regulatory driven)
- Class 3 (AACE) Cost Estimate
 - Cost Estimate is -20% to +30%
 - Completed about 20% of Engineering Effort
- Completed 18mo Project in Q4 of 2019

Commercial Carbon Capture Design & Costing Study

A 3D architectural rendering of a commercial carbon capture plant. The facility features a tall, grey, cylindrical smokestack on the left, a large yellow rectangular building in the center, and several smaller grey cylindrical storage tanks. A network of grey pipes and structural steel frameworks connects the various components. In the foreground, a white tanker truck is parked on a dirt road. The background shows a vast, flat landscape with green fields and a clear blue sky.

	Value	Units
Slipstream	300	MWe
EPC Capital Cost	\$438,000,000	\$
Loan Term	20	years
Interest Rate	4.5%	%
Total OPEX	\$28,200,000	\$/yr
Total Annual Cost	\$61,800,000	\$/yr
Total Annual CO ₂ Production CF	1,900,000	tonne/yr
Cost of CO₂ Capture	\$32.50	\$/tonne

COMMERCIAL CARBON CAPTURE DESIGN & COSTING STUDY: PART 2

DE-FE0031840

Commercial Carbon Capture Design & Costing Study: Part 2

(C3DC2) DE-FE0031840

- Retrofit a Carbon Capture System at an existing power station
 - Nebraska Public Power District's (NPPD) Gerald Gentleman Station (GGS)
 - **700 MWe carbon capture system (2x 350 MWe trains)**
 - **Ownership model: Capture System is 3rd Party Owned and Operated**
 - Design Basis: CO₂ product for EOR (not regulatory driven)
- **Class 2 (AACE)** Capital Cost Estimate
 - Estimate Accuracy Range: **-15% to +20%**
 - Complete about **50-60%** of Engineering Effort
- 18-month project; to be completed in Q1 of 2021
- \$5.8M project budget
 - \$4.6M DOE-NETL
 - \$1.2M ION & Partners

C3DC2 Study

Project Team and Roles



ION Clean Energy

- Technology Developer
- Process Design and Project Management



Nebraska Public Power District

- Host Site (GGS)
- Power Generation Engineering, Operational and Financial Expertise



Sargent and Lundy

- Balance of Plant (BOP) Engineering
- Overall Cost Estimate Development
- Constructability Review
- Construction Cost Estimating



Koch Modular Process System

- Carbon Capture pilot experience and expertise
- Capture Process Oversight, Design and Costing



Siemens

- Compressor Vendor


ProTreat® Process Model

ION CO₂ Capture Process

Key features of ION process compared to 'common' MEA-designed plant

- Cold-Rich By-pass
- Optimized lean rich cross exchanger (LRXC) design
- Caustic addition to DCC to act as SO_x Polishing Scrubber
- Compressor Selection

ProTreat output provides stream tables, key performance indices, and steam, cooling and electrical duties



System Design

700MWe CO₂ Capture Plant

- Capture System Design
 - 2x 50% trains for the Capture Island
 - 2x 50% on major pieces of equipment to assist in turndown and provide some risk mitigation
 - Designed for operation at full load, and track plant load to maximum turndown
 - Designed for 90% capture of CO₂; resulting in >95% capture at turndown
 - CO₂ product at historic plant CF (2018-2019): 4.3M tonnes of CO₂/yr
- BOP Design
 - Steam sourcing from GGS2 steam cycle
 - Cooling water from a hybrid system

C3DC2



C3DC2



C3DC2



C3DC2



Bioenergy w/ Carbon Capture & Sequestration (BECCS)

700MWe (4.3M TPA) CO₂ Capture Plant



- Overall cost evaluation for potential net zero and net negative emissions
- Engineering Design
 - Biofuel Sourcing
 - Corn Stover vs Eastern Red Cedar
 - Pellets vs Bales
 - Gasifier Design
 - Design for 10-15% coal offset
 - Evaluate boiler performance
 - Balance of Plant Design
 - Evaluation of capture performance on the existing CO₂ capture process design



Bioenergy w/ Carbon Capture & Sequestration (BECCS)

BECCS General Arrangement Drawing

- Corn Stover Pellets delivered by truck
- Gasifier converts pellets to syngas
- Boiler mods and resulting flue gas by B&W



Bioenergy w/ Carbon Capture & Sequestration (BECCS)

Flue Gas Comparison and CCS Performance

- Max Design is the Base Design Case, assuming full load of the power plant
- BECCS case replaces 10% of the coal with the syngas from the gasifier
 - 5.5% reduction in CO₂ flow to the capture island
 - Increase in capture efficiency to 93.3% (holding steam consumption constant)
 - 1.6% reduction in CO₂ product flow
 - Reduced CO₂ by 98% relative to coal emissions
 - CO₂ reduction >100% with 10% increase in packing and 23% more plates in LRXC

Parameter	Units	Max Design Value	BECCS (Corn Stover)	BECCS (Corn Stover)
DCC Inlet Conditions (1x50% train)				
Temperature	°F	145	144	144
Pressure	psia	13.75	13.75	13.75
O ₂ Concentration	vol %	4.34	5.43	5.43
CO ₂ Rate	vol %	11.5	10.78	10.78
	lb/hr	711,831	672,890	672,890
Flue Gas Flowrate	acfm	1,107,000	1,114,000	1,114,000
	lb/hr	3,973,000	4,003,000	4,003,000
CO₂ Capture Performance (1x50% train)				
Capture Efficiency	%	90	93	95
CO ₂ Captured	lb/hr	638,000	628,000	640,745
L/G	lb/lb	1.93	1.81	1.81
Electrical Duty	kW	31,900	31,700	31,700
SRD	MJ/kg CO ₂	2.51	2.55	2.55
Steam Consumption	lb/hr	765,100	765,100	765,100

Cost of CO₂ Capture

Costing Basis

- Designed to produce a reliable CO₂ product stream for EOR/Sequestration; not regulatory driven CO₂ capture
- Used historical data for the unit to model cumulative captured CO₂ based on observed power plant load factor, capture plant uptime, and ambient conditions
- Calculated the cost with and without the additional flue gas pre-conditioning to isolate the cost of CO₂ capture for comparison to sites that may already have this equipment
- BECCS evaluation was performed as a sensitivity study and its incremental capital and operating expenses are separate
- 3rd Party Ownership impact on overall costing being further investigated

	C3DC1 Results (300 MWe)	C3DC2 Cost Results	
		C3DC2 Results (700 MWe)	Cooling System Selection Sensitivity
Total CAPEX	\$437,500,000	\$1,172,900,000	-\$140,300,000
Annualized CAPEX	\$33,600,000	\$90,200,000	-\$10,800,000
OPEX	\$28,200,000	\$60,700,000	-\$4,100,000
Annual Cost	\$61,800,000	\$150,900,000	-\$14,900,000
CO2 Product	1,900,000	4,310,000	4,310,000
Cost of Capture	\$32.53	\$35.01	-\$3.46

Acknowledgement and Disclaimer

Acknowledgement

This material is based upon work supported by the Department of Energy National Energy Technology Laboratory under cooperative award number DE-FE0031840.

Disclaimer

“This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.”



Nebraska Public Power District



U.S. DEPARTMENT OF
ENERGY

ION
CLEAN ENERGY



Thanks

C3DC2 Team:

ION, NPPD, S&L, KMPS, Siemens

BECCS TEAM:

Trestle Energy, Frontline BioEnergy, Babcock & Wilcox

Department of Energy:


Commercial Carbon Capture Design & Costing Study: Part 2

(C3DC2) DE-FE0031840

#	Task	Milestone Title / Description	Completion Date	Verification Method
M1	1.0	DOE Kickoff Meeting	12/5/2019	Meeting Held
M2	1.0	Updated PMP	11/7/2019	PMP Transmitted to DOE FPM
M3	2.0	Basis of Design for Project Finalized	1/10/2019	Meeting Held w/ Results Project SharePoint Site; Completion Memo to DOE
M4	3.0	Preliminary Design Review Complete	3/30/2020	Meeting Held w/ Results Project SharePoint Site; Completion Memo to DOE
M5	4.0	Critical Design Review Complete	9/30/2020	Meeting Held w/ Results Project SharePoint Site; Completion Memo to DOE
M6	5.4	HAZOP Complete	11/24/2020	HAZOP Report Completed
M7	6.0	Overall Cost Estimate and Cost of Capture	1/12/2021	Meeting Held w/ Results Project SharePoint Site; Completion Memo to DOE
M10	4.2	BioMass Co-firing BOP Design	4/1/2021	Meeting Held w/ Results Project SharePoint Site; Completion Memo to DOE
M8	7.0	Front-End Engineering Design (FEED) Report	9/1/2021	Report Delivered to DOE/NETL
M9	7.0	Final DOE Report & Presentation	9/30/2021	Report Delivered to DOE/NETL

Commercial Carbon Capture Design & Costing Study: Part 2

(C3DC2) DE-FE0031840



Commercial Carbon Capture Design & Costing Study: Part 2

(C3DC2) DE-FE0031840

	Task Name	Duration	Start	Finish	Half 2, 2019					Half 1, 2020					Half 2, 2020					Half 1, 2021					Half 2, 2021										
					J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O			
1	▣ C3DC2 Project - FEED Study	526 days	Mon 9/2/19	Thu 9/30/21																															
2	▸ 1.0 Project Management and Planning	460 days	Mon 9/2/19	Wed 6/30/21																															
20	▸ 2.0 Overall Project Design Basis	361 days	Thu 10/31/19	Tue 4/13/21																															
51	▣ 3.0 Process Design - CO2 Capture Island Design	290 days	Mon 9/30/19	Wed 11/25/20																															
52	▸ Preliminary Design - CO2 Capture Island	254 days	Mon 9/30/19	Tue 10/6/20																															
103	M4: Preliminary Design Review	0 days	Fri 4/24/20	Fri 4/24/20																															
104	▸ Detailed Design - CO2 Capture Island	159 days	Thu 4/16/20	Wed 11/25/20																															
136	▣ 4.0 Engineering & Design - Integration and BOP	340 days	Fri 12/20/19	Fri 4/30/21																															
137	▸ Detailed Design - Integration and BOP	340 days	Fri 12/20/19	Fri 4/30/21																															
383	M5: Critical Design Review	10 days	Wed 9/16/20	Tue 9/29/20																															
384	▸ BECCS - Biomass Co-firing	121 days	Thu 11/5/20	Thu 4/29/21																															
430	▸ 5.0 Studies and Investigation	412 days	Tue 12/3/19	Fri 7/23/21																															
540	▸ 6.0 Cost Estimate	199 days	Tue 7/21/20	Fri 4/30/21																															
574	▣ 7.0 Reporting	158 days	Tue 2/23/21	Thu 9/30/21																															
575	▸ M8: Front-End Engineering Design (FEED) Report	137 days	Tue 2/23/21	Wed 9/1/21																															
583	▸ M9: Final DOE Project Report	71 days	Thu 6/24/21	Thu 9/30/21																															
589	▸ BECCS Reporting	70 days	Thu 4/1/21	Wed 7/7/21																															

