

# Full-Scale FEED Study For a 816 MWe Capture Plant at the Prairie State Generating Company Using Mitsubishi Heavy Industries of America Technology



***Kevin C OBrien, PhD***  
***Director, Illinois Sustainable Technology Center***  
***Director, Illinois State Water Survey***  
***Prairie Research Institute***  
***University of Illinois at Urbana-Champaign***

***Jason Dietsch***  
***Assistant Research Engineer***  
***Prairie Research Institute***  
***University of Illinois at Urbana-Champaign***

***DOE/NETL 2021 Carbon Management and Natural Gas & Oil Research Project Review Meeting***  
***Pittsburgh, PA / August 2, 2020***



## Disclaimer

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

## Cooperative Agreement No. DE-FE0031841


### PROJECT OVERVIEW

**Funding: \$17,509,676**

DOE: \$14,004,676

20% Cost Share: \$3,505,000 (PSGC)


Work Period: 1 Jan 2020 – 31 Dec 2021



### PROJECT OBJECTIVES:

**Overall:** Perform a Front-End Engineering Design (FEED) study for the retrofit of the Prairie State Generation Company's (PSGC) coal-fired power plant with post-combustion carbon capture. The FEED study will outline the use of Mitsubishi Heavy Industries' (MHI) Advanced KM CDR Process™ to retrofit one of PSGC's two generating units (approximately 816 MWe). The FEED study will enable PSGC to move forward with actual build/operate in future work.


# Project Team Management Structure




FRONT-END ENGINEERING DESIGN STUDIES FOR CARBON CAPTURE  
SYSTEMS ON COAL AND NATURAL GAS POWER PLANTS

# TECHNICAL BACKGROUND

# Mitsubishi Heavy Industries' (MHI) Advanced KM CDR Process™



# Project Technology Development 1990 - present



# Opportunity to Evaluate Improved Solvent (KS-21)

Parameters Relative to KS-1™	KS-1™	KS-21™
Volatility	100	50-60
Thermal degradation rate	100	30-50
Oxidation rate	100	70
Heat of absorption	100	85

## Thermal stability

- Reduce thermal degradation and allow higher stripping T and P, reducing compression work

## Oxidative stability

- Potentially more tolerant to impurities
- Reduce amine oxidation and HSS formation rate

## Volatility

- Reduce amine loss from emission and cost of water wash system
- Steam consumption savings outweigh cost increases due to higher solvent circulation



Key Activity

# TECHNICAL APPROACH / PROJECT SCOPE

# Project Tasks

Task #	Task
1.0	Project Management and Planning
2.0	Front-End Engineering Design (FEED) Study
2.1	Design Basis
2.2	Preliminary Engineering
2.3	ISBL Detailed Engineering
2.4	OSBL Detailed Engineering
2.5	Studies and Investigations
2.6	Cost Assessment
3.0	Regulatory and Permitting at Host Site
4.0	Final FEED Study Package

# Project Milestones

Task / Subtask #	Deliverable Title	Due Date
<del>1.0</del>	<del>Project Management Plan Update</del>	<del>3/3/2020</del>
<del>2.0</del>	<del>Design Basis Document Complete</del>	<del>10/30/20</del>
<del>2.0</del>	<del>Report on Utility Requirements</del>	<del>11/19/20</del>
<del>3.0</del>	<del>Preliminary Regulatory and Permitting Pathway</del>	<del>2/18/21</del>
<del>2.0</del>	<del>HAZOP Review</del>	<del>4/30/21</del>
<del>2.0</del>	<del>Impact on Kaskaskia Watershed Document Complete</del>	<del>5/28/21</del>
<del>2.0</del>	<del>Constructability Review Complete</del>	<del>6/30/21</del>
<del>3.0</del>	<del>Regulatory and Permitting Analysis Complete</del>	<del>8/6/2021</del>
<del>2.0</del>	<del>Detailed Engineering Document Complete</del>	<del>11/30/21</del>
<del>4.0</del>	<del>Final Report Submitted</del>	<del>12/31/21</del>
<del>4.0</del>	<del>FEED Study Package Complete</del>	<del>12/31/21</del>

# Risk & Mitigation Strategy

Description of Risk	Probability	Impact	Risk Management Mitigation and Response Strategies
<i>Technical / Scope Risks</i>			
Insufficient water supply	Low	Low	<ul style="list-style-type: none"> <li>Studies outlined in SOPO - explore various options to source the cooling and makeup the cooling and makeup water demands of the capture system including supply from host site vs. an external source.</li> </ul>
Uncertainty associated with the need of identifying steam and electric sourcing	Low	Low	<ul style="list-style-type: none"> <li>Studies outlined in SOPO - explore options to address these issues. Can apply learnings from Petra Nova Project.</li> </ul>
<i>Costs / Schedule Risks</i>			
Project cost and/or schedule overruns	Low	High	<ul style="list-style-type: none"> <li>Team has previous experience conducting FEED studies on budget and on time</li> </ul>
<i>Management / Planning Risks</i>			
Availability of key personnel for project	Low	Medium	<ul style="list-style-type: none"> <li>Commitments received from partner organizations</li> </ul>
Uncertainty of permitting agencies and timelines	Low	Low	<ul style="list-style-type: none"> <li>Meetings with relevant agencies for previous projects enabled baseline knowledge for timelines and requirements</li> </ul>
<i>EH&amp;S Risks</i>			
Air (amine and CO <sub>2</sub> ) emission management	Low	Low	<ul style="list-style-type: none"> <li>Leverage experience from Petra Nova Project to meet strict VOC permit requirements</li> <li>Built into ISBL design criteria</li> </ul>
Wastewater stream management	Low	Medium	<ul style="list-style-type: none"> <li>Studies outlined in SOPO – explore options to address these issues</li> </ul>
<i>External Factors Risks</i>			
Negative stakeholder response to FEED study	Low	Low	<ul style="list-style-type: none"> <li>Discussions with elected officials have received very positive support</li> </ul>
<i>Financial Risks</i>			
Cost share for project not obtained or insufficient	Low	High	<ul style="list-style-type: none"> <li>Cost share authorized by host site's Board of Directors</li> <li>Host site is financially stable</li> </ul>

Key Activity

# PROGRESS AND CURRENT STATUS

# Carbon Capture Facility Location



Source: Google Earth



# Carbon Capture Facility Location



# Carbon Capture Facility Location





# Duct Tie-in



# OSBL

- Duct Tie-in
- Ductwork to facility
- Auxiliary Boilers
- Cooling Tower
- Administration Building
- Water Treatment
- Wastewater Treatment
- Raw Water Pipeline
- Raw Water Storage Pond
- Storage Tanks
- Utility Systems
- Fire Protection Layout
- Roads and Storm Drainage
- Site Lighting

# ISBL

- Draft Fan
- Flue Gas Quencher
- Absorber
- Regenerator
- Product Compressor

# **Studies**

## **Steam and Electric Sourcing Study**

- Auxiliary Boiler
  - Purchasing power from the grid

## **Transportation Study**

- Identified and evaluated transportation routes to bring equipment and modules to the site

## **Water Supply Study**

- Draw raw water from the Kaskaskia River
- Build a storage pond for drought conditions

# **Studies**

## **Water and Wastewater Treatment Study**

- Selected the systems for treatment of incoming raw water and exiting wastewater

## **Cooling Water System Study**

- Closed loop system with draft cooling tower

## **Compressor System Overpressure Relief**

- Evaluation of overpressure relief locations along the compression path

# Studies

## **Constructability Review**

- Evaluate and identify construction access, lay-down areas, lift plans, and sequencing of construction work

## **Project Execution Schedule**

- A detailed project schedule will be developed to aid in the overall construction timeline and costs associated with the contractors

## **Hazard and Operability (HAZOP) Review**

- An in-depth examination of the ISBL section to identify and evaluate any process or equipment risks. Recommendations for changes to the system design or operation will be made based on the HAZOP findings

Key Activity

# REMAINING TASKS

# Moving Forward

- Continued Review of Design to Identify Ways to Lower Costs
- Contracting/Procurement Strategy
- Project Capital Cost Estimate (+/- 15%)
- Completion of Regulatory and Permitting Analysis
- FEED Study Package Completed
- Submission of Final Report

# Acknowledgements

Name	Organization
Andrew Jones	National Energy Technology Laboratory / U.S. Department of Energy
Don Gaston, Javier Arzola, Rich Meyer	Prairie State Generating Company
Kevin O'Brien, Yongqi Lu, Vinod Patel, Stephanie Brownstein, Jason (Zhenxing) Zhang, Jason Dietsch	Prairie Research Institute / University of Illinois Urbana-Champaign
Tim Thomas, Tiffany Wu, Cole Maas	MHIA
Keisuke Iwakura, Shintaro Kiuchi	MHIENG
Matt Thomas, Alan Donovan, Bob Slettehaugh, Bryan Lofgreen	Kiewit Engineering Group
Paula Guletsky, Anthony Baker	Sargent & Lundy

**This project is supported by the U.S. Department of Energy / National Energy Technology Laboratory (DOE/NETL) through Cooperative Agreement No. DE-FE0031841**