Engineering-Scale Test of a Water-Lean Solvent for Post-Combustion Capture DE-FE0031945

Joseph Swisher Senior Technical Leader Advanced Generation & Carbon Capture and Storage

U.S. Department of Energy National Energy Technology Laboratory Carbon Management and Natural Gas & Oil Research Project Review Meeting Virtual Meetings August 2 through August 31, 2021



 Image: margin base
 Image: margin base

 www.epri.com
 © 2021 Electric Power Research Institute, Inc. All rights reserved.

Project Overview

Project period October 2020 to March 2024


Funding	Federal	\$4,129,607							
	Cost share	\$1,032,411							
	Total	\$5,162,018							

Organizations Electric Power Research Institute Pacific Northwest National Lab. RTI International Paul M. Mathias Consulting, LLC Gradient Worley Southern Company Services (NCCC) **Objective** – Perform extended test campaigns on coal and natural gas flue gases with the EEMPA solvent operating at the ~0.5 MWe-equivalent scale for both coal and gas to verify its favorable performance characteristics while evaluating the environmental, health and safety (EH&S) risks of the technology and quantifying its potential to lower the cost of CO₂ capture.

N-(2-ethoxyethyl)-3-morpholinopropan-1-amine








EEMPA can achieve low specific reboiler duties

The favorable thermal performance is attributable to


- The low water content (around 2 wt.% or less) meaning less water to vaporize
- A shift in the ionic character of the solvent with higher temperature, disfavoring the CO₂-bound ionic species
- SRDs down to 2.0 GJ/tonne have been observed in experiments. Cost-optimal designs for coal indicate 2.34 GJ/tonne is achievable.





More about **EEMPA**

- Strengths
 - Single-component, miscible in water
 - Low viscosity gain upon reaction with CO₂
 - Low surface tension
 - Compatible with potentially cheaper materials of construction (e.g., plastics)
 - Low corrosivity
 - Good thermal and chemical stability
 - Potential for advanced heat integration and regeneration steps that could save costs (e.g., flash regeneration)
- Challenges
 - Potentially costly, and large-scale production yet to be demonstrated
 - Imposes need for careful control of the process water balance



Comparison of thermal degradation of EEMPA with MEA under similar experimental conditions. EEMPA achieved 90% slower degradation than MEA under comparable experimental conditions


EEMPA has several characteristics that make it a promising post-combustion capture solvent



First testing milestone: lab-scale testing (FWP-70924)


- Conducted at PNNL on the Laboratory Continuous Flow
 System
- Accumulated 40 hours on simulated flue gas
- Achieved a 96% capture rate
- Observed a reboiler duty as low as 2.0 GJ/tonne CO₂

www.epri.com




Next stage: bench-scale testing (FWP-70924; FWP-76949)

- Conducted using RTI's Benchscale Gas Absorption System
- Accumulated 137 hours of testing
- Achieved ~90% capture for over 40 hours of the testing
- Tested three regeneration methods
 - Reboiler
 - interstage heaters
 - 2-stage flash





EEMPA exhibited good stability during bench-scale test



7

The current project: engineering scale testing

Scope

- Develop a route to produce larger volumes of EEMPA
- Plan a test using the Pilot Solvent Test Unit (PSTU) at the National Carbon Capture Center
- Modify PSTU equipment
- Manufacture the required quantity of solvent
- Run test campaigns on coal and natural gas flue gases
- Conduct a final TEA and environmental, health, and safety (EH&S) risk assessment

Schedule and key milestones

- Budget period 1 (Oct 2020 – Dec 2021)
- Budget period 2 (Jan 2022 – Dec 2022)

Budget period 3

(Jan 2023 – Mar 2024)


- Develop route for synthesis meeting \$10/kg cost target
- Execute host site agreement
- Manufacture required solvent volume
- Made equipment modifications
- Develop test plan
- Min. 2 month coal campaign
- Min. 2 month natural gas campaign



Recent progress

Initial techno-economic analysis

- Conducted on Revision 4 basis (NETL-PUB-22638, December 2018 costs)
- Considered 90% capture from both a supercritical coal (SCPC) and natural gas combined cycle (NGCC) plants using a simple stripping configuration
- EEMPA-based capture estimated to achieve 64% and 60% increase in the levelized cost of electricity compared to plants without capture




Sales price = cost of CO_2 captured Emissions penalty = cost of CO_2 avoided



Recent progress


Progress on synthesis

- Present one-step synthesis has a high yield, but relies on reagents that may be hard to source at lower prices
- Current reagents are available at the needed volumes
- Producers have been identified with sufficient resources for manufacturing
- Multiple routes to EEMPA are currently being investigated that would allow use of less expensive raw materials



Test planning

- Developing plan for monitoring viscosity, water content, and CO₂ loading to aid process control.
- Raman could be used to track CO₂ loading directly and in real time.






Recent progress

Test planning

- Aspen Plus models are being developed and verified to predict performance in PSTU equipment.
- Developing plans and equipment specifications for
 - Heat exchanger and chiller for the cooler-condenser
 - Plastic packing for the absorber
 - Flash regeneration using the existing Advanced Flash Stripper equipment





Future work

Budget period 2 (Jan 2022 – Dec 2022)

- Installation and modification of equipment
- Manufacture of solvent
- Detailed test planning

Budget period 3 (Jan 2023 – Jun 2024)

- Commissioning and parametric testing
- Coal flue gas campaign
- Natural gas flue gas campaign
- Final TEA
- Final EH&S risk assessment

Summary

- EEMPA is promising in several respects
 - It has been demonstrated at the lab & bench scale
 - Low reboiler duty confirmed at both scales
 - Reagents for manufacture of needed quantities can be procured
 - Host site has flexibility to work with optimal configuration
- Progress is being made on developing a larger-scale synthesis method
- Working to develop process modifications to help maintain the water balance of a water-lean solvent

www.epri.com



Acknowledgment

This material is based upon work supported by the Department of Energy under Award Number DE-FE0031945.

Disclaimer

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.




Appendix



www.epri.com

Project organization chart with key personnel



Gantt Chart

							ч		T						- T	· ·		- T	
•	1/29/2021			Project ord		0 1 2		6 7 8	9 10 11	1 12 13 14		17 18 19 2	20 21 22 23		26 27 28 29		32 33 34 35		39 40 41
Project duration	38 months 17 days				ndar Month	J F M	A M J	J A S	O N D) J F N	MAM	JJA	S O N D	JF	M A M J	J A	S O N D		A M J
Project end date	3/31/2024			Calend	dar quarter	Q1-2021	Q2-2021	Q3-2021	Q4-2021	Q1-2022	Q2-2022	Q3-2022	Q4-2022	Q1-2023	Q2-2023	Q3-2023	Q4-2023	Q1-2024	Q2-2024
. –		Lead	_	_	Duration		1	1											
	Task/Subtask Title	organization			(months)		<u> </u>	<u> </u>	<u> </u>										
-	Engineering Scale Test of a Water-Lean Solvent		1/29/2021		39				_			_		_		_			
Task 1.0	Project management and planning	EPRI		3/31/2024	39														
	Project manamgent Plan updates	EPRI		3/31/2024	39	Δ		PMP	updated										
	Technology Maturation Plan	EPRI		4/30/2021	3				spance			_							
Subtask 1.3	Initial Techno-economic analysis and EH&S review	EPRI	2/1/2021	4/30/2021	3					- · · ·	al TEA and E&								
										risk assessn	ments comple	ted							
-	Solvent scale-up and design of engineering scale test equipment			12/31/2021	11		Bud	dget Period 1											
Task 2.0	Scale-up of solvent production	PNNL		12/31/2021	11							1	New synthesis r						
	Determine best synthesis route for larger scale	PNNL, RTI		9/30/2021	8				A				deteremined	d.					
Subtask 2.2	Setup process for larger-scale synthesis	PNNL, RTI	7/1/2021	12/31/2021	6					4									
										-			New pro	ocess detern	nined,				
Task 3.0	Design of Engineering Scale Test Equipment	EPRI		12/31/2021	9									facturer ide	ntified.				
Subtask 3.1	Adapt models to evaluate test design	PNNL, RTI	4/1/2021	8/30/2021	5				_		Go 1: Solvent								
Subtask 3.2	Design and specify equipment	PNNL, RTI		10/31/2021	4						cture and equi								
Subtask 3.3	Develop construction cost and plan	PNNL, RTI	9/1/2021	12/31/2021	4		!			🔺 modifica	ation meet bu	dget.							
										_									
Task 4.0	Host site planning	EPRI	4/1/2021	12/31/2021	9					Г	City 1 - 1								
Subtask 4.1	Conduct design hazard review	PNNL, RTI	4/1/2021	9/30/2021	6			4	4		Site host agr								
Subtask 4.2	Exectute host site agreement	EPRI, NCCC		12/31/2021	7					A	executed. Pe	-		1					
Subtaks 4.3	Permitting	EPRI, NCCC	9/1/2021	12/31/2021	4					1 L	plan devel	iopeu.			Solven				
		-		<u> </u>											manufacture delivered to b				
-	Solvent manufacture and test facility modification			12/31/2022	12				1		Budge	et Period 2		<u> </u>	delivered to h	iust site.			
Task 5.0	Manufacture of solvent	RTI		12/31/2022	12	Ne	w equipment	and											
	Procurement of raw materials	RTI		4/30/2022	4		fications engine		1					Go-No	Go 2: Solvent				
Subtask 5.2	Production and delivery to host site	RTI	3/1/2022	12/31/2022	10]						actured and				
		_		10/5											nent modificatio	ons			
Task 6.0	Construction at host site	EPRI		12/31/2022	12			Design Haz						comple	٠te.			installation and	1
Subtask 6.1	Permitting	EPRI, NCCC	1/1/2022	6/30/2022	6		L	Review comp	leted.								modificati	on complete.	
Subtask 6.2	Procurement of equipment	EPRI		9/30/2022	9				-				_						
Subtask 6.3	Construction activities at the host site	NCCC	3/1/2022	12/31/2022	10									4					
Took 7.0	Test alon development	F001	7/4/2022	12/24/2022	~														
Task 7.0	Test plan development	EPRI	7/1/2022	12/31/2022	6				<u> </u>	ant hat 1	ate			4					
Budget Devied 2	Testing and data analysis		1/1/2022	2/21/2024	15					est batch mee						daet Derie 1	2		
-	Testing and data analysis	PNNL		3/31/2024	15 12				acc	ceptance crite	ciid.	Test plan co	ompleted.		Bu	Idget Period			
Task 8.0	Operation of Engineering Scale Test			12/31/2023	12 2						l	see plan c							
	Shakedown and commissioning	PNNL, RTI		2/28/2023	2													1	
	Parametric testing	PNNL, RTI	3/1/2023 5/1/2023	4/30/2023 7/31/2023	2												Fina	al reports delive	erea
	Coal flue gas campagin	PNNL, RTI PNNL RTI			3 4									months of			·		
Subtask 8.4	Natural gas flue gas campaign	PNNL, RTI		11/30/2023	4 1								testing	g on coal flue	e'				
Subtask 8.5	De-mobilization, removal and/or disposal of solvent	PNNL	12/1/2023	12/31/2023	Ţ								gas u	complete.					
Task 9.0	Data Analysis and Final Reporting	EPRI	7/1/2023	3/31/2024	9														
Subtask 9.1	Analysis of test campaign results	EPRI PNNL, RTI	7/1/2023	3/31/2024 3/31/2024	9									Two month	s of				
	Final TEA	EPRI, PNNL		3/31/2024 3/31/2024	9 7									sting on natu					
	Final TEA Final EH&S Assessment	EPRI, PNNL EPRI	9/1/2023 10/1/2023		6								fì	lue gas com	plete.	L			- 📥
JUDIOSK 9.3		CPRI	10/1/2023	3/31/2024	0														

17

