Concrete Thermal Energy Storage Enabling Flexible Operation without Coal Plant Cycling

10 MWh-e Pilot Plant at Plant Gaston

Scott Hume Principal Technical Leader

2021 Crosscutting Research and Advanced Energy Systems Project Review Meeting

May 11, 2021

DE-FE0031761





Acknowledgement and Disclaimer



Acknowledgement

This material is based upon work supported by the Department of Energy under DE-FE0031761.


Disclaimer

"This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."

www.epri.com

Agenda

- Background
 - Storage and TES
 - Material Testing
- CTES Pilot Plant
 - Objectives and Team
 - Operation
 - Anticipated Performance
 - TES Design
 - Layout
 - Construction
- Q&A



© 2021 Electric Power Research Institute, Inc. All rights reserved.



Project Background

Background – Energy Storage Challenge


- Intermittent renewables are driving thermal plants to provide grid support causing:
 - Damage from cycling
 - Shorter lifetimes, higher emissions per kWh, and lower profitability
- If energy can be stored:
 - Plants can operate during low/negative pricing periods without exporting power
 - Batteries can be used; however, the cost of storage is high at \$1300-2100/kW for a 4-hour system*; footprint and safety are also issues
 - Longer duration (e.g., 10+ hour storage) is also a challenge for batteries

*Energy Storage Technology and Cost Assessment. EPRI, Palo Alto, CA: 2018. 3002013957

Thermal energy storage may deliver lower-cost options



Potential TES Applications



Why Concrete?

- Potential low-cost TES system
- Solid 'thermocline' structure used to store thermal energy
- Low-cost material ~\$68/tonne
- Can be easily cast into any shape




3-block, flue gas-heated testing modules


Very durable – see 2000-year old Pantheon in Rome, built of concrete!



- Steam tubes embedded into concrete monoliths – conductive heat transfer
- No moving parts
- Modular system (41' [12.5 m])
- Road/rail transportable



Stackable and scalable



10 MWh-e scale pilot concept

Concrete Material Investigations

- High temperature testing carried out by Storworks and EPRI to verify strength and thermal properties for multiple concrete recipes
- Multiple samples were:
 - soaked at 600°C for up to 5000h
 - cycled 1500 times between 400-600°C
- Properties tested throughout
- Parallel flow stability tested
- Pilot plant designed









Concrete TES Pilot



Project Objectives

"Demonstrate concrete thermal energy storage (CTES) integration with coal power plant to enable low-cost energy storage that will eliminate the need for excessive operational flexibility"

How to achieve this?

Design, construct and test a nominal 10 MWh-e CTES pilot plant at the Alabama Power's Plant Gaston facility and conduct extensive testing of the system using supercritical steam heating and highpressure steam generation

CTES thermohydraulic model validation and operating experience

Project Team

Prime

- Electric Power Research Institute, Inc. (EPRI)
 - Scott Hume (PI), Dr. Andrew Maxson, George Booras





Sub-Contractors

- Storworks Power (Bright Energy)
 - Mike Matson, Cully Little, John Kreuder
- Southern Company
 - Josh Barron, Scotty Westbrook (site)
- United E&C (formally AECOM)
 - Steven Mastrangelo, John Kulbaga










High Level Details

- 10 MWh-e scale (>30 MWh-th)
- Location Plant Gaston
- Details (per block)
 - 0.24 MWh-e => 42 total needed
 - 7 m³, 20 tonnes
 - 30"x 36"x 41' (road/rail transport)
- TES Assembly
 - Arrangement: 7 high, 6 modules wide
 - Insulated/Cladding similar to HRSG
 - Overall size 20' tall, 22' wide, 42' long




Alabama Power's Plant Gaston

Supercritical steam source – representative of full scale




CTES Pilot Plant - Charging



Supercritical steam condensed, cooled and stored


www.epri.com




Generated steam measured and disposed

Anticipated Performance


- Supercritical steam heats TES, cooling to high pressure condensate
- For discharge, lower pressure and temperature steam generated
- Effective 'Round Trip Efficiency' is the lost work potential






Protecting the CTES foundation

- Finite element conduction model showed extensive thermal energy transmission to foundation
- Actively cooled blocks designed to intercept the heat conduction, limiting the maximum foundation temperature to <75°C (167°F)






CTES Structural Aspects

- Original design used column stacks
- For seismic structural requirements, a brick wall approach was introduced
- 6 'half blocks' needed

www.epri.com


- 1" gap between adjacent blocks
- Cooling blocks extended to increase stability



Cooling Block Structural Design

- Cooling block undergoes substantial temperature gradient during operation
- Block tendency to 'bow'
- Rebar used to hold block down to avoid uneven forces on the center of the TES modules









Detailed Design


- 76 documents produced
 - Process
 - Mechanical
 - Piping
 - Electrical
 - Instrumentation and Control
 - Specifications and Lists
- Some redesign carried out for:
 - Steam interface relocated
 - Reduced piping costs (at TES and condensate lines)



Pilot Plant Layout

- Compact design next to Unit 5 SCR
- Two main foundation pads
 - Main TES blocks, cooling fan
 - Balance of plant (condensate cooler, water tank, nitrogen blanketing, feedwater pump)
- 800 ft of 4" P91 steam pipework needed
- Local DCS with feedback to Unit 5
- Convenient access to power and boiler water








Construction Progress

UNDER

- Long lead item procurement started
- Foundation scope contacted
- TES blocks 100% manufactured
- Cooling blocks underway







Commissioning expected by the end of 2021, testing 2022

Q&A



Special thanks to Steven Markovich for his support during this endeavor!



