Engineering Scale Testing of Transformational Non-Aqueous Solvent-Based CO<sub>2</sub> Capture Process at Technology Centre Mongstad

### DE-FE0031590

Marty Lail, RTI International

U.S. Department of Energy National Energy Technology Laboratory Carbon Management Project Review Meeting August 15 - 19, 2022

## **Project Overview**

**Description:** Testing and evaluation of Non-Aqueous Solvent (NAS)-based CO<sub>2</sub> capture technology at engineering scale at TCM

### **Key Metrics**

- Energy requirements
- Solvent losses
- Solvent degradation
- Technoeconomic and EHS evaluation

### **Specific Challenges**

- Minimize rise in absorber temperature
- Operate TCM plant within emission requirements
- Optimize solvent regeneration
- Maximize NAS performance with plant modifications



## **Project Overview**

### Funding

- Total \$17,384,512
- DOE \$ 10,013,512
- Cost-share \$ 7,371,000

### **Project Performance Dates**

• August 8, 2018 – December 31, 2022

### **Project Participants**



New coal-fired power plants with  $CO_2$  capture at a cost of electricity 30% lower than the baseline cost of electricity from a supercritical PC plant with  $CO_2$  capture, or approximately \$30 per tonne of  $CO_2$  captured by 2030.

### Breakdown of the Thermal Regeneration Energy Load

a –	$C_P(T_R - T_F)$	M <sub>sol</sub>	1		$\mathbf{p}_{\mathbf{H}_20}$	1	$\Delta H_{abs,CO_2}$
$\mathbf{q}_{\mathrm{R}}$ –	$\frac{\mathbf{C}_{\mathbf{P}}(\mathbf{T}_{\mathbf{R}}-\mathbf{T}_{\mathbf{F}})}{\Delta \alpha}$	$\overline{M_{CO_2}}$	$\left[\frac{1}{x_{sol}}\right]^+$	$\Delta \Pi V, H_2 O$	p <sub>CO2</sub>	$\left[\frac{M_{CO_2}}{M_{CO_2}}\right]^{-1}$	$M_{\rm CO_2}$


Reboiler Heat Duty		isible eat	Heat of Heat Vaporization Absorp								
Solvent	С <sub>р</sub> [J/g K]	ΔH <sub>abs</sub> [kJ/mol]	ΔH <sub>vap</sub> [kJ/mol]	x <sub>solv</sub> [mol solvent/mol solution]	Δα [mol CO <sub>2</sub> / mol solvent]	Reboiler Heat Duty [GJ/t-CO <sub>2</sub> ]					
30 wt% MEA- H <sub>2</sub> O	3.8	85	40	0.11	0.34	3.75					
RTI's NASs	2.0	85	negl.	0.47	0.45	2.40					

For NAS, heat of vaporization of water becomes a negligible term to the heat duty


Process capable of achieving these criteria will have a lower energy penalty than SOTA processes

## Path to Reducing ICOE and Cost of CO<sub>2</sub> Avoided

- Primarily focus on reducing energy consumption – reboiler duty
- Reduce capital expenditure
  - Simplify process arrangement
  - Materials of construction
- Limit operating cost increase




 $^{1}$  Rochelle, G. T. Amine Scrubbing for  $\mathrm{CO}_2$  Capture. Science ~2009, 325, 1652-1654.



From lab to large scale (12 MW) demonstration through series of projects

	DOE Case 11	DOE Case 12	RTI Case 1	RTI Case 2
Description	No Capture (DOE Case 11)	CO <sub>2</sub> Capture (DOE Case 12)	RTI-Case 1	RTI-Case 2
Solvent		30 wt%MEA	RTI-NAS	RTI-NAS
SRD (GJ/t-CO <sub>2</sub> )		3.6	2.30	2.37
Regenerator pressure (bar)		1.6	1.95	4.8
Coal flow rate (lb/hr)	409,528	565 <i>,</i> 820	513,122	505,487
Gross power output (kWe)	580,400	662 <i>,</i> 800	650,110	638,080
Aux. power req. (kWe)	30,410	112,830	100,110	88,080
Net power output (kWe)	549,990	549,970	550,000	550,000
Net plant HHV efficiency (%)	39.28%	28.43%	31.35%	31.82%
Power plant cost (\$MM)	1,090	1,361	1,290	1,276
CO <sub>2</sub> capture cost (\$MM)		506	345	345
CO <sub>2</sub> compression cost (\$MM)		88	78	47
TPC (\$MM)	1,090	1,955	1,714	1668
TOC (\$MM)	1,349	2,409	2,116	2060
Total OPEX (\$MM)	199.1	297.6	270	266
COE, excl CO <sub>2</sub> TS&M, mills/kWh	80.95	137.28	122.27	119.55
Cost of CO <sub>2</sub> Capture, (\$/t-CO2)		56.44	45.66	43.30





#### TCM

- Amine plant modifications
- Leadership in detailed engineering, fabrication, and construction
- Process modeling expertise
- Excellence in operations

#### **Absorber Modifications**

- One interstage cooler
- Equipment within budget
- Control temperature bulge at top to decrease emissions

#### **Regenerator Mods**

- Higher capacity pump for reboiler
- Force recirculation due to high boiling points of solvent components 7
- Equipment within budget


# Technical Approach/Project Scope

- Confirm the potential to reduce the parasitic energy penalty by 20 to 40% compared with the MEA process
- Demonstrate the long-term process operational reliability
- Perform NAS-specific modifications to the TCM unit to show lower energy penalty
- Demonstrate NAS in the modified TCM unit for at least two months
- Verify solvent degradation rate, emissions, solvent loss, and corrosion characteristics

### **Progress and Current Status**

Task No.	MS No.	Milestone Description	Planned Completion Date	Actual Completion Date	Verification Method
1.0	1	Updated Project Management Plan (PMP)	Oct. 31, 2018	Sept. 5, 2018	PMP file
1.0	2	Project Kickoff Meeting	Oct. 31, 2018	Oct. 2, 2018	Presentation file
1.0	3	Initial TMP	Dec. 31, 2018	Dec. 31, 2018	TMP file
2.0	4	EH&S report as outlined in Appendix E of the FOA	Jan. 31, 2019	Jan. 31.2019	Topic report
3.0	5	Solvent qualification test results	July 31, 2019	January 17 <sup>th</sup> , 2020	Quarterly report
4.0	6	FEED study and cost estimate	Dec. 31, 2019	February 4 <sup>th</sup> , 2020	Quarterly report
5.0	7	Submit requisition for interstage cooler heat exchanger to fabricator	March 31, 2021	February 24, 2021	Quarterly report
5.0	8	Submission of purchase order to manufacturer for initial	May 31, 2021	June 25, 2021	Quarterly report
5.0	9	Receive forced recirculation pump for regenerator for installation at host site	November 15, 2021	January 6 <sup>th</sup> , 2022	Quarterly report
6.0	10	NAS solvent batch (75 tons) delivered to TCM site	December 31, 2021	January 31, 2022	Quarterly report
5.0	11	Commissioning of the revamped unit	January 31, 2022	March 07, 2022	Quarterly report
7.0	12	Test reports for parametric and long-term testing in revamped capture unit together with an updated State Point Data Table as defined in Appendix A of the FOA	June 30, 2022	June 30, 2022	Quarterly report
8	13	Confirmation of decommissioning and waste handling	September 30, 2022		Quarterly report
9	14	Final TEA according to DOE guidelines	December 31, 2022		Topical report
10	15	EH&S report as outlined in Appendix E of the FOA	December 31, 2022		Topical report
10	16	Maturation Plan and Technology Gap Analysis following DOE guidelines in FOA appendices	December 31, 2022		TMP file and Gap Analysis report

## **Progress and Current Status**



- By end of July over 1800 hours on stream
- Approximately 1300 hours at steady state
- 1100 hours with RFCC gas
- 700 hours with CHP gas
- TCM added time to end of campaign

10


# Progress: Start Up

#### Magnetic flow meters not registering initially

- Low conductivity of lean, anhydrous NAS solvent
- Flow meters do register flows after small H<sub>2</sub>O and CO<sub>2</sub> loading
- Added ultra-sonic flow meters as back-up to ensure desired flows are measured
- Flow meters on reboiler loop and interstage cooler loop

#### Unexpected emissions during start-up

- Initial flue gas flow through absorber (no circulation) caused emissions spike
- Emissions became lower with time
- Solvent circulation led again to higher emissions
- Identified components as minor impurities from solvent synthesis
- Levels decreased after prolonged circulation
- Became under control in ~12 hours




#### **Emissions control after start-up**


- Amine emission levels well below 1 ppm
- Aldehyde levels also below permitting limits
- Emission mitigation with acid wash is working well
- First two weeks of campaign focused on emissions

#### Foaming in the Regenerator

- During initial CHP testing observed instability in regenerator
- Suspected foaming or rapid solvent degassing
- Shifted regenerator to higher pressure
- Increased solvent loading
- Added antifoam
- Currently not experiencing foaming, but has been intermittent




### **Progress and Current Status Coal**




- Success criteria to demonstrate SRD of 2.6 GJ/tonCO<sub>2</sub> or lower on coal flue gas (13.5% CO<sub>2</sub>, 90% capture)
- Aligned with process modeling of plant configuration
- Confirms energy penalty observed in previous demonstrations

## **Progress and Current Status Coal**




- Long-term testing
- 3.2 barg regen pressure
- Elevated aerosols in June
- Reduced capture rate to stay below permitting limit
- Hypothesize that the PM levels in the gas temporarily elevated and gas became cleaner over time

### Progress and Current Status NGCC




14


## NGCC High Capture Efficiency



Reboiler duty increases with higher capture efficiency


# Ongoing collaboration with CCSI<sup>2</sup>





- Working with CCSI<sup>2</sup> on NAS thermodynamic model refinement and uncertainty quantification.
- Updated model will be validated using experimental data from TCM demonstration.
- Worked with CCSI<sup>2</sup> to develop a test matrix using the sequential design of experiment approach for testing at NGCC and coal flue gas conditions at TCM.
- Design factors of interest:
- CO<sub>2</sub> Capture: 85 95%
- Absorber L/G Ratio: 2.5 6.5 kg/kg
- Stripper Pressure: 0.9 3.2 barg

### Progress of NGCC sDOE



- TCM well-suited to perform sDOE studies
- Identified promising conditions at 90% capture and low L/G

# Plans for future testing/development/ commercialization

### Remainder of TCM test campaign

High Level Test Pla	an l	ast Up	odate: Jul	20, 2022						
RFCC										
СНР										
RHP (+ w/recycle)					Tentative	Aug 30 ->				
RHP w/dilution										
START DATE	1	5-Aug	22-Aug	29-Aug	5-Sep	12-Sep				
CALENDAR WEEK		33	34	35	36	37				
				FORCE						
		namic	Misc	Valid./	long term testing -					
Test Plan		sting	Testing	LTT	RHP w/	/recycle				
Gas in use										
CO <sub>2</sub> Concentration		3.7	3.7 - 20	13.5	13.5	13.5				
RTI person on site		JT	VG	VG	PM	PM				

- Complete dynamic testing
- Complete high removal efficiency testing
- EPRI third party verification
- Finish long-term testing

### Future Development

- Targeting opportunities to build pilots for cement, iron, and NGCC
- Engineering scale project underway for load—following NGCC (ARPA-E FLECCS)
- Engineering scale demonstration of advanced water wash for GEN1NAS
- GEN2NAS with substantially lower vapor pressure bench-scale development

### **Key Findings and Lessons Learned**


### Key Findings

- RTI GEN1NAS is able to achieve target SRD for flue gas at ~13.5% CO<sub>2</sub> concentration in the TCM amine plant with new configuration.
- Aerosol emissions can be controlled in response to fluctuations in flue gas conditions by reducing the capture efficiency
- High efficiency capture >99% from NGCC flue gas is achievable and has been demonstrated with NAS at TCM
- sDOE testing in collaboration with CCSI<sup>2</sup> under NGCC conditions has identified several promising operating conditions

### Lessons Learned

- Small concentrations of volatile impurities from synthesis can exceed emissions limits at start-up and should be purged from the solvent as a final step of manufacturing
- Certain aspects of non-aqueous solvent operation require additional modification of conventional amine plants such as the overhead condenser operation and size of heat exchanger

### **Organization Chart**



### **Gantt Chart**

															BP2	2		·								
#	Task title	Start	End	2	020	)					20	21										202	22			
		date	date	11	12	1	2	3	4	56	7	8	9	10	11	12	1	2	3	4	5 (	5 7	Ţ	9	10	11 12
1.0	Project Management and Planning	08/08/18	12/31/22												_									-		
	1.1 Test Agreement with TCM	08/08/18	09/30/20																							
2.0	EH&S and Risk Evaluation and Permitting	08/08/18	02/28/19																							
3.0	Solvent Qualification	03/01/19	01/31/20																							
4.0	Preliminary Design of a NAS Optimized System	08/01/19	07/31/20																							
	4.1 Pre-FEED	08/01/19	09/30/19																							
	4.2 FEED study	10/01/19	02/28/20																							
5.0	Revamp Implementation	10/01/20	12/31/21																							
	5.1 Detailed Engineering and Procurement	10/01/20	06/30/21																							
	5.11 Design Freeze	11/01/20	12/31/20																							
	5.12 Long Lead Items Ordered	01/01/21	02/12/21			-																				
	5.13 Long Lead Items Received	02/12/21	09/01/21				Ļ				1															
	5.2 Interstage Cooler and Recirculation Pump Install	04/01/21	12/31/21																							
	5.21 Installation and Commisisoning	09/01/21	12/15/21												-											
	5.22 Mod Project Closeout	12/15/21	12/31/21												Í		ĺ									
6.0	Solvent Production	10/01/20	12/03/21																							
7.0	Test Plan Development, Testing, Data Analysis	01/01/21	06/30/22			Ì				-					ļ											
	7.1 Modified Amine Plant Test Plan Development					ļ									ļ		1									
	7.2 NAS Modified Amine Plant Testing														Í		ĺ									
	7.3 NAS Modified Amine Plant Data Analysis																									
	7.4 EPRI Third Party Verification																	1								
8.0	Decommissioning and Waste Handling	07/01/22	09/30/22																					+		
9.0	Final TEA (550 MW Net)	07/01/22	12/31/22																							
40.0	Cost Deposit Analysis and Taskas Is an Mat Di	40104100	40/04/00																							
10.0	Cost Benefit Analysis and Technology Mat Planning	10/01/20	12/31/22																							