

National Carbon Capture Center (FE0022596)

Tony Wu

Southern Company

August 16, 2022

U.S. Department of Energy
National Energy Technology Laboratory
2022 Carbon Management Project Review Meeting



U.S. DEPARTMENT OF
ENERGY



NC
NATIONAL CARBON
CAPTURE CENTER

Nation Carbon Capture Center (NCCC)

Located in Wilsonville, AL at Alabama Power's Plant Gaston Since 2009



- A **centralized test facility** providing comprehensive support for technology testing and evaluation
 - Process, engineering, operational, analytical, troubleshooting and maintenance
- Goal: **Accelerating** technology development, scale-up, cost reduction and commercialization
 - CO₂ capture, utilization and removal
- Sponsored by **DOE/NETL, research and industrial partners**; managed by Southern Company
 - Coal, utility, research, oil & gas, policy
 - Project period: 2014-2025 (Current BP7)
 - Total \$348MM (DOE \$253.4MM / Non-DOE \$94.6MM)
 - PI: John Northington, Director of NCCC

NCCC – Technical Program



CO₂ Capture

- Capture from coal-fired power plant since 2009
- Added capture from NG-derived flue gas in 2020
- Solvent, catalyst, membrane, sorbent, hybrid technologies

CO₂ Utilization

- Added in 2020
- CO₂ to value-added products like building materials, fuels, plastics, chemicals & algae
- Evaluate additional infrastructure needed

CO₂ Removal - DAC

- Added in 2020
- Evaluate additional infrastructure as needed
- Look to collaborate w/ national labs, universities and other research institutions

DAC: Direct Air Capture

NCCC – Facility Infrastructure

Plant Gaston: Host Site

- Unit 5 (U5) -890 MWe supercritical
 - Dual fuel – coal and natural gas
 - 35,000 lb/hr slipstream flue gas (FG) from U5
 - Exhaust gas from NCCC returns to U5 stack
- Low/Medium pressure steam, water (demin, potable, filter-treated), instrument air and power
- Wastewater returns to plant Gaston for treatment and disposal

NCCC



- NG flue gas from package boiler (new 2021)
 - 40,000 lb/hr flue gas
 - Exhaust stack
- Low pressure steam, nitrogen and cooling water
- Test equipment, test bays and infrastructure




Test Facility for Post-Combustion CO₂ Capture, CO₂ Utilization and DAC Technologies

NCCC by Numbers (2011-2022)

- **80,000+ hours** of performance data collected
 - Post-combustion capture and CO₂ utilization
- **50 technologies** from **37 developers** tested or planned
 - Solvent, membrane, sorbent, phase change, & hybrid-based capture technologies
 - Chemical, fuel, concrete and algae-based utilization technologies
 - 66% are private companies
- **8 technologies** scaled up (or ready) to 10+ MW
 - Aker, Carbon Clean, ION Clean Energy, Linde, MTR, RTI, Shell Cansolv and UT Austin
- International testing collaboration: **7 countries**
 - Canada, China, Germany, India, Japan, Norway, UK






Coal FG Config

NG FG Config

PSTU: Pilot Solvent Test Unit
SSTU: Slipstream Solvent Test Unit
LSTU: Lab Scale Test Unit
PB: Pilot Bay


Operation Availability and Flexibility

Flue Gas Availability



62% more flue gas availability to support testing in 2021 since NG flue gas came online

Test Flexibility – e.g. PSTU Test



Developer can switch between coal and NG flue gas during test campaign

Test Bays and Equipment

Pilot Scale

NG Flue Gas Infrastructure

PSTU

PB3

PB2E

PB2W

Lab/Bench Scale



SSTU


Benchscale



LSTU

Current Technology Testing Portfolio

	Test Campaign (2021 & 2022)	
Tech Areas	Pilot	Lab/Bench
Solvent/ Contactor	PSTU ION <input checked="" type="checkbox"/> PSTU MEA (re-baseline) <input checked="" type="checkbox"/> PSTU Susteon Catalyst PSTU UT PZAS GTI HFM Contactor <input checked="" type="checkbox"/>	SSTU MEA (re-baseline) <input checked="" type="checkbox"/> SSTU GTI/CCSL <input checked="" type="checkbox"/> GTI/CCSL ROTA-CAP
CO ₂ Membrane		NETL OSU
Sorbent	TDA Sorbents <input checked="" type="checkbox"/>	PCI Sorbents
Others	Carbon America (Cryogenic)	
CO ₂ Utilization		SR- Ethylene <input checked="" type="checkbox"/> UCLA- Concrete <input checked="" type="checkbox"/> Helios-NRG- Algae





Color bars represent testing hours from different test campaigns.

Test Completed

Red - New Tests in 2022

- PZ w/Advanced Flash Stripper (PZAS)
 - Two test campaigns completed in 2018 & 2019
 - Current campaign funded by DOE (FE0031861), EU LAUNCH and private company
- Test Objectives
 - NGCC FG conditions: 4% CO₂, 8% H₂O, 110 °C
 - Study solvent degradations, corrosion & mitigations
- PSTU/AFS Main Modifications
 - New FG heater for temperature control
 - 2-stage washes: water and acid
 - NO₂ removal from FG
 - N₂ sparger to remove O₂ in solvent
 - Carbon filters for solvent containments removal
 - 7 new corrosion ports
- Status
 - Detail design completed; Construction in progress
 - Target Oct for commissioning




Advanced Flash Stripper (AFS) on PSTU 4th Floor

2022 Test Campaign- Solvent & Contactor


GTI HFM Contactor (FE0012829)

- High surface areas membrane contactor w/aMDEA
- Installed in Apr 2017
- Testing concluded in Mar 2022 for a total of 2,600 hours on both coal and NG FG
- Project decommissioned in May



GTI ROTA-CAP (FE0031630)

- CCSL intensified solvent → reduced energy & equipment size
- GTI rotating packed bed (RPB) absorber & regenerator → improve mass transfer
- CCSL solvent tested in SSTU (baseline) Aug-Nov, 2021
- Skids installed in Oct 2021
- Testing started in Oct 2021 and continues



Susteon Catalyst (Non-FOA)

- Patented ionic liquid catalyst in amine solvent to Improve kinetics & CO2 loading
- Similar catalyst is being tested with sorbents for DAC
- Test w/ MEA solvent in PSTU w/wo catalyst
- Testing started in Aug and continues



Pilot Solvent Test Unit (PSTU)

2022 Test Campaign- Sorbents


TDA (FE0012870)

- Alkalized alumina adsorbent- Low cost & heat of ads
- Near isothermal op at 150 °C
- Skids installed in Oct 2017
- Testing concluded in Oct 2021 for a total of ~2,900 hours on both coal and NG FG
- Project decommissioned in May 2022



PCI (SC0017221)

- Nano-sorbents on tailorable mesh substrate (Microlith®)
- High surface areas, heat & mass transfer rates
- Lower ΔP vs. pellet sorbent, and comparable ΔP vs. monoliths
- Tested at NCCC briefly in Mar 2020
- Skid installed in Mar and initial testing completed in Apr. More test is planned later this year




Nano-sorbents coated on Microlith mesh

Altex (SC0013823)

- Intensified Sorbent Process-sorbents coated on both sides of HX
- Low cost and compact Microchannel Heat Exchanger (MCHEX) wash-coated w/ PSU Molecular Basket Sorbents (MSB)
- Testing targets Jan 2023




Double-Sided Absorber – Combined Sorption and Desorption Cycles
Integrate heat of sorption with heat of desorption.



2022 Test Campaign- Membrane

OSU (FE0031731)

- Facilitated transport membrane
- CO₂ transport via reaction with amine
- CO₂ selective amine polymer layer on polymer support
- Two test campaigns completed in 2015 & 2018
- Skid delivery targets for Aug/Sep
- Testing to start in Sep



NETL


- Ongoing membrane material evaluation since 2015
- Test membranes in hollow fiber and flat sheet configurations
- Plan to restart testing in Sep



2022 Test Campaign- Other Capture & CO₂ Utilization

Carbon America (non-FOA)

- Phase changing cryogenic process - FrostCC
- FG compressed, cooled, and expanded to solidify and separate CO₂
- Skid delivery in Q4 2022
- Testing to start in Jan 2023



Helios NRG (FE0031713)

- Algae growth w/ CO₂ in FG
- Multi-stage continuous (MSC) process and closed system
- High water recycle
- Natural sunlight, top lit
- Skid installed in May
- Testing started in June and continues



Future Testing Outlook – 2023 & beyond

- Solvent (PSTU)

- EPRI/PNNL/RTI
 - ▶ Water lean solvent by PNNL
 - ▶ Plastic packing in absorber
 - ▶ Moisture control in FG is critical
- China Huaneng CERI (Clean Energy Research Institute)

- Membrane

- GTI, MTR, SUNY Buffalo

- Sorbent

- Altex
- SUNY Buffalo
- Cormetech

- CO₂ Utilization

- UCLA concrete (2nd test)
- Texas A&M algae
- Helios-NRG (2nd test)

- DAC

- Southern States Energy Board/AirCapture
- Innosepra



Acknowledgements



Nationalcarboncapturecenter.com

Special
Thanks to
NETL/DOE

Andy O'Palko
Andrew Jones
Lynn Brickett
Dan Hancu
Amishi Kumar



Acknowledgement & Disclaimer

Acknowledgment: "This material is based upon work supported by the Department of Energy under Award Number(s) DE-FE0022596."

Disclaimer: *"This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."*