Novel Transformational Membranes and Process for CO₂ Capture from Flue Gas DE-FE0031731

PI: Winston Ho, Co-PIs: Yang Han & Li-Chiang Lin William G. Lowrie Department of Chemical & Biomolecular Engineering Department of Materials Science and Engineering The Ohio State University

Carbon Management Project Review Meeting NETL, Pittsburgh, PA, August 18, 2022

Outline

- Project Overview
- Technical Background
- Accomplishments
- Summary/Outlook


Project Objective

- Develop a cost-effective design and fabrication process for a novel transformational membrane and its membrane modules that capture CO₂ from flue gas
 - 95% CO₂ Purity
 - 60–90% CO₂ Recovery


Funding and Performance Dates

- Total Budget: 07/01/2019–03/31/2023
 DOE: \$2,999,988; OSU: \$740,000; GTI: \$10,000
 (20% cost share)
 - BP1: 07/01/2019–12/31/2020
 DOE: \$1,395,100; OSU: \$348,778
 - BP2: 01/01/2021–03/31/2023
 DOE: \$1,604,888; OSU: \$391,222; GTI: \$10,000

Technical Background: Thin-Film Composite (TFC) Membrane Structure: 3 Layers Efficient and Scalable Membrane for Low Cost




Amine-Based Facilitated Transport Membrane for High Performance



Technical Approach

- BP1: 07/01/2019–12/31/2020
 - Computation-aided material design
 - Lab-scale membrane synthesis, characterization and transport performance studies
 - Design of integrated membrane skid
 - High-level techno-economic analysis
- BP2: 01/01/2021-03/31/2023
 - Laboratory-scale membrane synthesis to continue
 - Fabrication and characterization of scale-up membrane (21" wide)
 - Fabrication and evaluation of spiral-wound membrane modules (8" diameter, 22" length)
 - Fabrication and field test of integrated membrane skid
 - Update techno-economic analysis by Gas Technology Inst.
- Integrated program with fundamental studies, applied research, synthesis, characterization and transport studies, and high-level techno-economic analysis


Improved Polymer Support




 Substrate morphology has significant effect on CO₂ transport performance of composite membrane


Improved vs. Benchmark Supports


Improved






Benchmark





Better TFC Membranes by Improved Polymer Supports




Developed Membrane Outperforms Others

1000 **DE-FE0031946** (Engineering scale) **OSU Gen II** OSU Gen **US** CO₂/N₂ selectivity 67°C 67°C **77°C** 77°C Energy OSU Gen' III 100 **DE-FE0031731** (Bench scale) Robeson -ower upper bound 10 1000 2000 3000 4000 CO₂ permeance (GPU)


Smaller Footprint

21"-Wide Continuous Roll-to-Roll Support Casting Demonstrated




- Vapor-induced phase separation process demonstrated
- 1,300 ft in length per casting run

Prototype Gen III Membrane Fabricated by Roll-to-Roll Coating



Thin selective layer coated on fabricated polymer support
 ~4,200 GPU and CO₂/N₂ selectivity of ~160 at 77°C

Prototype Spiral-Wound (SW) Membrane Element Fabricated



- 8"-diameter SW element fabricated using scale-up membrane
- Element contained 41 membrane leaves for 35 m² area

SW Membrane Element in Housing











ø8" SW element fitted tightly into SS module housing


Module Tests with Simulated Flue Gases



Good Module Stability Demo with Ohio **Coal Flue Gas at U. of Kentucky Sponsored by Ohio Dept. of Development** in a Separate Project




The Proposed Process for 90% Capture




- Partial retentate recycle enables efficient separation
- Proposed membrane process does not require flue gas cooling and cryogenic distillation

Integrated Bench Skid Constructed



90+% CO₂ Capture and 95+% Purity Demonstrated with Simulated Flue Gas



Summary/Outlook

- Achieved milestones/success criteria
 - Support CO_2 permeance = 23,000-3,0000 GPU (~316,000)
 - Membrane CO_2 permeance = 3,800-4,000 GPU (~4,200)
 - CO_2/N_2 selectivity = 140–200 (~160)
 - Scale-up membranes fabricated (21" wide)
 - Prototype SW modules fabricated (Ø8" x 22" & 35 m²)
 - Integrated skid constructed (90% capture & 95% purity)

Remaining tasks

- Thorough skid testing with simulated flue gas at OSU
- 500-h skid stability with actual flue gas at NCCC
- Final TEA by GTI
- Environmental Health and Safety (EH&S) assessment

Acknowledgments

- Krista Hill, Andy Aurelio, and José Figueroa, DOE/NETL

 Great efforts and strong inputs
- Kunlei Liu & his Team, U. of Kentucky
 Model testing using Ohio coal

Financial Support DOE/NETL: DE-FE0031731

Appendix

- Project Organization
- Gantt Chart

Project Organization and Roles

Ohio State University

- Technical lead
- New membrane synthesis/characterization
- Computation-aided material design
- Prototype membrane & module fabrication
- Integrated membrane skid fabrication
- Testing of integrated membrane skid

Winston Ho, Yang Han & Li-Chiang Lin

DOE NETL

Project Officer

Krista Hill

AEP

 Consult on plant integration and demonstration considerations

Randy Keefer

GTI

 Techno-economic analysis and cost calculations

Shiguang Li

Gantt Chart

	Total Cost			1s	t Quarter		2nd	Quar	rter	3rd	Quar	ter	4th	Quarter		5	5th Quarter		6th	Qua	rter			
Task Name	of Task (\$)	Start	Finish	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
Budget Period 1	1,743,878	7/1/2019	12/31/2020																					
Task 1: Project Management and Planning	174,388	7/1/2019	12/31/2020																					
Updated PMP submitted			7/30/2019																					
Task 2: Synthesis of Improved Polymer Support	227,610	7/1/2019	3/31/2019																					
Complete polymer support synthesis and demonstrate CO $_2$																								
permeance of the support = $23000 - 30000$ GPU at ~77° C			3/31/2019																					
Task 3: Optimized Synthesis of Transformational Membrane	455,222	7/1/2019	12/31/2020					Y																
Subtask 3.1: Investigation of CO ₂ Carrier Structures	151,742	7/1/2019	12/31/2019	1				Ť																
Complete density functional theory calculations to identify																								
the structures for synthesis			12/31/2019																					
Subtask 3.2: Incorporation of Nano-fillers	151,740	1/1/2020	6/30/2020																					
Nano-fillers incorporated in the membrane			6/30/2020																					
Subtask 3.3: Synthesis of Higher MW Polyamine	151,740	7/1/2020	12/31/2020																					
Complete synthesis of 3 – 5 million MW polyamine			12/31/2020	V				V		1		1												
Task 4: Membrane Characterization	455,222	7/1/2019	12/31/2020							_														
Subtask 4.1: Morphology of Membranes	151,742		12/31/2019	4				*																
Obtain SEMs showing membrane morphologies			12/31/2019													,								
Subtask 4.2: Transport Properties	151,740	1/1/2020	6/30/2020																					
Determine CO $_2$ permeance and CO $_2/N_2$ selectivity			6/30/2020															V			V			
Subtask 4.3: Membrane Stability	151,740	7/1/2020	12/31/2020																					
Complete membrane stability testing and demonstrate CO $_2$																								
permeance = $3000 - 3800$ GPU and CO $_2/N_2$ selectivity =																								
$80 - 140 \text{ at} \sim 77^{\circ} C$			12/31/2020										1			/								
Task 5: Preliminary Techno-economic Analysis	158,886	4/1/2020	12/31/2020																					
Complete preliminary techno-economic analysis showing																								
the feasibility of $40.0 - 41.5$ /tonne CO ₂ for 90% recovery			12/31/2020																					
Task 6: Design of an Integrated Skid	227,610	4/1/2020	12/31/2020																					
Complete the design of the integrated skid			12/31/2020																					
Task 7: NCCC Site Preparation	44,940		12/31/2020															-						
Quarterly Progress Reports		10/1/2019						ļ																
Budget Period 1 Annual Report		1/1/2021	3/30/2021																					

Gantt Chart

	Total Cost			7th Q	uarter	Т	8th Qu	arter	Oth	Ouar	ter	104	h Qua	rter	11th	Quart	ter	12th Q	Iartor	12	th Or	arter	14	th Qu	arter	154	h Quar	ter			
Task Name	of Task (\$)	Start	Finish	Jan Fe																									Anr	Mov	Ium
Budget Period 2	2,006,110	1/1/2021	3/31/2023																										Арг	wiay	Juii
Task 1: Project Management and Planning	2,000,110	1/1/2021	3/31/2023														-		+		+	-		1	-	+				\rightarrow	
Subtask 1.1: State Point Data Table	200,010	3/1/2023	3/31/2023																									_			
State point data table submitted	0	5/1/2025	3/31/2023																											\rightarrow	
Subtask 1.2: Technology Gap Analysis	0	3/1/2023	3/31/2023														-													\rightarrow	—
Technology gap analysis submitted	0	3/1/2023	3/31/2023			+	-								-		-													\rightarrow	
Subtask 1.3: Environ. Health & Safety Risk Assessment	0	3/1/2023	3/31/2023		-	-	_							_	_		_	_										-		\rightarrow	
EH&S risk assessment submitted	0	3/1/2023	3/31/2023			+	-								-		-													\rightarrow	
Subtask 1.4: Technology Maturation Plan	0	3/1/2023	3/31/2023														-											ľ		\rightarrow	—
Technology maturation plan submitted	0	3/1/2023	3/31/2023			+	-								-		-													\rightarrow	
Task 8: Construction of the Bench Skid	260,440	1/1/2021	7/31/2022		_	-								_	_													ľ		\rightarrow	
Task 9: Further Optimized Membrane Synthesis	65,110	1/1/2021	3/31/2022			+	-	-	<u> </u>		_								+	-								-		\rightarrow	
· · · ·	48,830	2/1/2021	3/31/2022	-	+	+	+	+	H-						-						┢		-		+	-				-+	—
Task 10: Optimized Membrane Characterization Complete optimized membrane characterization and	48,830	2/1/2021	5/51/2022												\neg				-	_	\vdash			+		+		-+		\rightarrow	
demonstrate CO_2 permeance = $3800 - 4000$ GPU and																	- 🔻														
$CO_2/N_2 \text{ selectivity} = 140 - 200 \text{ at } \sim 77^{\circ} \text{ C}$			3/31/2022																												
Task 11: Scale-up Membrane Fabrication	179,050	3/1/2021	5/31/2022			+															-										
Task 12: Scale-up Membrane Characterization	162,770	4/1/2021	5/31/2022			+																								\rightarrow	
Complete scale-up membrane characterization and	102,770	4/1/2021	5/51/2022			-	-													-	-									-+	
demonstrate CO $_2$ permeance = $3800 - 4000$ GPU and																			Τ.												
			5/21/2022																												
CO_2/N_2 selectivity = $140 - 200$ at $\sim 77^{\circ}C$			5/31/2022		_	_														_	_				_	-					
Task 13: Prototype Membrane Module Fabrication	179,050	5/1/2021	5/31/2022		_	_	-	+										_	_	_	_				_	-					
Task 14: Prototype Membrane Module Testing Complete prototype membrane module testing and	162,770	6/1/2021	5/31/2022			_	_											-		_	-	_	-	_		-				\rightarrow	
demonstrate CO $_2$ permeance = $3800 - 4000$ GPU and																			7												
			-																												
CO_2/N_2 selectivity = 140 - 200 at ~77° C			5/31/2022				_	_											+	_	┢										
Task 15: Skid Testing with Simulated Flue Gas	97,660	8/1/2022	8/31/2022			_													_	_				_							
Complete skid testing with simulated flue gas and																						-									
demonstrate CO_2 permeance = $3800 - 4000$ GPU and																															
CO_2/N_2 selectivity = 140 - 200 at ~77°C			8/31/2022																				<u> </u>								
Task 16: Skid Installation and Commissioning at NCCC	97,660	9/6/2022	9/30/2022					-															<u> </u>		_						_
Task 17: Parametric Testing of the Skid at NCCC	97,660	9/6/2022	9/30/2022		_	+	_	-									\rightarrow		+	_	+		<u> </u>			<u> </u>		\rightarrow			—
Complete skid parametric testing with prototype modules in series and conditions for steady state operation identified			9/30/2022																					1		1					
Task 18: Continuous Steady Operation of the Skid at NCCC	260,440	9/12/2022	9/30/2022		_	+-		+							-+		+		+	_	+			-	-				_	\dashv	—
Complete steady state operation with modules in series and	200,440	7/12/2022	10/31/2022			+	_							-+	\dashv		+			+	+				-	1		-+		\dashv	
demonstrate feasibility on capture of the CO $_2$ with >95%																							1			1					
CO_2 purity for >500 h			10/31/2022																				1	1		1					
Task 19: Final Updated Techno-economic Analysis	160,800	10/1/2022			-	+	+	+						-+			+			+	-		+	+	-	-		-+		\dashv	—
Complete final techno-economic analysis showing the	100,000	10/1/2022	12/31/2022			+		+									-+			_	+		F							\rightarrow	
feasibility of $\$39.5 - 40.0$ /tonne CO ₂			12/31/2022																		1									ļ	
Task 20: Removal of the Skid from NCCC	33,250	1/1/2023	1/31/2023											-+						1			Ì	1	1	1				\neg	
Quarterly Progress Reports		4/30/2021	4/30/2023																			1		Í	1					~	~
Final Project Report		4/1/2023	6/30/2023					1														1								Z	0