

FWP-FEAA 384

# Intensified, Flexible, and Modular Carbon Capture Demonstration with Additively Manufactured Multi-Functional Device

Costas Tsouris, Josh Thompson, Gyoung Jang, Jim Parks  
Manufacturing Science Division, Oak Ridge National Laboratory

National Energy Technology Laboratory  
2022 Carbon Management Project Review Meeting

August 15-19, 2022

ORNL is managed by UT-Battelle, LLC for the US Department of Energy


# Project Overview

- **Funding provided by DOE-FECM: \$1.5M**
- **Overall Project Performance Dates:**  
January 1, 2021 – December 31, 2022 (extension will be requested)
- **Previous Project: FWP-FEAA375**  
January 1, 2020 – December 31, 2020  
Focused on validation of additively manufactured intensified device for enhanced carbon capture using a low aqueous solvent


# Motivation for this Project

- Opportunities for additive manufacturing to improve carbon capture
- Intensified packing device for flexible, modular carbon capture from point sources
  - Intensified device enhances mass transfer, just like commercial packing, and allows a third fluid (coolant) to remove the heat of reaction between CO<sub>2</sub> and amines
- Demonstrate pathway to scalability for the intensified device


# Technology Background: How the technology is envisioned to work: A Brief Review



Absorption/Desorption System at the National Carbon Capture Center (NCCC)



Column A



Intensified Device




**Motivation:** Intrastage cooling with intensified devices may have economic and operational advantages over interstage cooling


# Technology Background: Intensified Device Concept



Sulzer Structured Packing





# Technology Background: Intensified Device Design & Manufacturing





(a) Create profile of packing cross section, (b) extrude segment of packing at 45 degrees, (c) pattern into two parallel panels with gap for fluid, (d) mirror and rotate the adjacent panels, (e) pattern into a full packing, (f) cut into a cylinder, (g) create a manifold for coolant to flow into heat exchanger, (h) create inlet and outlet ports, (i) manufacture from CAD to part.

# Technology Background: Intensified Device Installation on Column



8-inch diameter column

# Technology Background: Intensified Device Installation on Column



8-inch diameter column

# Technology Background: Intensified Device Demonstration for MEA

Air Flow Rate (LPM)	CO <sub>2</sub> Flow Rate (LPM)	CO <sub>2</sub> Conc. (%)	Molar Capture Rate Before Cooling (mol/min)	Molar Capture Rate After Cooling (mol/min)	Fractional Increase (%)	Capture Efficiency (%) (Before → After Cooling)
810	90	10	2.24	2.30	2.7	59.9 → 61.2
510	90	15	2.75	2.90	5.5	73 → 77
360	90	20	2.95	3.29	11.5	78 → 88
264	90	25	3.52	3.57	4.3	94 → 98
360	40	10	1.38	1.45	5.1	83 → 87
360	63.5	15	1.53	1.77	15.7	58 → 67
360	90	20	2.95	3.29	11.5	78 → 88
360	120	25	3.07	3.28	6.9	62 → 66

Solvent flowrate: 3.2 LPM

Solvent input temperature: 70 °C

- Miramontes, E.; Jiang, E.A.; Love, L.J.; Lai, C.; Sun, X.; Tsouris, C. Process Intensification of CO<sub>2</sub> Absorption Using a 3D Printed Intensified Packing Device, *AIChE J.* **e16285**, (2020).

# Technology Background: Intensified Device Demonstration for LAS

Exp.	Solvent Condition	Solvent Flowrate (LPM)	Air Flowrate (SLPM)	CO <sub>2</sub> Flowrate (SLPM)	CO <sub>2</sub> Amount (%)	CO <sub>2</sub> output before cooling (%)	CO <sub>2</sub> output after cooling (%)	Capture efficiency (%) (before → after)	Fractional Improvement (%)*	Feed temp. (°C)	Average Temp.	
											No-cooling	Cooling
1	Pristine	3.26	510	90	13.8	2.21	0.64	84 → 95.4 (11.4↑)	13.5	59	60.7	52.2
2	Pristine	3.26	510	90	14.0	1.95	0.47	86 → 96.6(10.6↑)	12.3	52	59.6	50.4
3	Pristine	3.26	510	90	13.8	1.61	0.64	88.3 → 95.4 (7.1↑)	8.0	45	58.6	50.0
4	1 <sup>st</sup> Regen.	3.26	510	90	14.7	3.18	1.57	78.4 → 89.4(11.0↑)	14.0	41	54.5	45.3
5	2 <sup>nd</sup> Regen	3.26	608	107	13.1	3.75	2.23	71.3 → 82.9(11.6↑)	16.3	44	55.2	46.8
6	2 <sup>nd</sup> Regen + DI H <sub>2</sub> O(5L)	3.26	608	107	13.0	2.94	2.08	77.4 → 84.0(6.6↑)	8.5	44	55.4	46.9
7	3 <sup>rd</sup> Regen	3.26	425	75	13.3	1.19	0.67	91.1 → 95.0(3.9↑)	4.3	41	52.8	44.9
8	3 <sup>rd</sup> Regen	2.82	510	90	13.1	2.75	1.75	79.1 → 86.7(7.6↑)	9.7	41	53.8	46.6
9	4 <sup>th</sup> Regen	3.26	353	62	13.3	0.79	0.44	94.0 → 96.6(2.6↑)	2.8	41	49.8	39.7
10	4 <sup>th</sup> Regen	3.65	510	90	12.8	2.16	1.13	83.2 → 91.2(8.0↑)	9.7	41	52.7	44.2
11	5 <sup>th</sup> Regen	2.39	510	90	13.1	5.85	4.71	55.3 → 64.0(8.7↑)	15.7	41	52.3	45.5
12	5 <sup>th</sup> Regen	2.82	510	90	13.0	4.92	3.25	62.2 → 75.0(12.8↑)	20.7	41	54.2	46.4
13	6 <sup>th</sup> Regen	3.26	510	90	13.2	5.74	3.86	56.7 → 70.9(14.2↑)	25.1	41	53.5	45.0
14	6 <sup>th</sup> Regen + DI H <sub>2</sub> O(5L)	3.26	510	90	13.1	5.33	4.73	59.3 → 63.9(4.6↑)	7.8	41	52.1	43.5

# Overall Project Objectives for FEAA 384

- Design and construct a larger-scale column (Column B) than the one previously tested (Column A) to:
  - Scale up CO<sub>2</sub> capture from 0.1 t/day to 1 t/day
  - Demonstrate 15% enhancement in CO<sub>2</sub> capture with a 3D printed intensified device for aqueous and low-aqueous amine-based capture at realistic operating conditions
  - Demonstrate that Column B can be constructed with modular packing elements and intensified devices
  - Demonstrate that Column B can effectively capture CO<sub>2</sub> from different CO<sub>2</sub> gas compositions and during process transients, with capacity ramping up and down anticipating the intermittent nature of renewable energy


# Technical Approach/Project Scope

## Project Schedule: Two-year project

- **Task 1.0** – Project Management and Planning (1-24 Months)
- **Task 2.0** – Design, Evaluation, and Construction of Column B based on Results from FEAA375 (1-12)
- **Task 3.0** – Advanced Manufacturing and Core Metrics Testing of Intensified Device for Column B (1-15)
- **Task 4.0** – Using NTRC Engine Combustion Exhaust to Simulate Various Flue Gas Compositions (1-15)
- **Task 5.0** – Test Plan Development for Subsequent Tasks (13-15)
- **Task 6.0** – Aqueous Solvent Capture with Simulated Coal-Fired Power Plant Flue Gas (13-16)
- **Task 7.0** – Aqueous Solvent Capture with Simulated Natural Gas-Fired Power Plant Flue Gas (17-19)
- **Task 8.0** – Aqueous Solvent Capture under Process Transients (20-21)
- **Task 9.0** – Column B Modification and Demonstration of Modular Capture with Low-aqueous Solvent (22-24)
- **Task 10** – Collaboration with CCSI<sup>2</sup> on Modeling of Process Intensification with Column B Results (1-24)


# Progress and Current Status of Project

## Task 1.0 – Managing Design and Construction of CO<sub>2</sub> Capture Column





# Task 2.0 – Design Evaluation and Construction of Column B (1-12)

## Modeling Framework:



# Modeling Framework




MEA  
30 wt%



**Model validated with published CO<sub>2</sub> solubility and pilot data**

Thompson, Tsouris, "Rate-Based Absorption Modeling for Post-Combustion CO<sub>2</sub> Capture with Additively-Manufactured Structured Packing", *Ind. Eng. Chem. Res.*, **2021**, 60(41), 14845-14855.

# Modeling MEA w/Intrastage Cooling




- Simulation of intrastage cooling with device shows good agreement with experiments from Miramontes *et al.* (2020)
  - $\text{CO}_2$  capture difference: all  $\leq 5\%$
- $\text{CO}_2$  capture improvement and temperature profile agreement suggest modeling framework for heat transfer is accurate in predicting device performance

# Task 3.0 – Advanced Manufacturing and Core Metrics Testing of Intensified Device for Column B (1-15) Scale-up from 8” to 12” Diameter


- New unit cell geometry: Column A



- Added flanges for device integration with the column
- Added supports for printability



# Features of Intensified Device



# Scaled-Up Intensified Devices





12-inch diameter, 16-inch height




August 18, 2022

# Location of New Column



National Transportation Research Center  
ORNL Hardin Valley Campus

# Process Flow Diagram for Column Design




Process flow and equipment essential to proper design around absorption column

# Improvements in High Bay, Laboratory, and Mezzanine Areas



# Modular Column Design



**Modular column design provides flexibility in testing packing locations and gas/liquid axial sampling**

## Task 4.0 – Using NTRC Engine Combustion Exhaust to Simulate Various Flue Gas Compositions (1-15)

- Feed gas will be generated with natural gas generator set
  - 100 kW generator
  - 9L natural gas engine
  - Electricity dissipated by load bank
- Exhaust gas generation:
  - Up to 1.4 tons CO<sub>2</sub>/day
  - Water dew point and temperature managed by heat exchangers




Genset installed in the Mezzanine area



Load bank installed in the Mezzanine area

# Commercialization

- Need to demonstrate a path to scale-up
- Developed plan and looking forward to implementing it to demonstrate scalability in a future project
- For small-diameter columns, the intensified packing will be a section of the column
- For larger columns, it will just be a part of the column packing



# Summary

- Modeling work was used for column design
  - Modeling framework developed was extended to other research projects at ORNL
- Project delays related to supply chain
- Delays impacted project schedule, anticipated to be up to two quarters
- Column construction is expected to be completed in August of 2022
- Hydraulic testing will follow, and then heat & mass transfer experiments

## Future Work

- CO<sub>2</sub> capture experiments using aqueous MEA
  - CO<sub>2</sub> capture experiments using LAS (RTI)
  - Performance evaluation under transient conditions
  - Scale-up & TEA } Future project (long term)
- } Tasks 6-9 (short term)

# Publications from FEAA384

- Thompson, Tsouris, “Rate-Based Absorption Modeling for Post-Combustion CO<sub>2</sub> Capture with Additively-Manufactured Structured Packing”, *Ind. Eng. Chem. Res.*, **60**, 14845, (2021). <https://doi.org/10.1021/acs.iecr.1c02756>
- Tarancon, A., et al. “2022 Roadmap on 3D Printing for Energy,” *JPhys Energy*, **4**, 011501 (2022). <https://doi.org/10.1088/2515-7655/ac483d>

## Acknowledgments

- Office of Fossil Energy and Carbon Management
- RTI International and Marty Lail
- David Lang
- Lynn Brickett

# The Whole Project Team

## Research Team:



Costas Tsouris, PI



Joshua Thompson



Gyoung Jang




Jim Parks

## Coordination, Construction, and Safety Team:



Scott Curran



Scott Palko



Jonathan Willocks



Jason Case

## CCSI<sup>2</sup> Connection:



Charles Finney

## Additive Manufacturing Team:



Amiee Jackson



Lonnie Love



Xin Sun, Consultant

# Appendix

# Project Schedule and Completion

August 2022

Timeline in Quarters	FY: 21			22				23		% Completed
	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	
<b>Task 1.0 – Project Management and Planning</b>	█	█	█	█	█	█	█	█	█	
<b>Task 2.0 – Design Evaluation and Construction of Column B based on Results from Task 3.0 in FWP-FEAA375</b>	█	█	█	█	█					70
Subtask 2.1 Design Evaluation, Equipment Design and Sizing	█	█								100
Subtask 2.2 Column B Construction			█	█	█					75
Subtask 2.3 Instrumentation of Column B			█	█	█					90
Subtask 2.4 Initial Column Evaluation					█					0
<b>Task 3 – Advanced Manufacturing and Core Metrics Testing of Intensified Device for Column B</b>	█	█	█	█	█	█				50
Subtask 3.1 Advanced Manufacturing of Intensified MellaPak 250 Device for Column B Geometry	█	█	█	█	█					100
Subtask 3.2 Core Metrics Testing and Validation of the Intensified MellaPak 250 Device						█				0
<b>Task 4 – Using NTRC Engine Combustion Exhaust to Simulate Various Flue Gas Compositions</b>	█	█	█	█	█					90
Subtask 4.1 Engine, Fuel, and Load System Selection and Configuration	█	█								100
Subtask 4.2 Design and Installation of Auxiliary Systems to Supplement CO <sub>2</sub> , Flow, and/or Temperature Control			█	█	█					90
<b>Task 5.0 – Test Plan Development for Subsequent Tasks</b>					█					
<b>Task 6.0 – Aqueous Solvent Capture with Simulated Coal-Fired Power Plant Flue Gas</b>						█	█			
Subtask 6.1 Baseline Experiments with Commercial Packing						█				
Subtask 6.2 Experiments with Intensified MellaPak 250							█			
<b>Task 7.0 – Aqueous Solvent Capture with Simulated Natural Gas-Fired Power Plant Flue Gas</b>							█	█		
Subtask 7.1 Baseline Experiments with Commercial Packing							█	█		
Subtask 7.2 Experiments with Intensified MellaPak 250							█	█		
<b>Task 8.0 – Aqueous Solvent Capture under Process Transients</b>								█		
Subtask 8.1 Baseline Experiments with Commercial Packing								█		
Subtask 8.2 Experiments with Intensified MellaPak 250								█		
<b>Task 9.0 - Column B Modification and Demonstration of Modular Capture with Low-aqueous Solvent</b>									█	
Subtask 9.1 Modify Column B to Demonstrate Modular Design									█	
Subtask 9.2 Baseline Experiments with Commercial Packing									█	
Subtask 9.3 Experiments with Intensified MellaPak 250									█	
<b>Task 10 - Collaboration with CCSI<sup>2</sup> on Modeling of Process Intensification with Column B Results</b>	█	█	█	█	█	█	█	█	█	

Supply chain delays since Jan 2022 have resulted in ~2-quarters delay of the project

# Technical Approach/Project Scope

- Scale up CO<sub>2</sub> capture rate by a factor of 10 from Column A to Column B
- Scale up intensified device
- Demonstrate enhanced capture by aqueous MEA using intrastage cooling
- Demonstrate enhanced capture by LAS using intrastage cooling
- Demonstrate modularization with one or more packing elements for each module
- Demonstrate smooth operation with variable gas feed flowrate and CO<sub>2</sub> concentration