




*Improving the cost-effectiveness of algal CO2 utilization by synergistic integration with power plant and wastewater treatment operations*

Department of Energy Cooperative Agreement No: DE-FE0032098



*2023 Carbon Management Project Review Meeting  
August 29, 2023 Pittsburgh, PA*

University of Illinois at Urbana Champaign  
Lance Schideman & Ryan Larimore



Illinois Sustainable Technology Center



# Project Overview

- DOE Funding Program DE-FOA-0002403: *Engineering-Scale Testing & Validation of Algae-Based Technologies & Bioproducts Area of Interest 1 (AOI 1)*
- Upscaling and integrating unit processes for algal carbon capture at a coal power plant site
- *End of Project Objectives & Goals:*
  - BP1 Goal- Cultivation system installed & operational achieving >10 g/m<sup>2</sup>/d productivity
  - BP2 Goal- Improved cultivation operations with productivity > 14.3 g/m<sup>2</sup>/d and reduced costs
  - Project End Goal: Techno-economic analysis at 5000-ac scale w/key performance parameters supporting a minimum selling price below market value of protein conc. and \$0 CO<sub>2</sub> capture credit

Budget Period	Work	Start	End	Budget
1	Design and Construction	10/1/2021	9/30/2023*	\$1,897,532
2	Testing and Optimization	10/1/2023	3/31/2025	\$601,564

\* Includes 6 mo No Cost Extension

## Project Overview - Participants



**PI: Lance Schideman, PhD, PE**  
**Illinois Sustainable Technology Center**  
**of the Prairie Research Institute**  
Project management and integration  
of wastewater nutrients.



**Global Algae Innovations (GAI):**  
Design and construction of algae  
cultivation system



**City Water Light and Power:**  
Host Site

# Technical Approach

## Project Strategy: Combination of Key Advantages

Best in Class Algae Cultivation  
System from GAI



First Demonstration with Global  
Algae Innovations (GAI) System  
Using Coal Flue Gas




City Water Light and  
Power

Improvement of Economics with  
Use of Wastewater Nutrient  
Inputs and Animal Feed Testing




# Technology Background- Simplified Process Flow Diagram






# Technology Background



GAI's 8-wet acre  
Kauai Algae Farm  
- CO<sub>2</sub> from a  
naptha-fueled  
power plant

# Technology Background- CO<sub>2</sub> Capture Process Integration with Algae Cultivation System

Previous  
CO<sub>2</sub> Absorber  
Column by GAI



# Technical Approach

Complete

Task / Subtask	Milestones
1/1.1	Submit Updated Project Management Plan (PMP)
1/1.2	Submit Initial Technology Maturation Plan (TMP)
2	Cultivation system installed and operational achieves at least 10 g/m <sup>2</sup> /d productivity with coal flue gas CO <sub>2</sub>
3	Absorber system installed and operational and achieves at least 75% carbon capture efficiency
4	Harvesting and drying system installed and operational and produces algae powder with less than 10% moisture content
5	Algae protein meal with at least 50% protein
6	Demonstrate ability to replace at least 50% of nutrients in algal inoculation cultures
7	Interim TEA and LCA confirming costs for baseline performance
8.	Integrated system has average CO <sub>2</sub> capture efficiency of >80%,
8	Cultivation system has an average productivity of 14.3 g/m <sup>2</sup> /d with coal flue gas CO <sub>2</sub>
9	Demonstrate ability to use power plant waste heat to extend algae growing season and increase cold weather productivity
10	Determine projected value of algal biomass based on live chicken digestion tests
11	Final TEA incorporating averages of key performance parameters projects a required selling price that is less than the market price of the protein concentrates at a scale of 5000-acres with \$0 credit for CO <sub>2</sub> capture and mitigation
12	Final LCA incorporating averages of key performance parameters projects at least a 50% reduction in GHG for the target products



# Project Overview

Overall CWLP power plant site showing current operations and proposed research and demonstration facilities



# Project Achievements- System Construction




Design Layout



Constructed




# Project Achievements Flue Gas Absorber System Design and Construction




nominal flows
1-3 gpm media
2-6 scfm flue gas

**S** = sample port  
**F-T-P** = flow-temp-pressure

Process Flow Diagram



# Project Achievements- 83% CO<sub>2</sub> Capture Based on pH Change Model




## Project Achievements- Average Algae Productivity >10 g/m<sup>2</sup>-day Startup Target

Demonstrated good growth of *Spirulina* with 50% of nutrients provided from a municipal wastewater source  
- Working to acclimate cultures to higher proportion of wastewater



Small Raceways Used for Culture Upscaling





Daily Algae Biomass Productivity




# Project Achievements

Demonstrated good growth of *Spirulina* with 50% of nutrients provided from a municipal wastewater source  
- Working to acclimate cultures to higher proportion of wastewater



## Project Achievements- *Understanding relationship of pH and ammonia conc*


- Concentrated Wastewater N form is typically in the form of ammonia ( $\text{NH}_3$ )
- Experiments comparing algae growth at different combinations of levels of pH and  $\text{NH}_3$  ( $\text{p}K_a = 9.24$ )
  - Data shown for 135 mg/L  $\text{NH}_3$
  - Growth retarded pH 9.5 and above
- When operating  $> \text{pH } 9.3$  need to control delivery of  $\text{NH}_3$  to match algal uptake
  - Typical algal biomass is 10-15% N
- May be possible to gradually acclimate algae to higher  $\text{NH}_3$  concentrations



# Animal Feed Testing

## Protein Content Analysis:

- Initial testing of algae biomass characteristics has shown that all cultivation medium can meet our 50% protein target
  - Absorbed Media made with flue gas CO<sub>2</sub>
  - Artificial Media made with chemical HCO<sub>3</sub><sup>-</sup>
- Outdoor raceway cultures have room for improvement to increase protein content




# Baseline TEA for 5000-acre Algae Farm in IL

Daily Avg. CO<sub>2</sub> Captured from flue gas: 358 tonne/day (98 tonne C/day)

Daily Avg. Algae Production: 202 tonne/day(Ash Free Dry Weight), 8 tonne/day (Ash)




Parameter	5000-acre scale
<b>Algal Culture</b>	<i>Spirulina</i>
<b>Gross / Net Power Plant Capacity (MW) – CWLP Dallman Unit 4</b>	230/200
<b>Power Plant CO2 emission (tonnes/MWh)</b>	0.76
<b>Power Plant Annual CO2 Emission (tonnes/year) (based on peak load capacity factor: 0.85)</b>	1.53 Mil./1.3 Mil.
<b>Target Carbon Dioxide Removal (%)</b>	8.5% / 10 %
<b>Avg. Algae Productivity (g/m<sup>2</sup>-d)</b>	10.4
<b>Algae Cultivation Area (Acres)</b>	5,000
<b>Annual Avg. Algal Biomass Production (dry tonnes/yr)</b>	74,000

Techno  
Economic  
Analysis and  
Interim Life  
Cycle  
Analysis






# Baseline Capital and Operating Expenses (CAPEX/OPEX)



- Algal biomass production cost: \$1,072/ton
- Protein concentrate target product value: ~\$1,400/ton
- Other revenue sources:
  - Credits for wastewater nutrient removal or CO<sub>2</sub> utilization
- Further improvements for lower costs and higher productivity:
  - Extraction of high value algae bioproducts (e.g., pigments)
  - Reduced energy for algae mixing, harvesting and drying
  - Increasing wastewater use for cultivation media chemicals
  - These improvements included in the planned project testing

# Scale Up Potential and Land Requirements

- Large scale algae cultivation >1500 ac. is possible @ Springfield, IL
- Need to use both local utility land AND private farm land
- Would require a network of flue gas & water pipelines (~10 mi. each)





# Summary

- **Project Status:** Construction is complete, and systems are being transitioned to operational optimization phase (BP2).
- **Key Project Advantages:**
  - Wastewater nutrients can increase revenue and decrease costs
  - Selection of Spirulina has advantages of existing markets and high pH tolerance
  - Algae biomass productivity higher than conventional row crops (~ 2x increase)
- **Project Impact - Animal Feed:**
  - High protein content meal produced
  - Large offtake market (Soy >350 Mil tons/yr)
  - 100% use vs losses in fuel conversion



# Extra Slides

---



## Project Achievements – Absorber Test



Zobi Harvester