Longleaf CCS Hub (DE-FE0032341)

Ben Wernette, PhD Southern States Energy Board

Dave Riestenberg Advanced Resources International



Standard Disclaimer

This presentation is based upon work supported by the Department of Energy and was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendations, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.







Project Motivation

- The Longleaf CCS Hub seeks to develop a CO₂ storage facility near Bucks, Alabama
- Builds on the successful SECARB injection demonstration at the Anthropogenic Test Site, conducted at nearby Citronelle, Alabama
- Opportunity to decarbonize the many industrial facilities in Mobile County
- Motivated project owner and developer in Tenaska





Location

- The proposed storage complex site is located north of Mobile Alabama
- The complex will provide storage for the CO₂ emissions captured from regional emitters along the Mobile River and to the south
 - > 19 MMtonnes per year from 40+ emitters
- Located 5 miles to the east of the SECARB Anthropogenic test site at Citronelle

Regional emitters in the Gulf South that may wish to explore opportunities to decarbonize.

0.1 – 1.0 MMTPA Less than 0.1 MMT



Map of the Longleaf CCS storage complex in northern Mobile County.



SECARB Anthropogenic Test Overview

- 25 MW capture unit at Alabama Power's Plant Barry (500 metric tons per day)
- Four-inch, 12-mile CO₂ pipeline from Plant Barry to the Citronelle Dome
 - Normal operating pressure of 1,500 psig
- Three wells drilled in 2011 to 11,800ft.
- Injection 8/2012 to 9/2014
- 114,104 metric tons of CO₂ injection under Class V
- Post-Injection Site Care Period 9/2014 to 5/2018
 - Permit closure in May 2018 based on USDW non-endangerment and CO₂ containment demonstration (5-yr renewal)
 - Based on monitoring and modeling results

SECARB Anthropogenic Test Footprint









Left: Local stratigraphic column illustrating the target storage reservoirs. Right: Well log correlation of local stratigraphy illustrating lateral continuity of target formations.



Sources

- Over 19 MMTs of CO₂ emitted from over 28 industrial sources
- Diverse industrial sources participating in the project

Company	Industry	CO ₂ Emissions Tons/Yr	Letter of Support
Calvert	Steel	500,000	Received
Calysta	Sustainable Protein	500,000	Received
Plant Barry	Power Generation	1,500,000	Received
Williams	Natural Gas Processing	100,000	Received

Regional emitters that have agreed to participate in project activities.

Illustration of the MAST chemical corridor, and the potential demand for decarbonization solutions.







Project Objectives

Rigorously characterize the subsurface for large-scale storage

Develop a comprehensive community benefits plan

Obtain Class VI UIC permit(s)

CO₂ sources and transportation

Storage field development

Risk assessment

NEPA EIV for the integrated project



Tasks

Task 1 – Project Management and Planning

Task 2 – National Environmental Protection Act

Task 3 – UIC Class VI Authorization to Construct

Task 4 – Detailed Site Characterization of a Commercial-Scale CO₂ Storage Site

Task 5 – Storage Field Development Plan

Task 6 – CO₂ Source(s) Feasibility Study

Task 7 – Pipeline FEED Study

Task 8 – Business and Financial Plans and Arrangements

Task 9 – Community Benefits Plan



Task 4 – Detailed Site Characterization of a Commercial-Scale CO₂ Storage Site

- Project owner and developer, Tenaska, has secured land rights for a storage complex in northern Mobile County, AL
- Class VI UIC Permit application submitted to EPA Region 4 in Spring 2023
 - Ongoing discussions with EPA and others
- Augment with stratigraphic test well drilling data acquisition
- Seismic acquisition

Map of the Longleaf CCS storage complex in northern Mobile





Task 9 – Community Benefits Plan

- Tenaska has been actively engaged with state legislative leaders, local officials, among others
- Project aligns with the Mobile Chamber's goals to support existing business and attract new industry to South Alabama
- Goals of CBP
 - Increase community involvement in project decision making
 - Increasing access to educational and career opportunities for those from disadvantaged and/or minority communities



Tenaska personnel engaging with community members in Mobile, Alabama.



Deliverables

Task/Subtask Number	Deliverable Title	Due Date	
1.0	Project Management Plan	Update due 30 days after award. Revisions to	
		the PMP shall be submitted as requested by the	
		NETL Project Manager.	
1.0	BIL Metrics Reporting	TBD but likely quarterly	
2.1	Environmental Information Volume	Due at the end of BP 1.	
2.2	NEPA Documentation (EA or EIS)	Due at the end of the Project Performance	
	NETA Documentation (EA of EIS)	Period.	
3.1	Application for Underground Injection Control Class VI Permit to	At the end of Budget Period 1.	
	Construct		
4.2	Geologic Catalog of Materials	At the end of each project year.	
5.2	Storage Field Development Plan supported by AFEs	Due within 90 days prior to end of the Project	
	Storage Tield Development Tian supported by ATES	Performance Period.	
5.4	Risk Assessment and Mitigation Plan	Due within 90 days prior to end of the Project	
		Performance Period.	
6.0	CO ₂ Source(s) Feasibility Study	Due at the end of the Project Performance	
	CO ₂ Source(s) reasonity Study	Period.	
7.0	CO ₂ Pipeline FEED Study	Due at the end of the Project Performance	
	CO ₂ Tipeline FEED Study	Period.	
8.0	Preliminary Business and Financial Plans	Due at the end of Budget Period 1	
8.0	Final Business and Financial Plans	Due at the end of the Project Performance	
		Period.	



Thanks!

Ben Wernette, PhD Southern States Energy Board wernette@sseb.org

Dave Riestenberg Advanced Resources International <u>driestenberg@adv-res.com</u>



Mobile, Alabama.

Project webpage: https://longleafccs.com/

