Advancing Characterization of Faults Through Deployment of Novel Geophysical, Geochemical and Geomechanical Technologies at the San Juan Basin (SJB) CarbonSAFE Site

DE-FE0032064

William Ampomah, PhD

Section Head-Research Engineer/ Assistant Professor New Mexico Tech

> U.S. Department of Energy National Energy Technology Laboratory Carbon Management Project Review Meeting August 28 – September 1, 2023

Project Participants

• NMT

- Dr. William Ampomah
- Dr. Sai Wang
- Mr. George El-kaseeh
- Mr. Luke Martin
- Dr. Alex Rinehart
- Dr. Jiawei Tu
- Dr. Adewale Amosu
- Graduate Student
- University of Utah
- Prof. Brian McPherson
- Dr. Kevin Lynn McCormack
- Silixa LLC
- Mr. Thomas Coleman
- Dr. Carlos Maldaner
- Dr. David Podrasky







UNIVERSITY

OF UTAH

- LANL
- Dr. Lianjie Huang
- Dr. Jeffrey Hyman
- Dr. Zhou Lei
- Dr. Rajesh Pawar
- Dr. Konstantin Lipnikov

Contractors

- Dr. Tom Bratton
- AHS
- Dr. Michael P. Smith
- Dr. Christopher Smith
- Mr. Patrick Gordon





Project Overview

- Funding Profile
- Project Performance Dates:
- 07/01/2021-03/30/2025

	BI	P1	B	P2	B	P3	Total			
	07/01/21 - 03/31/23		04/01/23 - 03/30/24		04/01/24	- 03/31/25				
	DOE Funds	Cost Share	DOE Funds	Cost Share	DOE Funds	Cost Share	DOE Funds	Cost Share		
NMIMT	332,640	32,389	169,139	43,195	156,146	28,481	657,924	104,064		
University of Utah	54,419	13,608	26,449	6,612	14,132	3,530	95,000	23,750		
Silixa LLC	246,970	140,315	-	23,800	-	23,800	246,970	187,915		
LANL	79,996	-	80,008	-	39,996	-	200,000	-		
T otal (\$)	714,025	186,312	275,596	73,607	210,274	55,811	1,199,894	315,729		
T otal Cost Share %		20.7%		21.1%		21.0%		20.8%		













Project Overview: Objectives

- The project will carry out field deployment of an integrated suite of cost-effective and novel geophysical, geochemical, and geomechanical technologies for detection and characterization of faults and fractures.
- The project will deploy these technologies at the San Juan Basin (SJB) CarbonSAFE Phase III site
- To permanently deploy an integrated behind casing fiber optic sensing system, including Distributed Strain Sensing (DSS), Distributed Temperature Sensing (DTS), and a high sensitivity Distributed Acoustic Sensing (DAS) system.
- To employ Rock Volatile Stratigraphy (RVStrat), a novel geochemical technology that uses drill cuttings and core, to locate faults (including aseismic faults) and estimate their sizes and orientations.

Project Overview: Objectives

- To detect faults near and more distant from the well bore, including faults in the crystalline basement rock, using a novel multi-scale U-Net machine learning method to evaluate 3D surface seismic and 3D VSP images.
- To integrate proposed technologies to develop advanced rock physics and coupled thermo-hydrodynamic-mechanical models in combination with the Monte Carlo method, to determine state of stress on each mapped fault and estimate long-term slip potential and/or maximum fault slip potential resulting from large-scale CO₂ injection.

Project Approach



Milestones

Task/ Subtask	Milestone Title & Description	Planned Completion Date	Status
1.0	Project Kick-off meeting		Attend Meeting
2.2	Deployment of DAS/DSS/DTS behind casing in the SJB	02/02/2023	Completed
	CarbonSAFE stratigraphic well		
2.4	Drilling cuttings, core and legacy core cuttings assembled	02/02/2023	Completed
3	Seismic analysis detecting aseismic and basement faults	08/31/2023	Ongoing
4	RVstrat approach detecting and characterizing faults	03/31/2024	Ongoing
5.1/5.2	Wellbore analysis detecting and characterizing geological features such as faults	10/31/2023	Ongoing
5.3	Determination of principal stress, pore pressure within storage complex	03/31/2024	Ongoing
6.1/6.2	Compilation of fault information and baseline seismicity within storage complex and basement	03/31/2025	Ongoing
6.3	Fault slip analysis	09/30/2024	Ongoing
7.1	Completion of static model for numerical simulation	10/30/2023	Ongoing
7.3	Numerical modeling for hazard assessment	02/28/2025	Ongoing

7



Storage Complex @ San Juan Basin







SJB CarbonSAFE Project Facts



Key Project Facts

- Perform Site Characterization of storage complex within San Juan Basin
- Source CO2 from Escalante H2 plant, located in Prewitt, NM, USA.
- Initial UIC Class VI permit submitted in 2023
- Community and stakeholder outreach on CCS technology and its benefits

Characterization Plan

- Drilled characterization well, perform injectivity tests
- Recovered ~ 450 ft of Core, sampled drilling cuttings, advanced log suites measurements
- Perform suites of laboratory experiments and numerical models
- Purchased 100 sq.miles 3D seismic, acquire 3D VSP,
- Installed DAS/DTS/DSS Optical fiber behind casing





SJB CarbonSAFE Well - XRD data



Field Operation - Fiber Installation







Well drilling operations under SJB CarbonSAFE Project (DE-FE0031890).





SJB CarbonSAFE Stratigraphic Well- Fiber Installation

Stratigraphic Well Design



Silixa Distributed Optical Fiber Technology



Data Acquisition- Fiber Optic

The DTS, DSS, and DAS data acquisition plan includes:

- Mobilization 1 Fiber optic cable deployment
 - Measurements during fiber optic cable deployment
 - DSS and DTS surveys after the cable reaches total depth
 - DSS and DTS surveys during and after the cementation process
- Mobilization 2 Baseline
 - Strain (DSS) baseline
 - Temperature (DTS) baseline
 - Acoustic (DAS) baseline (ambient noise log)
 - Zero-offset and Walk-away VSP
 - Seismicity baseline
- Mobilization 3 Injection Test
 - Continuous monitoring during DFIT using DTS, DSS, DAS

Cementation Results

- Two multimode fibers, double-ended in Bottom Hole Assembly
- BHA depth 8686.9 ft KB
- Cementation took place in two stages from 12:01 am to10:23 am on February 2nd, 2023
- A DV tool was utilized to facilitate stage two injection
- DTS Monitoring took place from February 1st ,11pm to February 3rd ,10am

Date	Time	Event
Feburary 2 2023	00:01	Begin pumping Water ahead
Feburary 2 2023	00:27	Stage one Lead Cement
Feburary 2 2023	03:02	Open DV Tool and Circulate
Feburary 2 2023	09:29	Stage Two Lead Cement
Feburary 2 2023	10:23	Shutdown

Cementation Results

- DTS absolute temperature during cementation.
- Top of stage one cement at 5034 ft KB
- Stage two ingress below the DV tool
- Weak exothermic response is apparent in stage 2



Zero Offset VSP

- VSP acquisition took place on February 26-27, 2023
- Acquired with Silixa's Carina DAS
- Vibroseis survey with near offset ring

Setting	Value	Units
Sampling frequency	1	kHz
Time decimation	20	
Spatial sampling	1	m
Gauge length	10	m

Table 3: Primary Carina settings for the DAS VSP survey.

Settings	Value	Units
Sweep design	Linear	
Sweep frequency range	4-120	Hz
Sweep length	12	S
Sweep tapers	300	ms
Listen time	5	S

Table 4: Vibroseis sweep parameters.







Zero Offset VSP



P-wave Velocity profile and Blocked model

- Good correlation with formation tops (blue)
- Model created by blocking off the mean of the velocities (orange)
- Large velocity contrasts outside of formation boundary's – Top of Pictured Cliffs 2700 ft to 3100 ft
- Large contrast in Velocity correlated with poor cement bonding from VDL logs, and casing ring.



Cementation monitoring

Absolute strain measurements during cementation



Post Wellhead Installation

Temperature data, post cementation (2023-02-03) (i.e. warmback)



Coincident with VSP

Strain data coincident with VSP survey, temperature corrected (2023-02-26)



Legacy 3D Surface Seismic Data

- The project procured a legacy 3D surface seismic dataset acquired at the San Juan CarbonSAFE storage site.
- We perform migration velocity analysis and prestack depth migration to obtain improved subsurface structural images.
- We use anisotropic diffusing filtering to reduce image noise and improve the reliability of fault detection.
- We detect faults on migration images using LANL's recently developed machine-learning algorithm (Gao, Huang, Zheng, 2022).



Nested-Residual U-Net (NRU) Fault Detection



ML-Detected Fault on Original PSTM Image

ML-Detected Faults on Denoised PSTM Image



ML-Detected Fault on Original PSDM Image

ML-Detected Faults on Denoised PSDM Image



Seismic Attribute based Fault Extraction



Ant Tracking - Todilto



Double Pass Ant Tracking - Alkali Gulch







AHS Rock Volatiles CCS Well Site Evaluation



Site Evaluation

- Presently the sealed at the well cuttings samples have been analyzed
- Unsealed cuttings samples and core samples RVS data will be needed for an apples-to-apples comparison to the regional baselines
- With the available data, it is possible to begin assessing some of the identified features relating to the Farmington site

Feature of Interest	Status in CarbonSAFE 1 Well
Petroleum System - Lateral Migration	?
Petroleum System - Vertical Migration	?
Carbon Dioxide Regional Baseline	?
Nature of Carbon Dioxide Release	?
Vertical Seals	?

Site Evaluation- Sample Locations



Lateral Migration

- Composition of the HCs reveals additional information
- Positive correlation between HC gases and liquids; HC liquids are likely present as a condensate in the gas
- HC liquids composition across the well is very benzene rich, values of ~1% are consistent for oil, values of a gas will be less because of its low volatility
- The high benzene content means significant water is present across most of the analyzed section due to its solubility

Further investigation is needed to evaluate where these liquids rich gas condensates came from and potential implications







Vertical Seals

- Geochemical evidence of several significant seals in the primary and secondary seals
- CO2 and helium show a stepwise change in the top of the Brushy Basin indicating an excellent seal
- HC composition indicates a potential seal in the U. Mancos and Chinle
- Other seals are possible
- Very positive evidence for the existence of good quality seals at CarbonSAFE 1



Site Summary

While the question of lateral migration of HCs needs to be evaluated, features of interest based on the evaluation of legacy cuttings samples were identified and the results in relation to the SJB CarbonSAFE Storage site are overall encouraging, especially in relation to a lack of a history of CO2 migration/loss and evidence of strong vertical seals

Feature of Interest	Status in CarbonSAFE 1 Well
Petroleum System - Lateral Migration	Needs Evaluation
Petroleum System - Vertical Migration	Encouraging
Carbon Dioxide Regional Baseline	Encouraging
Nature of Carbon Dioxide Release	?
Vertical Seals	Positive

Next Step- Coupled Modeling Workflow



Summary Slide

- We have preformed machine-learning fault detection on prestack time migration (PSTM) and prestack depth migration (PSDM) images and compare the results.
- Most lines of our machine-learning fault detection results show that there are no major faults around the primary CO2 injection zone
- Successfully utilized Silixa fiber to monitor cementation operations during SJB CarbonSAFE well drilling.
- Successfully acquired a zero-offset and Walk away VSP at the SJB CarbonSAFE site
- Established a baseline for DAS/DTS/DSS responses post-drilling operations.
- Utilized AHS drilling cuttings analysis to establish lateral and vertical storage integrity within the storage complex

Next Steps

- a. Complete analysis of unsealed cuttings and core and incorporate into sealing and migration assessment of the San Juan Basin
- b. Perform 3D migration and 3D fault detection using ML approach
- c. Compare residual U-shaped CNN method to conventional seismic attributes
- d. Complete the conversion of existing 3D geological models to a format that LANL numerical tools can use
- e. Continue the integrated hazard modeling utilize state-of-the art LANL toolsf. Acquire a time-lapse fiber data during the injection test at the SJB CarbonSAFE site

Acknowledgements

The project would like to thank DOE for the award opportunity through DE-FE0032064 and our partners. We would like to acknowledge additional support from San Juan Basin CarbonSAFE project.

Appendix

These slides will not be discussed during the presentation but are mandatory.

Next Steps- DfnWorks



Organization Chart



Proposed Schedule

	Budget Period 1-[07/01/2021 to 03/31/2023					Budget Period 2				Budget Period 3				
	Tasks	Project Year 1				Project Year2				Project Year 3				
	7		123456	789	10 11 12	1 2 3	4 5	6 7 8 9	10 11	12 1 2 :	34567	8910	11 12 1	23
Task 1.0	Project Management and Planning													
Subtask 1.2	Technology Maturation Plan													
Task 2.0	Deployment of Field Technology/Data Collection													
Subtask 2.1	Review of Well Design													
Subtask 2.2	Deployment of the DSS/DAS/DTS Fiber Optic Cable					M								
Subtask 2.3	Data Acquisition													
Subtask 2.4	Cutting Sample Collection and Pretreatment		М			M								
Task 3.0	Seismic Analysis for Fault Detection													
Subtask 3.1	Machine Learning Fault Detection of Surface Seismic Image							M						
Subtask 3.2	Machine Learning Fault Detection of VSP Images and VSP-DAS Images													
Subtask 3.3	Comparison with Industry Standard Seismic Fault Detection													
Task 4.0	Geochemical Analysis for Fault Detection and Characterization				М					М				
Subtask 4.1	Historical Sample Analysis													
Subtask 4.2	Volatiles Identification and Quantification													
Subtask 4.3	Bulk Mechanical Strength Measurements													
Subtask 4.4	Integration of well log and RVstrat Analysis													
Task 5.0	Wellbore Analysis for Fault Detection and Characterization													
Subtask 5.1	Fault and Fracture Detection using Wellbore Images								М					
Subtask 5.2	Fault and Fracture Detection using BARS													
Subtask 5.3	DFIT Analysis to Quantify Minimum Horizontal Stress, Pore Pressure, and Matrix Permeability									М				
Subtask 5.4	Viscoplastic Minimum Principal Stress Estimation													
Subtask 5.5	Strain Modeling with Finite Element Analysis													M
Task 6.0	Fault Slip/Activation Analysis													
Subtask 6.1	Compile Stress Information										M			
Subtask 6.2	Compile Fault Information											М		
Subtask 6.3	Compute Coulomb Failure Function													
Task 7.0	Integrated Modeling for Hazard Assessment													
Subtask 7.1	Geological/Static Modeling								М					
Subtask 7.1.1	Geologic Structural and Stratigraphic Framework													
Subtask 7.1.2	2 3D Hydrodynamic and Mechanical Model													
Subtask 7.1.3	Fracture Modeling													
Subtask 7.1.4	4 Fault Transmissibility Modeling													
Subtask 7.2	Advanced Rock Physics Modeling													
Subtask 7 2 1	Verify the presence of fractures in caprocks													
Subtask 7.2.2	Develop combined rock physics model													
Subtask 7.3	Advanced Numerical Modeling													4.0
Subtask 7.2 1	Hydrodynamic Modeling												.(
Subtack 7.3.1	Counted Thormo hydrodynamia Machaniad Madaling													
SubidSK 7.3.2														