### EERC. UN NIVERSITY OF NORTH DAKOTA.



#### Williston Basin Associated CO<sub>2</sub> Storage Field Laboratory DE-FE 0031694

Steve Smith University of North Dakota Energy & Environmental Research Center U.S. Department of Energy

National Energy Technology Laboratory DE-FE00031694 August 30, 2023

© 2019 University of North Dakota Energy & Environmental Research Center.

#### **Partners**











### **Project Goal and Objective**

Goal: To advance associated geologic storage of CO<sub>2</sub> in the Williston Basin by establishing the Williston Basin Associated CO2 Storage Field Laboratory (WBCFL).



- Generate field-based data on CO<sub>2</sub>
  EOR with associated storage in stacked reservoirs.
- Characterize a Residual Oil Zone for EOR and associated storage.
- Evaluate a monitoring, verification, and accounting (MVA) technique for its applicability to stacked CO<sub>2</sub> storage complexes.

### Task/Subtask Breakdown

#### Task 1 – Project Management, Planning, and Reporting

- Subtask 1.1 Project Management and Planning
- Subtask 1.2 Project Reporting and Technology Transfer

#### Task 2 – Fluid Behavior Studies

- Subtask 2.1 Sample Collection and Compositional Analysis
- Subtask 2.2 MMP Studies
- Subtask 2.3 EOS and PVT Studies

#### Task 3 – Field Site Reservoir Characterization

- Subtask 3.1 Core Sample Identification and Collection
- Subtask 3.2 Laboratory Determination of Petrophysical Properties
- Subtask 3.3 Field Monitoring of Reservoirs
- Subtask 3.4 Static Geomodeling
- Subtask 3.5 Dynamic Modeling



#### Task 4 – Active Seismoelectric Technology Demonstration

- Subtask 4.1- Active Seismoelectric Survey
- Subtask 4.2 Follow-Up Active Seismoelectric Survey

#### Task 5 – Life Cycle Analysis

- Subtask 5.1 Life Cycle Analysis of the Field Test
- Subtask 5.2 Life Cycle Analysis of Stacked Storage

### **Project Management, Planning, and Reporting**




At present, EERC is working with DOE on a NCTE to extend the project timeline to September, 2025

EERC. UND NORTH DAKOTA.

## **Project Location / CO<sub>2</sub> Source**

- Near Baker, MT
- Cedar Creek Anticline
- CO<sub>2</sub> Sourced from Shute Creek and Lost Cabin Gas Plants (WY)






Critical Challenges. Practical Solutions.

## **Study Area**

Two wells will be used for the project

- 13-18B (Producer)
- 23X-18B (Injector)
- Additional legacy wells are used for development of a geologic model




EERC. | UND NORTH DAKOTA.

### **Target Reservoir**

- Interlake Formation
  - Upper Interlake Main Pay Zone
  - Cycles 4 & 5 ROZ's
- 150 ft thick
- Porosity: 1.3 16.3%
- Permeability: 0.008 3.7 mD

Injection expected between September 2023 to December 2023






Main Pay Zone

**Residual Oil Zone** 

## **Core Characterization**


- Denbury drilled the 23X-18B (Injector) and collected core over the main pay and ROZ's
- Core analyses include:
  - P&P
  - XRD
  - MICP
  - Fluid saturations
  - NMR
  - SCAL






# **Fluid Studies**


- Whole Crude Analysis
- CO<sub>2</sub> MMP
- Contact Angle
- IFT






#### Upper Interlake Crude Oil Contact Angle

Surrounding Phase Temperature	Produced 200°F	Brine	Surrounding Phase Temperature	Carbonated Brine 200°F					
	Pressure, psi	Contact Angle, °		Pressure, psi	Contact Angle, °				
	3000	120.53		3000	145.03				
	3300	120.12		3300	144.46				
	3600	119.75		3600	144.70				
1077311	3900	119.47		3900	144.62				
	4200	119.27		4200	144.25				



Lower Interlake Crude Oil IFT Surrounding Phase **Produced Brine** Surrounding Phase **Carbonated Brine** Temperature 200°F Temperature 200°F Pressure, IFT, Pressure IFT. mN/m psi psi mN/m 3000 12.82 3000 14.09 3300 12.60 3300 14.07 3600 12.52 3600 14.05 3900 12.47 3900 14.01 4200 12.40 4200 14.03

Upper Interlake Crude Oil IFT






## **Geologic Model and Simulation**


Model developed using:

- Core data
- Legacy well data


- 1) Max Injection = 5 mmcfpd
- 2) Max BHIP = 6000 psi
- 3) Max Production =
  - a. 5 mmcfpd
  - b. 2000 bwpd
  - c. 500 bopd
- 4) Min BHPP = 1200 psi

- Simulations are still ongoing
- This view shows CO2 breakthrough occurring in approximately 2 months after injection begins
- Simulations will be updated as injection and production data is received





#### **Gas saturation**




Gas saturation March/01/2024


The gas is shown to breakthrough in March when injector is at the same depth as the production well



# Monitoring

Traditional Seismic Fiber Optics Active Seismoelectric








## **Active Seismoelectric Technology Demonstration**

Conducted over a select area of the stacked storage complex in the project field test area.



Significant accomplishments:

Performed a small-scale ASE survey in Mentor, Minnesota, to refine field deployment strategies and examine the data processing workflow.

Initial reservoir model values have been generated.

A full ASE survey was conducted over a select area of the stacked storage complex in the project field test area. Surface vibroseis sourcing and near-surface impulse sources in a high-density array were recorded.

Collected ASE data were processed using Zonge software to remove noise and enhance seismoelectric signal.


Initial analysis was carried out on subsets of the ASE data collected in the initial survey. Interpretation of the ASE data is ongoing.

EERC | UND NORTH DAKOTA

# Life Cycle Analysis

BP1 and BP2 data generated during the following tasks will be used to conduct an LCA of the project field test:

- Fluid Behavior Studies
- Field Site Reservoir Characterization
- Active Seismoelectric Technology
  Demonstration
- Additional data obtained from active CO<sub>2</sub> storage projects in ND





#### Summary

#### **Budget Period 1**

Determined the baseline reservoir characteristics of the stacked storage complex.

Determined the effects of hydrocarbon gas impurities in the recycled  $CO_2$  stream from stacked reservoirs on the optimization of  $CO_2$  EOR and associated storage.

Predicted seismoelectric response based on a forward model and acquire a baseline active seismoelectric (ASE) survey across the study field.

**BP1 (Denbury Site)** Start Date: 4/1/2022 End Date: 3/31/2023




#### **Summary**

#### **Budget Period 2**

Determine the reservoir response to pilot injection activities in a stacked complex in the context of associated  $CO_2$  storage.

Determine the effectiveness of ASE technology for ROZ characterization and MVA in a stacked storage complex.

Conduct detailed life cycle analyses (LCAs) of the project field injection test and a hypothetical stacked storage project in the central portion of the Williston Basin.



**BP2 (Denbury Site)** Start Date: 4/1/2023 End Date: 9/30/2025





Steve Smith Principal Geologist, Integrated Analytical Solutions ssmith@undeerc.org 701.777.5108 Energy & Environmental Research Center University of North Dakota 15 North 23rd Street, Stop 9018 Grand Forks, ND 58202-9018

www.undeerc.org 701.777.5000 (phone) 701.777.5181 (fax)



# **Budget Period 2 (Denbury Site)**

		Budget Period 2									
		2023		2024			2025				
<u>Deliverables</u>		Q18	Q19	Q20	Q21	Q22	Q23	Q24	Q25	Q26	Q27
Deliverable 7 (D7) – Establishment of Associated Storage	Task/Subtask	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jun 37 38 39	Jul Aug Sep
Field Test Site					→ DP1		20 23 30		04 00 00		40 41 42
Deliverable 8 (D8) – LCA and Technoeconomic	1.0 – Project Management, Planning, and Reporting	·									D10 🗸
Assessment of a Hypothetical Stacked	1.1 – Project Management and Planning										
Storage Project	1.2 – Project Reporting and Technology Transfer										D9 💙
Deliverable 9 ( <b>D9</b> ) – Data Submitted to NETL EDX	2.0 – Fluid Behavior Studies	'		I		,   		,   			
Deliverable 10 ( <b>D10</b> ) – Development of the Associated	2.1 – Sample Collection and Compositional Analysis			<b>М</b> 9		1		1		į l	
Storage Field Site	2.2 – MMP Studies										
	2.3 – EOS and PVT Studies				<b>D</b> 6	1 1 1		1			
Milestones	3.0 – Field Site Reservoir Characterization	i				i		i		l İ	
Milestone 9 ( <b>M9</b> ) – Sample Collection Completed	3.1 – Core Sample Identification and Collection					1		1		. !	
Milestone 12 ( <b>M12</b> ) – Baseline Active Seismoelectric Survey	3.2 – Laboratory Determination of Petrophysical Properties				D7	, , ,		1   			
Processing Complete	3.3 – Field Monitoring of Reservoirs									1	
Milestone 13 ( <b>M13</b> ) – Updated Static Geomodel Initiated	3.4 – Static Geomodeling	M13									
Milestone 14 (M14) – Initial Dynamic Modeling Initiated	3.5 – Dynamic Modeling	M14		•		M15 🔶		i I		, <b>i</b>	
Milestone 15 (M15) – Updated Dynamic Modeling Initiated	4.0 – Active Seismoelectric Technology Demonstration							1		!	
	4.1 – Active Seismoelectric Survey		<	M12							
Milestone 16 (M16) – Repeat ASE Complete –	4.2 - Follow-Up Active Seismoelectric Survey					M16 🔷		1 1			
Demonstration of ASE Technology	5.0 – Life Cycle Analysis			i							-
Milestone 17 ( <b>M17</b> ) – Life Cycle Assessment of Dual-Pilot	5.1 – Life Cycle Analysis of the Field Test			1				$\leftarrow$	M17		
Project Completed	5.2 – Life Cycle Analysis of Stacked Storage			1				i i	D8		
		<u>                                     </u>		:	1						



Critical Challenges. Practical Solutions.

**Denbury Gantt Chart** 

# **Budget Period 1 (Denbury Site)**

					Buc	dget	Perio	od 1				
	2022				2023							
		Q14			Q15	_		Q16	-		Q17	
Task/Subtask	Apr 1	May 2	Jun 3	Jul 4	Aug 5		Oct 7	Nov 8	Dec 9	Jan 10	Feb 11	М 1
	<u> </u>	-	Ŭ		•	Ū		Ŭ	Ŭ			
1.0 – Project Management, Planning, and Reporting												
1.1 – Project Management and Planning		√D4	7	D5								
1.2 – Project Reporting and Technology Transfer		$\diamond$	M8									
2.0 – Fluid Behavior Studies												
2.1 – Sample Collection and Compositional Analysis												
2.2 – MMP Studies												
2.3 – EOS and PVT Studies												
3.0 – Field Site Reservoir Characterization												
3.1 - Core Sample Identification and Collection												
3.2 – Laboratory Determination of Petrophysical Properties												
3.3 – Field Monitoring of Reservoirs												
3.4 – Static Geomodeling								> м	11		M	13
3.5 – Dynamic Modeling											M	14
4.0 – Active Seismoelectric Technology Demonstration												
4.1 – Active Seismoelectric Survey											$\diamond$	М
4.2 – Follow-Up Active Seismoelectric Survey												
5.0 – Life Cycle Analysis												
5.1 – Life Cycle Analysis of the Field Test												
5.2 – Life Cycle Analysis of Stacked Storage												

#### **Deliverables**

Deliverable 4 (D4) – Project Management Plan
 Deliverable 5 (D5) – Technology Maturation Plan
 Deliverable 6 (D6) – Fluid Behavior Studies Summary Report

#### **Milestones**

Milestone 8 (M8) – Project Kickoff Meeting Held
 Milestone 10 (M10) – Baseline ASE Survey
 Milestone 11 (M11) – Initial Static Geomodel Complete
 Milestone 13 (M13) – Updated Static Geomodel Initiated
 Milestone 14 (M14) – Initial Dynamic Modeling Initiated



Critical Challenges. Practical Solutions.

**Denbury Gantt Chart** 

#### **Deliverables**

Task/Subtask Number	Deliverable Title	Due Date
1.1	D4 – Project Management Plan	Submitted on May 2, 2022
1.1	D5 –Technology(ies) Maturation Plan (TMP)	Submitted on July 6, 2022
2.3	D6 – Fluid Behavior Studies Summary Report	January 19, 2024
3.2	D7 – Demonstration of Active Seismoelectric Technology for MVA	January 31, 2024
5.2	D8 – LCA and Technoeconomic Assessment of a Hypothetical Stacked Storage Project in the Williston Basin	February 29, 2025
1.2	D9 – Data Submitted to NETL EDX	September 30, 2025
1.0	D10 – Development of the Associated Storage Field Site	September 30, 2025



#### WBFCL Budget



