

Critical Component/Technology Gap in 21st Century Power Plant

Gasification Based Poly-generation:

Advanced Ceramic Membranes/Modules for Ultra Efficient


H₂ Production/CO₂ Capture for Coal-Based Poly-generation Plants

DE-FE0031930

Carbon Management Project Review Meeting

9-1-2023

- **Dr. Richard J. Ciora, Jr.**, Media and Process Technology Inc., Pittsburgh, PA
- **Professor Theo Tsotsis**, University of Southern California, Los Angeles, CA




Media and Process Technology Inc.



U.S. DEPARTMENT OF
ENERGY





MPT TECHNOLOGY BACKGROUND

Project Overview

Program: *DOE/FE “Critical Components for the 21st Century Power Plant”*

Funding: *Project Budget/Cost Share: \$2.38M (DOE: \$1.91M; Cost Share: \$0.47M)*

Overall Project Performance Dates: *October 1, 2020 - September 30, 2023 (36 months);
1-year No Cost Extension to September 30, 2024*

Project Participants:

- *Media and Process Technology Inc...Membrane manufacturer/supplier and technology developer (POC: Dr. Richard Ciora)*
- *University of Southern California...Membrane and system modeling (POC: Professor Theo Tsotsis)*


Overall Project Objectives:

Perform R&D to enable emerging inorganic membrane technology in Poly-generation based precombustion CO₂ capture.

- (i) Develop & fabricate a full ceramic multiple tube bundle w/ permeate purge capability.
- (ii) Fabricate multiple bundle housing/module as a pre-commercial scale unit.

MPT TECHNOLOGY BACKGROUND

Poly-generation: Inorganic Membrane Technology Role





Poly-generation: Advanced Inorganic Membranes

Project Objectives and Technical Program Summary


Primary Objective

Develop a permeate sweep/purge capable full ceramic multiple tube membrane bundle and multi-bundle module.

- ✓ This capability represents a Critical Technology Gap for advanced inorganic membranes in pre-combustion CO₂ capture.
- ✓ This capability is required to achieve the >30% COE cost savings target over baseline.
- ✓ Target operating conditions of 200 to >350°C and at up to 800 psig.

Technical Program Summary

- Develop and fabricate a permeate purgeable multiple tube bundle
- Design and fabricate a multiple bundle housing with appropriate seals
- Conduct a range of challenge tests to demonstrate bundle/housing stability
- Conduct long term performance stability testing at the target operating conditions
- Develop CFD model to predict membrane performance and inform module configuration
- Update the DSMP TEA for Poly-generation



M&P TECHNOLOGY BACKGROUND


Advanced Inorganic Membranes

- Wide range of membranes technologies
- Multiple tube bundles
- High temperature (>500°C)
- High pressure (>1,000psig)
- Stepping stone from the laboratory to field/commercial scales.


Ceramic Tube Extrusion



Intermediate Layer Deposition + Non-porous Tip and End Seals



Active Layer Deposition (CMS, Pd, Zeolite, ZIF, etc.)



Carbon Molecular Sieve Membrane



Pd-alloy Membrane



NaA, NaY, and MFI Zeolite Membranes



Package into Multiple Tube Bundle




Poly-generation: Advanced Inorganic Membranes

Motivation. Permeate Purge Capable, Dual End Open

Impact of Permeate Purge on H₂ Recovery

H₂ Partial Pressure Profile along Membrane Length
Feed Side (dashed line) and Permeate Side (solid line)



Deep H₂ recovery potential of counter current permeate purge/sweep.




Poly-generation: Advanced Inorganic Membranes

Permeate Purgeable; Face Seals; Multiple Bundle Housings


Advantages of Dual End Permeate Purgeable

1. Deep H₂ Recovery = Improved power production.
2. Higher membrane productivity = Lower cost.
3. Face seal capable = Simplified housing design.
4. Face seal capable = Higher packing density.
5. Higher packing density = Improved feed flow distribution; reduced bypass; higher performance.



Operating Target

250 to 400°C;
up to 800psig



Poly-generation: Advanced Inorganic Membranes

Current Status. Multiple Membrane Bundle Housing

Dual End CMS Membrane Bundles

Feed

Multiple Bundle Face Seal Housing


“First-of-its-kind”

Multiple Bundle Face Seal Housing

Reject


Permeate with Centerline Purge

Dense Tube Centerline Purge Port



Poly-generation: Advanced Inorganic Membranes


Project Structure...Team Member Roles and Tasks



Poly-generation: Advanced Inorganic Membranes

Project Overview: *BP1, BP2, NCE*

BP1



Candle Filter, Full Ceramic




Dual End, Full Ceramic



Radial



Face



COMSOL Model Basic Development

BP2




Dual End




Functional Dual End



Single Bundle, Radial Seal



Multiple Bundle, Face Seal




COMSOL Model Flow Distribution + Housing Design

NCE



Multiple Bundle, Face Seal




Long Term Performance and Challenge Testing in Multiple Bundle Membrane Housings + Predictive Performance Modeling



Poly-generation: Advanced Inorganic Membranes

Milestone Progress. *BP2*

Milestone	Milestone Description	Target Completion	Current Status	% Completion
I	Complete the CFD modeling of the dual ended bundle and multiple bundle module in U-bend and permeate sweep modes with recommendations for internal baffle and other flow management devices.	Q11	<p><u>Status:</u> Continuing “bundles in parallel” model development and simulation in multiple bundle housings. Simulation of Polygeneration WGR+Membrane for PFD, HMB, TEA update.</p> <p><u>Remain:</u> a. 6x Series/parallel bundles in module. b. Bundle and housing design/optimization.</p>	~90%
J	Prepare the CMS & Pd-Ag membrane tubes and 6x dual end bundles that meet the minimum leak and compression targets.	Q9	<p>Pd tubes, >120 of 120 (100% completion) CMS tubes, >120 of 120 (100% completion) Pd and CMS Bundles: 6x each (100% Complete)</p>	100%
K	Complete the shakedown and performance testing in permeate sweep mode.	Q7	Pd and CMS bundle performance verification in permeate sweep mode complete.	100%
L	Complete the testing of the 3 to 4 (6) bundles as base modular unit.	Q11 (Q12)	<p><u>Status:</u> - Testing of the multiple bundle housing (underway) - Mixed gas testing with permeate sweep (underway) Remain: a. Two bundle in series testing. b. Six bundle series/parallel testing.</p>	<p>Bundle: ~100% Testing: ~40% Overall: 50%</p>
M	Update the TEA for the new module design and process configuration with update for the Poly-generation scheme.	Q12	<p><u>Status:</u> • PFD and HMB process model simulation in DWSIM.</p> <p><u>Remain:</u> Update the PFD and TEA</p>	10%



Technical Progress: BP1

Milestone D/E. Fabricate Permeate Purgeable Bundles (complete)



1.5": 18 x 5.7mm Dense/Porous Tube w/ Centerline Permeate Takeoff


"First-of-its-kind"

2": 12 x 8.6mm Tube Dense/Porous Tube w/Centerline Permeate Takeoff

3": 4x 8.6mm Dense Tube w/Centerline Permeate Takeoff

2.5": 1x 5.7mm Porous Tube w/Centerline Permeate Takeoff (36-tube; 0.6m² surface area at 38")





Technical Progress: BP1

Milestone D/E. Challenge Test Permeate Purgeable Bundles

Membrane ID	Thermal Cycling, "Unloaded"			Membrane ID	Housing/Seal	Thermal Cycling, in Housing			Pressure Cycling, in Housing		
	250°C	400°C	450°C			250°C	400°C	450°C	250°C	400°C	450°C
PGI.5-PTA-1	13	(101) 160	25	PGI.5-PTA-1	Single Face, Metal	28	27	24		6	6
PGI.5-PT-2	0	(114) 173	0	PGI.5-PT-2							
PGI.5-PT-3	0	(91) 150	23	PGI.5-PT-3							
PGI.5-DT-2	8	63	2	PGI.5-DT-2							
PGI.5-DT-3	8	62	23	PGI.5-DT-3							
PGI.5-DT-6	0	0	34	PGI.5-DT-6							
PGI.5-DT-7	0	0	0	PGI.5-DT-7	Radial, Graphite	30					
PGI.5-DT-8	1	6	0	PGI.5-DT-8	Radial, Graphite	10					
PGI.5-DT-9	0	7	0	PGI.5-DT-9	Dual Face, Metal	10					
(PGI.5-DT-9)	0	0	0	(PGI.5-DT-9)	Single Face, Oring	10					
PGI.5-DT-10	0	4	0	PGI.5-DT-10	Dual Face, Metal	9	3	7		3	
PGI.5-DT-11	0	13	12	PGI.5-DT-11							
PGI.5-DT-12	0	12	24	PGI.5-DT-12	Dual Face, Oring				67		
PGI.5-DT-14	0	0	0	PGI.5-DT-14	Dual Face, Oring				39		
PGI.5-DT-15	0	0	0	PGI.5-DT-15	Dual Face, Oring				20		
PGI.5-DT-16	0	0	0	PGI.5-DT-16	Dual Face, Oring				75		
PGI.5-DT-6	0	34	16	PGI.5-DT-6							
PGI.5-DT-13	0	0	0	PGI.5-DT-13							
PGI.75-DT-1	0	27	0	PGI.75-DT-1	Radial, Graphite		8		9	(27) 62	
PGI.75-DT-2	0	24	0	PGI.75-DT-2							
PGI.75-DT-3	0	10	0	PGI.75-DT-3	Dual Face, Oring				6		
PGI.75-DT-4	0	8	0	PGI.75-DT-4	Dual Face, Oring				6		
PGI.75-DT-7	0	0	0	PGI.75-DT-7	Dual Face, Oring				29		
PGI.75-DT-8	0	0	0	PGI.75-DT-8	Dual Face, Oring				3		
PGI.75-DT-9	0	0	0	PGI.75-DT-9	Dual Face, Oring				26		
PGI.75-DT-10	0	0	0	PGI.75-DT-10							
PGI.75-DT-11	0	0	0	PGI.75-DT-11							
PGI.75-DT-12	0	0	0	PGI.75-DT-12	Dual Face, Oring				(0) 53		
PGI.75-DT-13	0	0	0	PGI.75-DT-13	Dual Face, Oring				(0) 53		
PGI.75-DT-14	5	(3) 6	0	PGI.75-DT-14							
PGI.75-PT-2	5	(3) 6	0	PGI.75-PT-2							
PG2-PT-1	0	0	33	PG2-PT-1	Radial, Graphite		9	24		4	
PG2-PT-2	0	6	8	PG2-PT-2							
PG2-PT-3	0	0	8	PG2-PT-3	Radial, Graphite			22		15	
PG2-PT-4	0	0	8	PG2-PT-4							
PG2-DT-1	0	4	22	PG2-DT-1							
PG2-DT-2	0	28	0	PG2-DT-2							
PG2-DT-7	0	0	0	PG2-DT-7	Radial, Graphite	21	12			17	
PG3-DT-1	12	8	0	PG3-DT-1							
PG3-DT-2	4	58	0	PG3-DT-2							
PG3-PT-1	0	(64) 125	0	PG3-PT-1							
PG3.5-DT-5	10	58	0	PG3.5-DT-5							
PG3.5-DT-6	2	0	0	PG3.5-DT-6							
Totals	68	1,052	238		Totals	118	99	117	412	116	6

Key
 PGxx-yy-ID#
 xx: Bundle Diameter
 yy: DT = Dense Tube
 PT = Porous Tube


BP1 Dense and Porous Tube Bundle Challenge Testing

Test Modes

1. Thermal Cycle (T/C); unloaded
2. T/C; constrained = radial or face seal housings
3. T/C; constrained; pressure cycled

Results Summary

1. 43 Successful Dual End Bundles
2. Dense and Porous Tube
3. >1,300 T/C unloaded
4. >300 T/C loaded housing
5. >500 T/C loaded, pressurized



Technical Progress: BP1

Milestone F/G. Dual End Bundle Housing Fabrication (complete)

2" Dual End Full Bundle Housing (Single Bundle and Dual Bundle) in Face Seal Configuration

"First-of-its-kind"




2" Dual End Bundle Radial Seal Housing




1.5" Dual End Bundle Radial Seal Housing



3" Dual End Bundle Radial/Face Seal Housing






Technical Progress: BP1

Milestone F. Face Seal Configuration Challenge Testing (*complete*)

High Temperature Face Seal Housing


High Pressure Performance Testing



Results Summary

1. Very high temperature and pressure capability demonstrated in face seal configuration.
2. Fixture leak rates well below the Milestone F and “stretch” target.






Technical Progress: BP2


Milestone J. Pd and CMS Membrane Tube Fabrication (Complete)

Dual End Pd Tubes

- A. Complete >120 tubes.
- B. Performance Average:
 - H_2 [GPU]: 3,700
 - H_2/N_2 [-]: >29,000




SEM Cross Section



Dual End CMS Tubes

- A. Complete >120 tubes.
- B. Performance Average:
 - He [GPU]: ~400
 - He/ N_2 [-]: >250
- C. Outliers (~20 tubes)
 - He [GPU]: ~550 to 700
 - He/ N_2 [-]: >300



Technical Progress: BP2


Milestone L. Pd Multiple Tube Bundle Fabrication (Complete)

Pd Membrane Bundle Performance. QC Testing

Target performance: (i) >75% of Average Single Tube Performance; (ii) N₂ Leak Rate <5 GPU

PdB19T.01

	Temp [°C]	H ₂ [GPU]	N ₂ [GPU]	H ₂ /N ₂ [-]	Comment [-]
Average Single Tube Performance	350	1,059	1.0	1,059	
Bundle PdB19T.01					
Day 9	331	464	2.2		
Day 16	331	469	2.4	192	
Day 17	331	N/A	2.6		
Day 17	331	912	2.5	367	Post Air Purge
	>75%?	86.1%	2.49	<5 GPU	
Day 18	336	559	3	215	
Day 21	338		2.9		
Day 21	338	986	2.7	368	Post Air Purge
	>75%?	93.1%	2.68	<5 GPU	



PdB19T.02


	Temp [°C]	H ₂ [GPU]	N ₂ [GPU]	H ₂ /N ₂ [-]	Comment [-]
Average Single Tube Performance	350	3,850	0.2	25,667	
Bundle PdB19T.02					
Day 1	350	2,617	1.31		
Day 1	350	3,637	1.34	2,712	
	>75%?	94.5%	1.34	<5 GPU	Post Air Purge
Day 2	350	2,898	1.28	2,257	
Day 7	350	1,145	1.27	904	
Day 7	350	3,261	1.24	2,623	Post Air Purge
	>75%?	84.7%	1.24	<5 GPU	

Tube ID [-]	Temp [°C]	H ₂ [GPU]	N ₂ [GPU]	H ₂ /N ₂ [-]	Comment [-]
Average Single Tube Performance	350	3,850	0.2	25,667	
Bundle PdB19T.03					
Day 1	350		0.88		
Day 4	350	1,403	0.91	1,547	
Day 4	350	2,083	1.02	2,052	Post Air Purge
Day 13	308	1,290	1.34	962	
Day 13	308	2,536	1.33	1,909	
	>75%?	65.90%	1.33	<5 GPU	
Day 14	308	973	1.36	717	
Day 14	308	2,847	1.32	2,156	Post Air Purge
	>75%?	74.00%	1.3	<5 GPU	
Day 17	311	1,322	1.37	963	
Day 17	311	3,141	1.38	2,278	Post Air Purge
	>75%?	81.60%	1.38	<5 GPU	
Day 20	311	1,394	1.48	939	
Day 20	311	3,275	1.43	2,287	

PdB19T.04, .05, .06

Tube ID [-]	Temp [°C]	H ₂ [GPU]	N ₂ [GPU]	H ₂ /N ₂ [-]	Comment [-]
Average Single Tube Performance	350	N/A	N/A	N/A	
Bundle PdB19T.04					
Day 1	RT	N/A	13.55	N/A	
	350	N/A			
Bundle PdB19T.05					
Day 1	RT	N/A	1.95	N/A	
Day 4	350	3,200	1.17	<5 GPU	
Bundle PdB19T.06					
Day 1	RT	N/A	1.65	N/A	
Day 3	350	4,300	0.94	<5 GPU	

On-spec





Technical Progress: BP2

Milestone L. Pd Bundle Challenge Testing (Complete; on-going)

Long Term Performance Stability Testing

PdB19T.03



Technical Progress: BP2

Milestone L. CMS Multiple Tube Bundle Fabrication (Complete)

CMS Membrane Bundle Performance. QC Testing

Target performance: (i) >75% of Average Single Tube Performance; (ii) N₂ Leak Rate <5 GPU

CMS DB19T.01		He [GPU]	N ₂ [GPU]	He/N ₂ [-]	Comment
Average Single Tube Performance		RT	N/A	4.1	
250	361	1.4	254		
Bundle CMS.DB19T.01					
Day 1	RT	N/A	11.3		
	250	214	6.3	34	High N ₂
Day 2	250	275	6.7	41	Overnight N ₂ purge
He Permeance Ratio [%]		76.2	[He permeance on spec; N ₂ permeance high]		
Bundle CMS.DB19T.01 (post polishing)					
Day 3	250	166	1.98	84	
Day 5	250	147	1.96	75	

CMS DB19T.03		He [GPU]	N ₂ [GPU]	He/N ₂ [-]	Comment
Average Single Tube Performance		RT	N/A	0.9	
250	351	1.6	224		
Bundle CMS.DB19T.03					
Day 1	RT	N/A	0.4		
	250	221	1.3	170	
Day 3	250	262	1.3	198	Start N ₂ purge.
Day 7	250	300	1.3	224	N ₂ purge.
Day 16	250	244	1.4	169	
Day 21	250	286	1.4	201	
Day 22	250	290	1.4		
Day 29	250	301	1.4	215	
He Permeance Ratio [%]		85.6	[He and N ₂ permeance on-spec]		


CMS DB19T.02		He [GPU]	N ₂ [GPU]	He/N ₂ [-]	Comment
Average Single Tube Performance		RT	N/A	2.5	
250	339	1.6	217		
Bundle CMS.DB19T.02					
Day 1	RT	N/A	1.6		
	250	225	1.5	147	
Day 2	250	270	1.6	170	Overnight N ₂ purge
He Permeance Ratio [%]		79.6	[He and N ₂ permeance on-spec]		



CMS DB19T.04		He [GPU]	N ₂ [GPU]	He/N ₂ [-]	Comment
Average Single Tube Performance		RT	N/A	0.8	
250	351	1.6	224		
Bundle CMS.DB19T.04					
Day 1	RT	N/A	5.9		
Day 1	250	N/A	14.8		Out of range for N ₂ .
He Permeance Ratio [%]		N/A	[He and N ₂ permeance on-spec]		
Patch Tubeshheet Leak					
Day 1	RT	N/A	1.8		
Day 1	250	N/A	1.6		Out of range for N ₂ .
He Permeance Ratio [%]		N/A	[He and N ₂ permeance on-spec]		

CMS DB19T.05		He [GPU]	N ₂ [GPU]	He/N ₂ [-]	Comment
Average Single Tube Performance		RT	N/A	0.9	
250	385	1.3	289		
Bundle CMS.DB19T.05					
Day 1	RT	N/A	3.0		
	250	N/A	3.7		
	250	346	3.8	92	N ₂ purge.
Day 3	250	370	3.6	104	N ₂ purge.
He Permeance Ratio [%]		96.2	[He and N ₂ permeance on-spec]		


CMS DB19T.06		He [GPU]	N ₂ [GPU]	He/N ₂ [-]	Comment
Average Single Tube Performance		RT	N/A	1.4	
250	344	1.3	258		
Bundle CMS.DB19T.06					
Day 1	RT	N/A	1.8		
	150	2.4			
	250	372	3.3	114	N ₂ purge.
	250	367	3.3	112	N ₂ purge.
	250	365	3.0	123	N ₂ purge.
He Permeance Ratio [%]		106.2	[He and N ₂ permeance on-spec]		
250	365	3.0	123		N ₂ purge.




Technical Progress: BP2

Milestone L. CMS Bundle Challenge Testing (Complete; on-going)

Long Term Performance Stability Testing (Face Seal Housing Configuration)



CMS DB19T.03



Technical Progress: BP2

Milestone L. Mixed Gas with Sweep Testing (Complete; on-going)

CMS DB19T.02

Mixed Gas with Sweep (Ar)
(Feed: 30/70 He/N₂; T: 250°C)

PdB19T.03


Mixed Gas with Sweep (Ar)
(Feed: 30/70 H₂/N₂; T: 340°C)

Part ID [#]	Feed Pressure [psig]	Sweep Rate [cc/min]	Actual Permeate Rate [cc/min]	Predicted Permeate Rate [cc/min]	Error Actual/Model [%]	Actual Reject He [%]
CMS DB19T.02						
No sweep	65	0	707	556	127.3	18.6
Co-current	65	308	1,035	1,081	95.8	16.4
Counter	65	308	1,124	1,040	108.1	12.3
No sweep	65	0	406	359	113.2	14.2
Co-current	65	308	714	778	91.8	11.6
Counter	65	308	863	820	105.2	5.5
No sweep	100	0	758	809	93.8	13.3
Co-current	100	308	1,131	1,179	95.9	11.5
Counter	100	308	1,280	1,212	105.6	9.2
No sweep	100	0	696	722	96.4	13.0
Co-current	100	308	1,006	1,122	89.6	10.5
Counter	100	308	1,136	1,119	101.5	7.2

Part ID [#]	Feed Pressure [psig]	Sweep Rate [cc/min]	Actual Permeate Rate [cc/min]	Predicted Permeate Rate [cc/min]	Stage	Error Actual/Model [%]	Actual Reject H ₂ [%]
PdB19T.03							
No Sweep	51.5	0	2,386	2,404	9.3	99.2	23.5
No Sweep	50.8	0	2,393	2,355	9.2	101.6	23.7
No Sweep	50.5	0	2,372	2,279	9.4	104.0	24.1
Co-current	51.5	751	4,511	4,297	17.8	105.0	19.1
Co-current	51.0	751	5,172	5,172	20.8	100.0	19.8
Counter	50.0	751	4,571	4,260	17.6	107.3	14.8
Counter	50.0	752	4,752	4,334	17.7	109.7	14.1

A. Reject Purity: Counter current purge delivers substantial reduction in fast gas reject purity (higher recovery).

B. Model Predictions: COMSOL model permeate rate in reasonably good agreement with actual performance.



Technical Progress: BP2


Milestone L. Mixed Gas with Steam Sweep (on-going)

Steam Sweep for Pressurized H₂ (permeate) Delivery
 (Feed: H₂/CO₂ at 50/50; T: 359°C)

Run ID	Run Mode	Feed Press [psig]	Perm Press [psig]	Feed [cc/min]	Reject [cc/min]	Total Perm Flow [cc/min]	Sweep Flow [cc/min]	Sweep Free Perm Flow [cc/min]	Target Reject Gas [-]	Actual Reject Comp [%]
Steam sweep										
374	Sweep	56.5	0	1,589	1,024	1,221	656	566	CO ₂	84
378	Sweep	57.0	0	1,635	1,085	1,106	556	550	CO ₂	84
385	No Sweep	57	0	1,442	1,001	441	0	441	CO ₂	78
Steam sweep at elevated permeate pressure.										
418	Sweep	91.5	0	1,896	1,127	2,756	1,987	769	CO ₂	N/A
419	Sweep	91.8	52	1,625	1,164	2,521	2,060	461	CO ₂	N/A
422	Sweep	91.9	56	1,625	1,171	2,550	2,090	460	CO ₂	N/A
No sweep at elevated permeate pressure.										
426	No Sweep	89.5	0	1,793	1,125	668	0	668	CO ₂	N/A
430	No Sweep	89.9	23	1,474	1,221	253	0	253	CO ₂	N/A
431	No Sweep	90	35.8	1,125	1,354	42	0	42	CO ₂	N/A
432	No Sweep	90	43	1,320	1,320	0	0	0	CO ₂	N/A

A. High productivity with sweep versus no sweep cases: Sweep enables deeper H₂ recovery under the same operating conditions.

B. Steam sweep of the permeate at elevated pressure: H₂ delivery at high purity and compressed to high pressure.



Technical Progress: BP2

“First-of-its-kind”

Milestone L. Multiple Bundle Module Testing (on-going)

1st Bundle Shakedown Testing in the 3-Bundle Housing

CMS DB19T.04
Mixed Gas Testing
 (Feed: 70/30 He/N₂; T: 250°C)



CMS DB19T.04

Dense Tube Dummy Bundle

Feed Pressure [psig]	Actual Permeate Rate [cc/min]	Predicted Permeate Rate [cc/min]	Error Permeate Mod [-]	Stage Cut [%]
45.0	1,110	1,056	1.05	65.9
45.0	1,095	1,142	0.96	58.0
45.0	1,180	1,304	0.91	49.7
45.0	1,371	1,438	0.95	46.0
65.2	1,800	1,676	1.07	68.8
65.2	1,734	1,945	0.89	52.2
65.2	1,915	2,143	0.89	46.8
80.1	2,125	2,140	0.99	64.4
80.1	2,284	2,555	0.89	51.2
63.0	2,013	1,823	1.10	66.1
63.0	1,729	1,717	1.01	62.5
63.9	1,544	1,621	0.95	61.3
63.9	1,528	1,533	1.00	64.3



A.

A. Good agreement between actual and predicted permeate rate in the multiple bundle housing: **Error typically under 5% with some excursions to 10%. Consistent with single bundle housing results.**




Technical Progress: BP2

Milestone I/M. COMSOL Model Predictions (on-going)

Three Bundle in Parallel Modeling




Baffled with Side Entry/Center Take-off




Base Case

Composition: 50/50 He/N₂
Pressure: 100psig feed; 0 psig permeate
Feed Rate: 257cc/min per tube
He Permeance: 1 m³/m²/hr/bar (365 GPU)
He/N₂ Selectivity: 100
He Recovery, Ideal: 74.4%



Baffled with Side Entry/Exit

Hybrid Baffled with
"Multiple" Side
Entry/Center Take-off



Technical Progress: BP2


Milestone M. Poly-generation PFD and TEA Update (*on-going*)


CMS Membranes (coupled with WGS reactor)

1. Deliver enhanced CO conversion with reduced water consumption versus conventional WGS.
2. "Roughing" step to recover the bulk H₂ and reduce load on the CGCU
3. Ideal location for CMS membrane due to its material and temperature stability.

Pd-Alloy Membrane



1. High selectivity yields excellent residual H₂ recovery.
2. Ideal to achieve the CO₂ capture and purity targets.





Technical Progress: BP2

Milestone I/M. Sweep Modeling for TEA Update (on-going)




Operating Conditions
P_f: 769 psig
P_p: 300 psig
Sweep: 5% of feed rate

Feed Composition
H₂: 40.5%
CO₂: 27%
H₂O: 24.9%
CO: 5.9%
Other: Balance

A. Deep H₂ Recovery on Counter Current Sweep: Counter current purge delivers substantial improvement in H₂ recovery.


B. Ultimate result...substantial cost reduction: Reduced membrane area; more efficient purge gas utilization; increased power production → >30% reduction in COE for CO₂ capture




Summary. BP1/BP2

Summary of Project Status and Successes

- Dual End Bundle Fabrication and Mechanical Challenge Testing (BP1).** Successfully fabricated 43 dual end purgeable dense and porous tube bundles at up to 3" diameter ("first-of-its-kind"). No failures in over 2,000 challenge tests up to 450°C.
- Bundle Seal Leak Performance Testing (BP1).** Demonstrated bundle seal leak rates well below the 1 GPU target in radial and face seal style housings at temperatures to 400°C and pressures to 800psig ("first-of-its-kind").
- Pd and CMS Dual End Bundles (BP2).** Six of each type; 18-tube + center-line permeate purge. ("first-of-its-kind").
- Performance Evaluated Pd and CMS Dual End Bundles (BP2).** Bundle mixed gas testing with co-/counter current permeate sweep ("first-of-its-kind").
- Performance Evaluated First 3-bundle Housing (BP2).** Good agreement with model predictions with the first CMS membrane bundle ("first-of-its-kind").
- Developed a COMSOL based CFD Model for Membrane Performance Prediction (BP1/BP2).** Successfully predicted the mixed gas performance of the 18-tube membrane bundles with permeate sweep. Targeting multiple bundle housing design optimization, performance modeling, and Poly-generation process development/TEA.






Project. BP2/NCE


Next Step

1. **Complete the testing of the first multiple bundle in parallel housing (3-bundle) with permeate sweep.** Battery of mixed gas testing with permeate sweep demonstration of the 3-bundle in parallel housing. Simulated gasifier off-gas with N₂ and steam permeate sweep.
2. **Fabricate and conduct testing with additional multiple bundle housings.** Additional 3-bundle and a 6-bundle housing (3-parallel x 2-series).
3. **FOCUS: Conduct long term challenge testing with multiple bundle housings.** Confirm the performance and mechanical stability of the bundles, seals, and overall housing design.
4. **COMSOL CFD Model for Membrane Performance Prediction.** Large scale housing design optimization; Poly-generation process and TEA development.
5. **Fabricate the first 4" (~2m²) dual end bundle.** Demonstrate/highlight scalability.

50MW = ~1,000m²
CMS Membrane Area



21 Bundle at 2m² each (4")
50MW = 24 Housings



Media and Process Technology Inc

Acknowledgements

The material presented here is based upon work supported by the Department of Energy under Award Number DE-FE0031930.

Disclaimer. This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Questions?