

Enhancement of Carbon Capture Reactor Performance

Project Number: DE-FE0032217

Performing Organization: University of Kentucky

Principal Investigator: Jesse Thompson

AOI-4: Carbon Capture R&D - Laboratory-Scale Testing of Highly-Efficient Materials
or Novel Concepts for Natural Gas Combined Cycle (NGCC) Power Plants


Disclaimer

This material is based upon work supported by the Department of Energy under Award Number DE-FE0032217

"This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."

Project Overview

- Develop novel carbon capture reactor components that contribute to increased CO₂ mass transfer through increased turbulent gas-liquid interfaces and improved solvent wetting within the absorber
- Design advanced components for Natural Gas Combined Cycle (NGCC) CO₂ capture plants targeting 97% or greater carbon capture efficiency and make significant progress toward a 40% reduction in the cost of carbon capture vs. a reference NGCC plant with carbon capture.
- **Project Timeline:** 2/1/2023 - 8/31/2024
- **Funding:** Federal - \$1M; CS - \$250K; Total - \$1.25M




Goals

Demonstrate the ability to efficiency capture CO₂ at 90-97% or greater and make significant progress towards a 40% reduction in cost of capture versus reference NGCC power plant with carbon capture at the same carbon capture efficiency




- ★ Reduction of heat and power requirements
 - Using water-lean solvent (WLS)
- ★ Maximize CO₂ capture volumetric productivity to reduce the footprint and capital of carbon capture for an NGCC plant
 - Improve wetting of solvent on structured packing with water-lean solvents and use of additive manufactured (3D printed) and polymers to enhanced the surface substructure to increase liquid turbulence and mixing

Absorber Packing

Commercial Packing




3D Printed Polymer




3D printed and polymer packing can be easily modified to have an additional surface sub-texture that further improves liquid turbulence on the surface translating to improved CO₂ capture rates

CFD-Modeling of Surface Mixing




- Surface texture amplitude
 - Liquid film thickness
- Local mixing within the liquid




Solvent Wetting - Contact Angle

The wetting (CA) of an aqueous amine solvent (AAS) is typically in the 30-60° range depending on the solvent and CO₂ loading

Rich - AAS on Stainless Steel



Rich - AAS on Nylon



Water-lean solvents (WLS) can have CAs in the 10-20° range, depending on CO₂ loading, but have similar CAs on steel and polymer surfaces


WLS on Stainless Steel



WLS on Nylon





UK NGCC Process




Initial TEA Estimates

Assuming a $\frac{1}{4}$ reduction in the packing height through process intensification and enhancement in CO_2 mass transfer, and using a lower cost material (polymer), can result in a significant (52%) reduction in the construction cost of the absorber.




	Case1 - MP 250Y	Case 2 - Polymer Packing
Packing Height (ft)	40	30
Tower Diameter (ft)	25	25
Shell Height (ft)	80.00	70.00
Shell/Packing Ratio	2.00	2.33
Total Shell Cost (\$)	\$178,708.00	\$164,461.00
Packing Volume (ft ³)	19,635	14,726
Unit Cost for Packing (\$/m ³)	\$4,012.00	\$2,407.20
Unit Cost for Packing (\$/ft ³)	\$113.61	\$68.16
Total Packing Cost	\$2,230,669	\$1,003,801
Total Column Cost	\$2,409,377	\$1,168,262
Cost Reduction		52%

Initial TEA Estimates




(Very) preliminary estimates for NGCC with the UK WLS process and enhanced packing shows a potential reduction in the levelized cost of electricity from reductions in the absorber column height and related components

Technical Tasks




Design and Fabrication of Absorber Reactor Components



Bench Testing of Absorber Components




Dynamic Contact Angle



Static Contact Angle (CA) measures the bulk repulsive/attractive interactions between the surface and solvent, whereas the Dynamic Contact Angle replicates the downward flow of the solvent on the packing and better describes the actual wetting profile on the packing

CO₂ Capture System

UK 3" CO₂ Capture Evaluation System w/ Simulated NGCC (~4% CO₂)



Milestones and Deliverables

Task Number	Title	Planned Completion Date	Actual Completion Date	Verification Method
1	Updated Project Management Plan	2/28/2023	2/24/2023	PMP File
1	Kickoff Meeting	3/31/2023	3/13/2023	Presentation File
1	Subcontracts Established	4/30/2023	5/26/2023	Written Verification
1	Initial Technology Maturation Plan	4/30/2023	4/26/2023	Appended to Quarterly Report
1	Final Technology Maturation Plan	5/31/2024		Appended to Quarterly Report
1	State Point Data Table Revision	5/31/2024		Appended to Quarterly Report
2	Identification of polymer that is stable for 5000 hr in the water-lean solvent at absorber temperatures of > 50 °C	11/30/2023		Written Verification
2	Production of 72" height of 3" diameter packing for installation into UK mini-scrubber	11/30/2023		Written Verification
3	Absorber components capable of > 20% increase in CO ₂ mass transfer from bench-scale testing	5/31/2024		Written Verification
4	Initial Techno-Economic Analysis (TEA)	7/31/2023		TEA Report
4	Final Techno-Economic Analysis	5/31/2024		TEA Report


Success Criteria

Task #	Due Date	Success Criteria (Task #)
2	11/30/2023	<u>Fabrication of Polymer Packing</u> : Packing prototype with 10% increase in solvent wetting as measured by dynamic contact angle
3	5/31/2024	<u>Testing of Absorber Components</u> : A completed test for the absorber components to achieve the target >20% mass transfer enhancement
1,4	5/31/2024	Collection of experimental data for update of <u>TMP</u> , <u>State Point Data Table</u> and <u>TEA</u>
4	5/31/2024	<u>TEA</u> : Demonstrate 97% capture efficiency and significant progress toward a 40% reduction in the cost of carbon capture vs. a reference NGCC plant with carbon capture.

Project Schedule

Task Number and Name	Length (months)	Start	End	Leader	Federal FY 22/23 - 23/24							
					Q2	Q3	Q4	Q1	Q2	Q3	Q4	
1. Project Management and Planning	19	2/1/23	8/31/24	UK CAER								
1.1 Project Management Plan	19	2/1/23	7/31/24									
1.2 Technology Maturation Plan	19	2/1/23	7/31/24									
1.3 State Point Data Table	16	2/1/23	5/31/24									
<i>M1: Updated Project Management Plan</i>	1		2/28/23		★							
<i>M2: Kickoff Meeting</i>	2		3/31/23		★							
<i>M3: Establish Subcontracts</i>	3		4/30/23			★						
<i>M4: Initial Technology Maturation Plan (TMP)</i>	3		4/30/23			★						
<i>M5: Final Technology Maturation Plan (TMP)</i>	16		5/31/24								★	
<i>M6: State Point Data Table</i>	16		5/31/24								★	
2. Design and Fabrication of Absorber Reactor Components	10	2/1/23	11/30/23	UK CAER								
2.1 Physical Property Measurements of WLS co-solvents	3	2/1/23	4/30/23									
2.2 Polymeric material stability	9	2/1/23	10/31/23									
2.3 Component Design Specifications	6	2/1/23	7/31/23									
2.4 Fabrication of Absorber Reactor Components	4	8/1/23	11/30/23									
2.5 Dynamic contact angle measurements	7	5/1/23	11/30/23									
<i>M7: Identification of polymer that is stable for 5000 hrs in the WLS at absorber temperatures of > 50 °C</i>			10/31/23						★			
<i>M8: Production of components for installation into UK mini-scrubber</i>			11/30/23						★			
3. Bench testing of Absorber Components	9	12/1/23	8/31/24	UK CAER								
3.1 Modification of CO2 mini-absorber	1	12/1/23	12/31/23									
3.2 Testing of Absorber Components	5	1/1/24	5/31/24									
3.3 Solvent and Component Degradation	8	1/1/24	8/31/24									
<i>M9: Absorber components capable of > 20% increase in CO2 mass transfer from bench-scale testing</i>			5/31/24								★	
4. Techno-Economic Assessment with Technology Gap Analysis	19	2/1/23	8/31/24	EPRI								
<i>M10: Issue initial TEA</i>			7/31/23				★					
<i>M11: Issue Final TEA Report</i>			5/31/24								★	

Technology Development



Acknowledgements

This material is based upon work supported by the Department of Energy under Award Number DE-FE0032217

- DOE-NETL: Nicole Shamitko-Klingensmith



U.S. DEPARTMENT OF
ENERGY



- UK: Keemia Abad, Kunlei Liu, Lisa Richburg, Moushumi Sarma



- EPRI: Abhoyjit Bhowan



- PPL

