

FWP-FEAA 384

Intensified, Flexible, and Modular Carbon Capture Demonstration with Additively Manufactured Multi-Functional Devices

Costas Tsouris, Josh Thompson, Amiee Jackson, Gyoung Jang, Dhruba Deka, Scott Curran, Scott Palko, Jonathan Willocks, Jason Case, Jim Parks
Oak Ridge National Laboratory

National Energy Technology Laboratory
2023 Carbon Management Project Review Meeting

August 28 – September 1, 2023

ORNL is managed by UT-Battelle, LLC for the US Department of Energy

Project Overview

- **Funding provided by DOE-FECM: \$1.878M**
- **Overall Project Performance Dates:**
January 1, 2021 – December 31, 2023
- **Previous Projects:**
Focused on design, manufacturing, and validation of intensified devices for enhanced carbon capture using MEA and low-aqueous solvents
 - Intensified device enhances mass transfer, just like commercial packing, and allows a third fluid (coolant) to remove the heat of reaction between CO₂ and amines
 - Jang et al., “Process Intensification of CO₂ Capture by Low-Aqueous Solvent,” Chem. Eng. J., **426**, 131240, (2021)
- **Motivation for the current Project: Scalability of the intensified device**




Technology Background: How the Intensified Device Works






Intensified
Device

Column A



- Miramontes et al., Additively Manufactured Packed Bed Device for Process Intensification of CO₂ Absorption and Other Chemical Processes, Chem. Eng. J., **388**, 124092, (2020)

How The Device Works



- Miramontes et al. Process Intensification of CO₂ Absorption Using a 3D Printed Intensified Packing Device, AIChE J. **e16285**, (2020)

- Depending on operating parameters, 5-25% CO₂ capture enhancement was observed


- **Safety incident in the laboratory, using Column A: Worker exposure to CO₂ solvent**
- **A Lessons Learned was published for other laboratories**

Overall Project Objectives for FEAA 384




- Design and construct a larger-scale column (Column B) than the one previously tested (Column A)
- Scale up CO₂ capture from 0.1 t/day to 1 t/day
- Demonstrate Column B construction with modular packing elements and intensified devices
- Demonstrate 15% enhancement in CO₂ capture for aqueous and low-aqueous amine-based solvents at realistic operating conditions
- Demonstrate effective capture for different CO₂ gas compositions and during process transients, with capacity ramping up and down anticipating the intermittency of renewable energy

Task 2.0 – Design Evaluation and Construction of Column B

Modeling Framework:




Modeling MEA w/Intrastage Cooling




- Simulation of intrastage cooling with device showed good agreement with experimental data from Miramontes *et al.* (2020)
 - CO_2 capture difference: all $\leq 5\%$
- CO_2 capture improvement and temperature profile agreement suggest modeling framework for heat transfer is accurate in predicting device performance

Modeling RTI's Low Aqueous Solvent w/Intrastage Cooling




Simulated vs experimental CO₂ capture rate of LAS under adiabatic (black) and cooling (red) conditions. Closed symbols are predictions from *Model 1*, and open symbols are from *Model 2*. Solid black line is parity line, and dashed lines are +/- 10% capture rate.

Process Diagram for Column Design




Column B Construction: Equipment in CVO Area




Cell 5

Column B Construction: Equipment in Cell 5




Task 3.0 – Advanced Manufacturing and Core Metrics Testing of Intensified Device for Column B Scale-up from 8” to 12” Diameter

- New unit cell geometry: Column A




- Added flanges for device integration with the column
- Added supports for printability



Scaled-Up Intensified Devices




12-inch diam., 16-inch height




8- and 12-inch devices
(volume ratio: 5.3)

Modular Column Design





- Temperature Indicator
- Pressure Indicator
- Flowmeter



Two Sulzer Mellapak 250Y packing elements per each module

Core Metrics Testing of Intensified Device: Pressure Drop



Pressure drop along the intensified device is relatively high


Design Revisions for Intensified Device

- Changes to reduce pressure drop
 - Increased channel width
 - Increased triangle height
 - Increased void fraction




	Void Fraction
Before	60.0%
After	81.7%

- Collaborating with CCSI2 (Panagakos) for further optimization of the device geometry



Before



After





Core Metrics Testing of Intensified Device: Pressure Drop and Holdup vs F_g for Different Liquid Flowrates



Pressure drop and holdup increase sharply near flooding

Core Metrics Testing of Intensified Device: Heat Transfer




(a) Water flowrate 5 LPM, zero air flow

(b) Water flowrate 16.8 LPM, air flowrate 1500 LPM


(c) Water flowrate 5 LPM, air flowrate 1500 LPM.

Feed water temperature is 60°C and feed air temperature is 25°C in all cases

Core Metrics Testing of Intensified Device: Heat Transfer



Average temperature reduction via cooling through intensified device at liquid-to-gas mass-flowrate ratios: $L/G = 0, 2.8,$ and 9.4



Heat transfer experiments without cooling (black) and with cooling using 2.95 L/min water at 20 C (red). Lines represent simulation results

Task 4.0 – Using NTRC Engine Combustion Exhaust to Simulate Various Flue Gas Compositions

- Feed gas will be generated with natural gas generator set
 - 100 kW generator
 - 9L natural gas engine
 - Electricity dissipated by load bank
- Exhaust gas generation:
 - Up to 1.4 tons CO₂/day
 - Water dew point and temperature managed by heat exchangers



Genset installed in the Mezzanine area



Load bank installed in the Mezzanine area

Summary

- Modeling work was used for column design
- Column construction and hydraulic & heat-transfer testing completed
- Project delays related to (1) safety incident and (2) personnel changes
- Mass transfer milestones are the focus of current work
 - CO₂ capture experiments using aqueous MEA
 - CO₂ capture experiments using LAS (RTI)
 - Performance evaluation under transient conditions

} Tasks 6-9



Commercialization

- Currently helping RTI demonstrate enhanced CO₂ capture from a cement plant using intensified packing devices (AMMTO funded project)
- Plan to demonstrate further scalability in a future project

Products from FEAA384

- Thompson, Tsouris, “Rate-Based Absorption Modeling for Post-Combustion CO₂ Capture with Additively-Manufactured Structured Packing”, *Ind. Eng. Chem. Res.*, **60**, 14845, (2021). <https://doi.org/10.1021/acs.iecr.1c02756>
- Tarancon, A., et al. “2022 Roadmap on 3D Printing for Energy,” *JPhys Energy*, **4**, 011501 (2022). <https://doi.org/10.1088/2515-7655/ac483d>
- Lai et al. “Multifunctional Intensified Reactor Device with Integrated Heat and Mass Transfer,” **Patent # 11,504,692 B2** (2022).

Acknowledgments

- Office of Fossil Energy and Carbon Management
- RTI International, Marty Lail
- David Lang and Justin Brown of NETL