

# Novel Modular Heat Engines with Supercritical CO<sub>2</sub> Bottoming Cycle Utilizing Advanced Oil-Free Turbomachinery: PHASE 2 Update

## GE Research Center

**UTSR 2023**

DE FE-00031617

10/31/2023

### TEAM

Bugra Ertas, PI  
Tom Adcock  
Rahul Bidkar  
Ben Conley  
John Powers  
Dave Torrey  
Xiaohua Zhang



# DISCLAIMER

This material is based upon work supported by the Department of Energy, NETL, under Award Number DE-FE00031617. This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.



# BACKGROUND

## APPLICATION AND MOTIVATION

- Natural Gas Compressor Stations
- Utilize waste heat sCO<sub>2</sub> Brayton power cycle
- 11pts Eff. Increase 41% to 52% cycle eff.

## TECHNICAL APPROACH




- 2 Drivetrain config. Dual spool approach
- Elimination of gearbox and use of CO<sub>2</sub> bearings
- Hermetic casing; free of CO<sub>2</sub> emissions
- Immersed generator in high density CO<sub>2</sub>

## TECH RISKS

- Rotor-bearing system dynamics
- Radial bearing damping and load capability
- Thrust bearing load capacity
- Thermal stability/design of hermetic machine

## OTHER POTENTIAL APPLICATIONS

- Concentrated solar power cycles
- Nuclear power cycles





# PHASE 2 SCOPE AND OBJECTIVES

- Develop design practices and methods
- Validate mechanical/thermal/electrical systems & design

(1) drivetrain rotordynamics

(2) thrust bearing load capacity


(3) thermal system design




high-speed driveline

TURBOMACHINE PHASE 1

TEST RIG



# TEST RIG LAYOUT




53" (1.35m)

**Max Speed = 27 KRPM**  
**Max Rotor Thrust = 1,500 lbs**  
**Max Casing Pressure = 400 PSI**  
**Working Fluid = CO<sub>2</sub>**




# ROTORDYNAMIC MEASUREMENTS AND BEARING DETAILS





# THRUST CHAMBER AND THRUST BEARING TESTS

- Thrust bearings are traditionally the weak link for gas bearings
- Test rig has ability to apply varying load through a thrust chamber
- Critical measurements are:
  - Axial load
  - Film gap
  - Thrust runner vibration/displacement
  - Flow, pressures, and temperatures




• Example measurements from, Ertas, 2021, ASME JGTP, 143/ 081024




# THERMAL SYSTEM DESIGN VALIDATION

- 1D Advection network iterates with structural thermal FEA model → iterates on heat flow between models, nodal and metal temperatures
- 1D energy balance at each node accounts for:
  - rotor windage, cavity swirl
  - calculates convective HTC
  - heat gen sources in EM/bearings
  - heat sink in H<sub>2</sub>O jacket
- Areas of concern:
  - EM temperatures
  - bearing temperatures
  - bearing and EM windage/power loss
- Experiments will allow benchmarking of thermal model



Bidkar, 2023, ASME Turboexpo PapeGT2023\_103989





# ADDITIVE MANUFACTURING PROGRESS: INCO 718 COMPONENTS

Compressor BRG

BUILD   
MACHINE 





Comp. BRG Housing

BUILD   
MACHINE 



Thrust BRG

BUILD   
MACHINE 



Midspan BRG Housing

BUILD   
MACHINE 




Midspan BRG

BUILD   
MACHINE 



Generator BRG


BUILD   
MACHINE 



# DAMPER COUPON TESTING


## Rotordynamics

- Machine concept has high power density and requires high speed operation
- Key risk in concept is operating above third critical speed
- To mitigate this risk → 3 bearing layout
- However, for reliable operation need a certain K and C



## Bearing support stiffness and damping


- A ¼ section bearing damper coupon has been built
- Coupon to have simple testing conducted on test bench
- Static force deflection → static stiffness
- Dynamic single frequency excitation testing → damping and stiffness



# CASING ASSEMBLY FABRICATION AND MACHINING

## Casing Material

- 4340 rotor forgings located
- Casing components to be black oxide coated
- Hydraulic pressure testing




## Assembly Machining

- Final precision machining to be conducted as an assembly
- Critical bores will be machined in one setup
- All radial bores to have runouts within 0.001"

## Current Progress



- Drawing finalized and major forgings received by vendor



# GAS SUPPLY SKID AND TEST CELL

- CO<sub>2</sub> delivery powered by 8 gas boosters
- Gas boosters driven by high pressure air
- Gas boosters deliver CO<sub>2</sub> for:
  - Bearing pressurization
  - Mag gap cooling of EM
  - Cavity cooling
  - Bearing cooling
  - Casing pressurization
- Skid also possesses:
  - Heat exchangers
  - Pressure vessels and settling tanks
  - FMs, TCs, PTs
  - Emergency backup air system
  - H<sub>2</sub>O cooling to EM water jacket


	Flow Temp Entering Rig (°C)	Case # 1	Case # 2
		Baseline	Thrust Brg. ID Cooling
		CO <sub>2</sub> Flow 0.65 kg/s	CO <sub>2</sub> Flow 0.76 kg/s
		400 psia	400 psia
<b>Water Flow gal/min</b>	29.44	1.4	1.4
<b>Thrust Chamber kg/s (% rig flow)</b>	21	0.31 (48%)	0.31 (41%)
<b>Gap Cooling kg/s (% rig flow)</b>	18.3	0.10 (16%)	0.10 (14%)
<b>3 Radial Brg kg/s (% rig flow)</b>	29 to 29.3	0.073 (11%)	0.073 (10%)
<b>Thrust Brg kg/s (% rig flow)</b>	40	0.031 (5%)	0.031 (4%)
<b>Rad. Brg # 1 Cooling Flow kg/s (% rig flow)</b>	18	0.1 (15%)	0.1 (13%)
<b>Rad. Brg # 2, 3 Cooling Flow kg/s (% rig flow)</b>	18	0.03 (4%)	0.03 (4%)
<b>Thrust Brg. ID Cooling kg/s (% rig flow)</b>	18	0 (0%)	0.113 (15%)



# Schedule and Tasks

## TEST RIG DESIGN

- bearing system ✓
- structures ✓
- electrical system ✓
- thermal system design ✓
- rotordynamics ✓
- test loop ✓



## ADDITIVE COMPONENT BUILDS

- compressor bearing ✓
- compressor bearing housing ✓
- midspan bearing ✓
- midspan bearing housing ✓
- generator bearing ✓
- thrust bearing ← IN PROGRESS



## PARTS MACHINING AND FABRICATION

- probe brackets ✓
- casing assembly ✓
- rotor system ✓
- laby seals ✓
- windage shield/cooling tubes/load shank ✓




← IN PROGRESS

## EQUIPMENT PROCUREMENT

- CO<sub>2</sub> flow loop ✓
- electric machine armature ✓
- CF wound PM EM rotor ✓
- EM VFD ✓

← IN PROGRESS



EM VFD

Program Activities	GE Research	Year 1		Year 2		Year 3		Year 4											
		Quarter:		Quarter:		Quarter:		Quarter:											
		1	2	3	4	1	2	3	4	1	2	3	4						
<b>Task 1: Project management</b> Coordination, schedule & risk management, reports & publications, conf. travel <i>Deliverable: Quarterly progress reports</i>	X X X																		
<b>Task 2: Bearing design &amp; fabrication</b> Bearing design Bearing fabrication <i>Milestone: Bearing design completed</i> <i>Milestone: Bearing fabrication completed</i>	X X X																		
<b>Task 3: Test rig design, pressure vessel &amp; flow loop procurement</b> Rig & flow loop design Rig procurement <i>Milestone: Rig design completed</i> <i>Milestone: Detailed drawings released</i> <i>Milestone: Pressure vessel &amp; flow loop procured</i>	X X X																		
<b>Task 4: Electric machine design &amp; procurement</b> EM design & consult EM procurement <i>Milestone: EM design completed</i> <i>Milestone: Detailed drawings released</i> <i>Milestone: EM procured</i>	X X X																		
<b>Task 5: Test rig fabrication &amp; assembly</b> Rig parts machining Loop & rig assembly DAQ & rig commissioning <i>Milestone: Test rig &amp; flow loop assembled; shake-out completed</i>	X X X X																		
<b>Task 6: Full-scale rotor testing</b> Testing <i>Milestone: Testing completed</i>	X X																		
<b>Task 7: Modular heat engine costing</b> Roll-up of latest cost data and information <i>Milestone: Costing completed</i>	X X																		

◆ Denotes Milestone ▼ Denotes Deliverable

