


Integrated Bench-Scale Testing of a Structured Sorbent for Direct Air Capture

DE-FE0032243

Presented by
Andrew Tong
Arnold C. Toppo
Raghubir Gupta

2024 Carbon Management Research Project Review Meeting



Project Overview

Title	Integrated Bench-Scale Testing of a Structured Sorbent for Direct Air Capture	
Funding Solicitation	DE-FOA-0002614 AOI2B	
Award No.	DE-FE0032243	
Period of Performance	7/01/2023 - 06/30/2026	
Project Funding	DOE: \$3M	Cost-Share: \$0.75M
Overall Project Goal	Design, build, and test an integrated bench-scale DAC system for continuous production of >1 TPY CO ₂ using the electrically heated structured material assembly (SMA)	
Project Participants	Susteon Inc. and TotalEnergies	
DOE/NETL Project Manager	Mr. Zachary Roberts	

Technical Approach and Project Scope


Objective:

Reduce the overall cost of DAC through the development of a structured material assembly (SMA) and integrated DAC system design with sorbent regeneration using low-carbon electricity (TRL 4 to TRL 5).

Approach

1. Perform a detailed technical risk assessment to identify high-risk areas.
2. Design and optimize SMA manufacturing and performance.
3. Design, build, test integrated Bench-scale system for >1TPY CO₂ production.
4. Refine and update process and economic model.
5. Refine commercialization plan.

Susteon's Sorbent-Based DAC Technology



Innovative

Efficient heating to minimize heat losses




Synergistic

Beneficial effect of atmospheric moisture



Efficient

Low desorption energy
(~65 kJ/mol)




Inexpensive

Abundantly available sorbent precursors



Accelerated


Fast adsorption + desorption kinetics



Scalable

Modular design utilizing existing supply chains

Technology Roadmap



TRL

4

3

2

1



2020

2021

2022

2023

Bench-Scale Component Testing (1 kg/day)



Lab-scale Reactor Testing (3 g/day)

- ❑ Verified sustained performance of structured sorbent
- ❑ Proof of concept resistive layer coating showing high CO₂ desorption rates



Lab-scale TGA Testing

- ❑ Na-based sorbent selected
- ❑ Elucidation of reaction pathway

- ❑ Optimized sorbent and heating material washcoat synthesis on selected structured sorbent
- ❑ Verified performance of structured sorbent for adsorption and desorption under Joule heating

Bench-Scale Component Testing (FE0032118)

1 kg/day Bench Unit Design



Bench-Scale Component Testing (FE0032118)

CO₂ Capacity Summary

Adsorption


Air Flow: 413 slpm (65 lb/hr)
Temperature: 20-30°C

WHSV: 270 hr⁻¹ (based on sorbent mass)
Relative humidity: ~ 50%
Duration: 45 minutes


Desorption

N₂ flow: 4 slpm
Max temperature: 100°C



Ramp rate: 8°C/min
Vacuum purge pressure: -8 psig
Duration: 120 minutes



Technology Roadmap



Structure Material Assembly (SMA)



- ✓ High electric to thermal heating efficiency (up to 95%)
- ✓ Low thermal mass (~50 wt% washcoat loading)
- ✓ Low pressure drop (<200 Pa)


Initial TEA Results

SMA Performance Drives Cost of CO₂ Production

KPI


Impact

1. CO ₂ Capture Kinetics	→	Productivity
2. CO ₂ Working Capacity	→	CO ₂ Purity CO ₂ Desorption Energy
3. Stability	→	SMA Lifetime
4. Water Co-Adsorption	→	CO ₂ Desorption Energy
5. Pressure Drop	→	Adsorption Energy



SMA Manufacturing: Adsorption Enhancement

Laboratory SMA Testing




Increased CO₂ capacity of SMA by over 4x via SMA Optimization


- **Sorbent**
Tuned promoter and alkali carbonate ratio
- **Support**
Doubled surface area and pore volume for greater sorbent active site accessibility to CO₂ in air
- **Substrate**
Enhanced surface area resulting in 80% increase in washcoat loading

SMA Manufacturing: Adsorption Enhancement

Adsorption Working Capacity




Cycle 14 Adsorption Profile




Exceeded target adsorption rate by **125%**
Increased volumetric productivity = lower CAPEX

SMA Manufacturing: Desorption Performance




Cumulative CO₂ Desorption Profile




Target desorption rates achieved using direct Joule Heating



Integrated DAC Bench System: Process Sequence



Integrated DAC Bench System: Process Flow Diagram



Integrated DAC Bench System: SubModule Design





1. Minimizing dead volume **increases CO₂ purity**.
2. Increased CO₂ purity **reduces CAPEX and OPEX** in OSBL downstream CO₂ purification.
3. Inherently thermally and electrically insulating material **reduces parasitic energy loss and electrical safety risk**.

Integrated DAC Bench System: SubModule Design




CO₂ Desorption

C: 0.2bar
Total Deformation 3
Type: Total Deformation
Unit: mm
Time: 2 s



Air Evacuation,
CO₂ Recovery


D: -0.9bar
Total Deformation
Type: Total Deformation
Unit: mm
Time: 2 s




1. Minimizing dead volume **increases CO₂ purity**.
2. Increased CO₂ purity **reduces CAPEX and OPEX** in OSBL downstream CO₂ purification.
3. Inherently thermally and electrically insulating material **reduces parasitic energy loss and electrical safety risk**.

Aluminum Honeycomb Gas Sealing Panel
(3"/7.62mm core thickness, 0.003"/0.0762mm skin thickness)

Integrated DAC Bench System: SubModule Electrical Circuit



Integrated DAC Bench System: Module Assembly and Status



Deliverable Status

- PFD, P&IDs, H&MB, and Conceptual Mechanical Design Complete
- Fabricators identified and preliminary testing ongoing
- Vendors for components identified
- RFQs released and procurement ongoing

Key Milestone

- Module Fabrication and Testing (**Q4 2024**)


Community Benefits / Societal Considerations and Impacts

- Engaged external DEIA practitioner
- Drafted a DEIA Statement
- Initiated implicit bias training for employees
- Developed repository of Minority Business Enterprises, Minority Owned Businesses, Woman Owned Businesses and Veteran Owned Businesses to solicit services, materials, equipment bids.
- Seminar and internship programs in development with Department of Chemistry in the College of Science and Technology (COST), at North Carolina Agricultural and Technical State University (NC A&T) for Fall 2024

Lessons Learned

- SMA performance is the key driver for CO₂ production cost.
- Water in air (sensible and latent heat of vaporization) is the greatest contributor to DAC's energy intensity.
- Perform technology risk assessment early and structure prototyping and development around the risk mitigation.
- Modular design for technology, project, and financial risk mitigation.
- Solicit customer, supplier, and fabricator feedback early and often.
- Partner early with the first technology adapter and incorporate the feedback from this partner into design and operation of the bench/pilot units.

Ongoing Development: Technology Roadmap



Thank You!

Raghubir Gupta
rg@susteon.com
President and CEO


Jian-Ping Shen
jps@susteon.com
Principal Scientist

Andrew Tong
at@susteoninc.com
R&D Manager

Richard Wood
rw@susteoninc.com
Lab Technician

Arnold Toppo
act@susteoninc.com
Process Design Engineer

Appendix: Organizational Chart



Project Schedule

Project Timeline			Months from Project Start Date																																				
			BP1																		BP2																		
Task	Start Date	End Date	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	
Task 1.0 - Project Management and Planning																																							
Subtask 1.1 - Project Management Plan	1-Jul-23	30-Jun-26																																					
Subtask 1.2 - Technology Maturation Plan	1-Jul-23	31-Mar-26																																					
Subtask 1.3 - State Point Data Table (SPDT)	1-Jan-26	31-Mar-26																																					
Milestone 1.1: Initial TMP within 90 days of project start		30-Sep-23			+																																		
Milestone 1.2: Final TMP within 90 days prior to project completion		31-Mar-26																																				+	
Milestone 1.3: Final state point data table due 90 days prior to project completion		31-Mar-26																																				+	
Task 2.0 - Detailed Design of Integrated DAC Prototype System																																							
Subtask 2.1 - Develop Functional Design Specifications	1-Jul-23	31-Aug-23																																					
Subtask 2.2 - Complete Piping and Instrumentation Diagram (P&ID), Control Specifications	1-Aug-23	31-Oct-23																																					
Subtask 2.3 - SMA Reactor Module Design	1-Sep-23	31-Dec-23																																					
Subtask 2.4 - PHA, Instrument List, and Equipment and Fabricator Selection	1-Jan-24	31-Mar-24																																					
Subtask 2.5 - Balance of Plant Design	1-Feb-24	31-Mar-24																																					
Milestone 2: DAC prototype rig design complete and ready for fabrication		31-Mar-24									+																												
Task 3.0 - Structured Sorbent Synthesis for Bench Unit																																							
Subtask 3.1 - Procurement of equipment and coating components	1-Sep-23	31-Mar-24																																					
Subtask 3.2 - Monolith Substrate and Coating Material Procurement	1-Jan-24	31-Mar-24																																					
Subtask 3.3 - SMA Synthesis and Characterization	1-Mar-24	30-Jun-24																																					
Subtask 3.4 - Sorbent Synthesis for Integrated Bench Prototype Testing	1-Jul-24	31-Dec-24																																					
Milestone 3: SMA synthesis equipment installed and protocol is verified. CO2 adsorption and desorption on synthesized samples >3.0 wt% (eCO2/gSorbent)		30-Jun-24												+																									
Task 4. Integrated Bench Unit Construction, Installation and Commissioning																																							
Subtask 4.1 - Completion of Vendor Design Drawings and Initiate Component/Equipment Procurement	1-Mar-24	30-Jun-24																																					
Subtask 4.2 - Integrated Bench Unit Construction and Installation	1-Jul-24	30-Sep-24																																					
Subtask 4.3 - Bench Unit Commissioning and PSSR	1-Sep-24	31-Dec-24																																					
Milestone 4: DAC prototype rig setup and ready to operate		31-Dec-24																																				+	
Go/No-Go Decision Point 1 to Enter BP2	31-Dec-24																																					⊕	
Task 5. Parametric and Accelerated Long Term of Integrated Bench Prototype Test Rig																																							
Subtask 5.1 - Parametric Testing with Integrated Prototype Test Rig	1-Jan-25	30-Jun-25																																					
Subtask 5.2 - Accelerated Long Term of Integrated Bench Prototype Test Rig	1-Jul-25	30-Mar-26																																					
Milestone 5.1: Projected adsorption and desorption rates achieved (Adsorption: >0.01 mol CO2/kg sorbent/min; Desorption: >0.01 mol CO2/kg sorbent/min)		30-Jun-25																																				+	
Milestone 5.2: Sustained CO2 Loading, CO2 purity, and adsorption/desorption rate achieved over 1000 adsorption/desorption cycles		30-Mar-26																																				+	
Task 6. Techno-Economic Analysis & Life-Cycle Assessment																																							
Subtask 6.1 - Process Model Update	1-Apr-25	31-Dec-25																																					
Subtask 6.2 - Techno-Economic Analysis	1-Apr-25	30-Jun-26																																					
Subtask 6.3 - Life Cycle Analysis	1-Jul-25	31-Mar-26																																					
Milestone 6.1: Initial TEA and LCA report due 120 after project start		31-Oct-23																																					
Milestone 6.2: Final TEA and LCA report due 90 prior to project completion		31-Mar-26																																					
Task 7. Technology Environmental Health and Safety (EH&S) Risk Assessment																																							
Milestone 7: Final EH&S analysis due 90 prior to project completion		31-Mar-26																																				+	
Task 8. Technology Gap Analysis (TGA)																																							
Milestone 8: Final TGA within 90 days prior to project completion		31-Mar-26																																				+	