



# NuDACCS – Nuclear Direct Air Capture with Carbon Storage

DE-FE0032160

**Brandon Webster**  
**Battelle Memorial Institute**

U.S. Department of Energy  
National Energy Technology Laboratory  
Carbon Management Research Project Review Meeting  
August 5 – August 9, 2024

**BATTELLE**



Aircapture

 Southern Company

THE UNIVERSITY OF  
**ALABAMA**

Sargent & Lundy



# Disclaimer

## U.S. Department of Energy Disclaimer

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendations, or favoring by the United States Government or any agency thereof. The views and the opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

## Battelle Disclaimer

Battelle does not engage in research for advertising, sales promotion, or endorsement of our clients' interests including raising investment capital or recommending investments decisions, or other publicity purposes, or for any use in litigation. Battelle endeavors at all times to produce work of the highest quality, consistent with our contract commitments. However, because of the research and/or experimental nature of this work the client undertakes the sole responsibility for the consequence of any use or misuse of, or inability to use, any information, apparatus, process or result obtained from Battelle, and Battelle, its employees, officers, or Trustees have no legal liability for the accuracy, adequacy, or efficacy thereof.

# Agenda

- Overview
- Technology Background
- FEED
- Business Case Analysis
- Lifecycle Analysis
- Workforce Readiness
- Environmental Justice
- Key Findings

# Project Overview

Period of Performance:  
October 2022 – September 2024

## Project Funding:

Federal Share: \$2,499,178

Non-Federal Share: \$864,446


Total: \$3,363,624

Project Team  
Members:

**BATTELLE**



Aircapture

 Southern Company

THE UNIVERSITY OF  
**ALABAMA**

Sargent & Lundy



## Project Goal:

The project will define system costs, performance, socio-economic impacts, and business-case options for leveraging available thermal energy from the nuclear plant to separate CO<sub>2</sub> from ambient air for off-site geologic storage.

# Project

Purpose: Conduct a Front-End Engineering and Design (FEED) and associated supplemental studies to determine the technical, economic, and socio-economic viability of utilizing nuclear heat/power source for deploying a direct air capture (DAC) installation capturing a minimum **5,000 net tpa**

## Task List


- Task 1.0 PM
- Task 2.0 FEED
  - DAC
  - Balance of Plant (BOP)
- Task 3.0 Project Economics and Business Case
- Task 4.0 Lifecycle Analysis and EH&S
- Task 5.0 Socio-Economic Impact
  - Environmental Justice
  - Economic Revitalization and Jobs Outcomes Analysis
  - Workforce readiness

## Deliverables


Task/subtask	Deliverable Title	Planned completion (month after award)	Verification method	Delivered?
1.6	Project Kickoff Meeting	3	Meeting Notes	Y
1.1	Updated PMPlan Complete	1	PMP submitted to DOE	Y
1.4	Updated DMPlan Complete	1	DMP submitted to DOE	Y
2.2.1	Process Design and Initial HAZOP Complete	9	Memo to DOE	Y
2.2	FEED Study Complete	17	Memo to DOE	Y
3.2	Cost Estimate BCA Complete	17	Memo to DOE	Y
4.1, 4.2	LCA and EH&S Risk Complete	17	Memo to DOE	Y
1.3	Workforce Readiness Plan Report Complete	12 initial, 17 final	Memo to DOE	Y
5.1, 5.2	Environmental Justice and Economic Revitalization Analyses	10 mid-project, 17 final	Briefing to DOE and project Stakeholders	Y
1.7	Final Report	18	Memo to DOE and project Stakeholders	(Target August)
1.2	TMP Complete	3 initial, 17 final	Memo to DOE	Y




# Overall Concept



# Project Location




- Preliminary tie-ins and equipment locations determined
- Site visit refined the initial design



# Technology Background

**Step 1 (Capture):** CO<sub>2</sub> is collected by moving air or mixtures of air and CO<sub>2</sub> rich gases across a proprietary contactor which adsorbs CO<sub>2</sub>.

**Step 2 (Regeneration):** The contactor is moved into a regeneration box where low-temperature steam flows across the contactor, removing CO<sub>2</sub> from the contactor, and the CO<sub>2</sub> is collected.



Goal: Use commercially available contactors and sorbents in an efficient system design to decrease the cost of DAC.

## Polymeric Amine Sorbent

### Monolithic Contactor

- Low pressure drop
- Low thermal mass
- High geometric surface area
- Compatible with various construction methods



### Adsorption

- 900 seconds / monolith in ambient air

### Desorption

- Saturated Steam in less than 90 seconds



# Aircapture Scale-Up/Testing

TRL 7+ achieved for DAC technology by Q4 2024



SN1: NCCC, Wilsonville, AL  
March 2023 to July 2024  
5 Campaigns, +140 days of operations,  
>92% uptime (DE-FE0031961)




SN3: Aircapture Berkeley, CA April 2024  
>50% CAPEX Reduction  
>20% OPEX Reduction



Project Hajar, 8 SN3 DACs + Supporting Skids June 2024  
Proving out DAC Grove concept first designed in  
DE-FE0032160 & DE-FE0032157

# FEED Study

- FEED study was completed
- Including process, BOP, constructability review, HAZOP, and other analyses
- Cost estimate created using Air Capture and S&L inputs
- Submitted on June 28<sup>th</sup>, 2024 currently under review by DOE




**Joseph M. Farley Nuclear Power Plant  
Units 1 and 2**

**Nuclear Direct Air Capture with  
Carbon Storage (NuDACCS)**


**NuDACCS FEED Study Summary  
Report**

Award/Agreement No. DE-FE0032160



Rev. 0 | June 10, 2024  
Project No. A14881.001

55 East Monroe Street  
Chicago, IL 60603-5780 USA  
312-269-2000  
www.sargentlundy.com




Battelle  
NuDACCS FEED Study  
Summary Report

Page ii  
Rev. 0 | June 10, 2024

**CONTENTS**

1. INTRODUCTION.....	1-1
2. FACILITY DESIGN DEVELOPMENT.....	2-1
2.1. AIRCAPTURE DAC TECHNOLOGY DESIGN .....	2-1
2.1.1. DAC Process Overview .....	2-1
2.1.2. DAC Technology Process Description .....	2-1
2.1.3. DAC Technology Package .....	2-2
2.2. BALANCE OF PLANT DESIGN .....	2-3
2.2.1. Steam Generation System: Included in .....	2-3
2.2.2. Cooling Water and Condensate System .....	2-3
2.2.3. Hydrogen System .....	2-3
2.2.4. Instrument Air System .....	2-4
2.2.5. Carbon Dioxide Transfer System .....	2-4
2.3. DESIGN INPUTS .....	2-4
2.3.1. Site Location and Conditions .....	2-4
2.3.2. DAC Facility CO <sub>2</sub> Capture Design Basis .....	2-5
2.3.3. DAC Facility CO <sub>2</sub> Product Quality .....	2-5
2.4. GENERAL ENGINEERING .....	2-6
2.4.1. Overall Process Flow Diagram .....	2-6
2.4.2. Project Design Criteria .....	2-7
2.4.3. Budgetary Quote Solicitation Support .....	2-7
2.4.4. Site Plan and General Arrangement Drawing .....	2-7
2.4.5. Process Hazard Analysis .....	2-8
2.5. ENVIRONMENTAL PERMITTING .....	2-8
2.5.1. Air Emissions .....	2-9
2.5.2. Wastewater Discharge .....	2-9
2.5.3. Waste Disposal .....	2-9
2.5.4. Preliminary Licensing Review .....	2-9
2.6. MECHANICAL ENGINEERING .....	2-11
2.7. ELECTRICAL ENGINEERING .....	2-11
2.8. INSTRUMENTATION AND CONTROLS ENGINEERING .....	2-12
2.9. STRUCTURAL AND CIVIL ENGINEERING .....	2-12
2.10. NUCLEAR ENGINEERING .....	2-14

These protected data were produced under agreement no. DE-FE0032160 with the U.S. Department of Energy and may not be published, disseminated, or discussed to others outside the Government until 5 years after the date the data were first produced, unless express written authorization is obtained from the recipient. Upon expiration of the period of protection set forth in this notice, the Government shall have unlimited rights in this data. This notice shall be marked on any reproduction of this data, in whole or in part.



Battelle NuDACCS FEED Report\_Rev. 0\_WORKING.docx




# BOP/Plant Farley Interfaces

Battelle  
Farley Nuclear Plant  
NuDACCS FEED Study  
Aircapture Process Flow Diagram



Project No.: 14881.001  
Rev. 0  
Date: April 30, 2024




**Stream Legend:**

- Steam
- Inner Cooling Water Loop
- Chilled Water Loop
- Process Condensate
- Hydrogen
- CO<sub>2</sub> Product
- Ambient Air and CO<sub>2</sub> Lean Air

REV.	DATE	PREPARER	REVIEWER	APPROVER	PURPOSE
A	08/16/2023	V. Patel	H. Hills	K. Pemberton	For Comment
0	04/30/2024	M. Porcelli	V. Patel	K. Pemberton	For Comment

# Aircapture Concept DAC Layout CFD – Initial Conditions

- Translated GA to 3D model – Focused on DAC island, utilities, transport, and conditioning/compression infrastructure



Preliminary DAC Layout Concept





NUDACCS Feed Study






Trench Installation



Sleeper Installation





U/G Piping and Electrical





Unfired Boiler Installation



A/G Piping and Electrical



Foundations and DAC Equipment





BOP Equipment





# Business Case Analysis

- BCA
  - Project would need to take advantage of 45Q and voluntary credit market
  - Two factors drove economics:
    - Small DAC island size (driven by heat-source capacity) the DAC capacity nearly doubles by tying into both reactor units
    - Tie-ins in protected zone led to higher costs
  - Submitted to the DOE on July 16<sup>th</sup>, 2024

The University of Alabama  
Nuclear Direct Air Capture with Carbon Sequestration  
Business Case Analysis and  
Review of Front-End Engineering Design Study



The University of Alabama

DIRECT AIR CAPTURE  
COMBINED WITH DEDICATED LONG-TERM CARBON STORAGE,  
COUPLED TO EXISTING LOW-CARBON ENERGY

1

# Lifecycle Analysis

- LCA model is set up in openLCA following NETL guidelines and ISO 14040/14044 standards
- Net carbon removal efficiency of 92.6%
- Electricity production and H2 production (SMR) lead gray emissions
- Global warming potential roughly doubles if not utilizing waste heat from Plant Farley for Steam Generation
- This assumes power required for steam is generated from a Nuclear Source (NETL Database)




Figure 2. LCA system boundaries





Figure 4. Contributions to GWP by process





# Workforce Readiness


- Jobs created by the NuDACCS project will require short-term construction jobs and longer-term operations jobs.
- The team reached out to the nearby technical colleges, universities, and HBCUs. As part of this outreach each institution was asked about several topics.

**Table 1. Formal Training requirements for jobs required to execute a DAC project.**

Jobs	Union?	Experience	Education Needed	Training Institutions
Engineers	No	Entry Level to Senior Level	BS or higher	Universities, HBCUs
Welders and Joiners	Yes	Apprenticeship	Certification or 2-year degree	Tech & Community Colleges, Vocational Schools, Unions
Electricians	Yes	Apprenticeship	Certification or 2-year degree	Tech & Community Colleges, Vocational Schools, Unions
Cement Masons	Yes	Apprenticeship	Certification or 2-year degree	Tech & Community Colleges, Vocational Schools, Unions
Machinists	Yes	Apprenticeship	Certification or 2-year degree	Tech & Community Colleges, Vocational Schools, Unions
Fabricators	Yes	Apprenticeship	Certification or 2-year degree	Tech & Community Colleges, Vocational Schools, Unions
Construction laborers	Yes	Minimal	High School or equivalent	NA
Construction supervisors	Yes	On-the-job training	Certification or 2-year degree + OSHA training	Tech & Community Colleges, Vocational Schools, Unions
Manufacturing and Maintenance	Yes	Apprenticeship	Certification or 2-year degree	Tech & Community Colleges, Vocational Schools, Unions

# Environmental Justice

- Overarching goal is to have benefits flow to disadvantaged communities and negative impacts avoided
- Disadvantaged communities have been identified using DOE and White House Council on Environmental Quality tools.
- Minority Serving Institutions (MSIs) and technical and community colleges can help train workers.
- Reports submitted to the DOE on July 12<sup>th</sup>, 2024



# Key Findings

1. Optimizing available resources, such as heat sources, land, and cooling systems, is crucial for maximizing DAC capacity.
2. Developing infrastructure and equipment outside restricted site areas is important to minimize the impact on Farley operations and reduce project schedule risks.
3. Integrating with an operating nuclear power plant is complex but offers access to low-carbon power, heat, and cooling water.
4. Smaller installations can be supported by investments in common transport and injection infrastructure.
5. Such smaller installations may need to rely on barge, rail, or truck transport unless connected to a pipeline network.



# Thank You!

- DOE NETL Project Manager – Zachary Roberts
- Aircapture
- Sargent and Lundy
- Southern Company
- University of Alabama
- Carbonvert

***BATTELLE***

**It can be done**