

UCLA SeaChange: Carbon Sequestration Pilot

DE-FE0032321

Gaurav Sant

2024 FECM/NETL Carbon Management Research Project Review Meeting

August 5 – 9, 2024


Project Overview

- Funding
 - DOE: \$1,600,000
 - Cost-share: \$450,000
- Overall Project Performance Dates
 - Project start: Q1 2024
 - Project completion: Q2 2025

Project Objectives

- Design, build, and commission an electrolyzer unit that will achieve 1 tonne/day (TPD) of carbon removal by way of seawater electrolysis with hydrogen generation
 - Limited energy usage of 2.5 MWh/t of gross energy intensity
- Establish a U.S. based manufacturing line for seawater electrolyzers that will achieve a net levelized cost of <\$100/tonne

There is an ongoing (dynamic) exchange of CO₂ between the atmosphere and oceans – and the oceans are the largest reservoir of carbon dioxide



The carbon dioxide concentration in seawater is 150x higher than in air

Global equilibrium: CO₂ that is removed from the atmosphere is permanently stabilized in the world's oceans by alkalinity compensation – *implications for "DAC"*

Technology Background

Stage 1: Seawater Electrolysis




Renewable electricity is used to split seawater into two streams, hydrogen and oxygen

Stage 2: Direct Air Capture



Carbon dioxide is converted into dissolved inorganic carbon and calcium carbonate


Stage 3: Permanent Storage




Carbon can then be stored in ocean and on-land for 10,000-1,000,000,000 years

How it works:

- Flow-through seawater electrolysis
H₂ production coupled to CDR



Technology Background




~2.3 MWh per tonne of CO_2 removal is the lowest demand for atmospheric CDR

- Sources: LaPlante et al, ACS Sust Chem Eng (2021) 9:3:1073-1089 ; LaPlante et al, ACS EST Eng (2023)


Not just CDR: Green hydrogen from seawater

Ocean CDR technology



A H₂ production process with net CO₂ capture

PEM/alkaline H₂ electrolysis



CO₂ emissions strongly depend on source of electricity

Blue/brown H₂



CO₂ emissions directly linked to the process

Two 100 kg CDR per day pilots online since March 2023 in Port of Los Angeles and Singapore




Technical Approach/Project Scope

- We are developing an electrolyzer to achieve our performance criteria by iterating new designs in a pilot test rig
- Key is to minimize energy usage while maximizing operational stability

Milestone Title & Description	Planned Completion Date
Milestone A – Kickoff meeting with DOE	Q1 2024
Milestone B – Finalized electrolyzer design. An electrolyzer design engineered to achieve the target GEI of ≤ 2.5 MWh/t _{CO2} .	Q3 2024
Milestone C – FEL-3 engineering. To provide an engineering package including a project execution plan, electrolyzer component manufacturing plan, electrolyzer assembly and commissioning procedure, general arrangement layout and 3D model, Equipment specifications (for OTS equipment), Preliminary line list (piping and electrical), Detailed P&ID and Material Selection Diagram (MSD), Detailed control description, including commissioning, startup, and maintenance assumptions.	Q4 2024
Milestone D – Electrolyzer commissioning and operation. Design, fabricate, and commission a 100 kW electrolyzer system including the balance of plant.	Q2 2025


Progress and Current Status of Project: Energy Contribution

- Measured the contribution of various components to the generalized cell design's energy performance
 - Electrolyte, membrane, and electrodes provide roughly equal voltage increments above the thermodynamic limit




Progress and Current Status of Project: Flow Modeling

- Modeled stack flow behavior given blocked cells to understand flow dynamics in case of individual cell fouling in large stack
- Results show that low cell blockage % is acceptable and does not meaningfully impact hydrodynamic performance, whereas high blockage ($> \sim 25\%$) has exponential and cascading effects on flow distribution




Progress and Current Status of Project: Electrolyzer Testing

- Demonstrated multiple extended runs (over 6 hours) of stable operation, with a “voltage creep” ranging between 10-40 mV/h
- Acid flush of single-cell system has shown complete recovery of initial voltage, indicating ability to cyclically run cell multiple times
- Primary challenge is to continue to lower initial voltage and manage solids removal from cell




Progress and Current Status of Project: Carbonation

- Designing and sizing demonstration-scale carbonator based on lab experiments
- Pilot study at the Los Angeles site under development



Progress and Current Status of Project: Manufacturing

- Building up manufacturing lines, including for proprietary coating processes for oxygen-selective anodes
- Partner's facility in San Diego, CA



Plans for future testing/development/commercialization

**~4,000 TPA CDR/Green H₂ Plant plant:
2025 phased installation in Singapore**



Plans for future testing/development/commercialization

**~100,000 TPA CDR/Green H₂ Plant in
Canada: Project Engineering underway**



Summary

- Key findings to date
 - Voltage in cell rises over time due to solids and gas blinding
 - Voltage can be recovered through acid flush of cell
- Future plans
 - Continue to decrease initial cell voltage
 - Optimize cell geometry for voltage stability
- Unique oxygen selective anodes are key enabler of the technology
- Seawater-based CDR technology is engineered with MRV at the forefront