


Pittsburgh, Pennsylvania  
FECM/NETL Carbon Management  
International Carbon Management  
Heidelberg Materials' Projects

Gregory Ronczka  
Vice President, Environment & Sustainability  
Heidelberg Materials North America  
August 6, 2024





# Driving CCUS with the most advanced project portfolio in the sector



- |  |  |
|--|--|
|  <b>1   CCS 2024</b><br>Brevik , Norway<br>400 kt CO <sub>2</sub> p.a.          |  <b>8   CCS 2028</b><br>Padeswood , UK<br>800 kt CO <sub>2</sub> p.a.         |
|  <b>2   CC 2024*</b><br>Devnya , Bulgaria<br>OxyCal pilot site                  |  <b>9   CCUS 2028*</b><br>Devnya , Bulgaria<br>800 kt CO <sub>2</sub> p.a.    |
|  <b>3   CC 2025</b><br>Mergelstetten , Germany<br>Oxyfuel pilot                 |  <b>10   CCUS 2029</b><br>Antoing , Belgium<br>800 kt CO <sub>2</sub> p.a.    |
|  <b>4   CCU 2025</b><br>Lengfurt , Germany<br>70 kt CO <sub>2</sub> p.a.        |  <b>11   CCS 2029*</b><br>Geseko , Germany<br>700 kt CO <sub>2</sub> p.a.     |
|  <b>5   CC 2026</b><br>Ennigerloh, Germany<br>LEILAC1+2, 100 kt CO <sub>2</sub> |  <b>12   CCS 2030</b><br>Slite, Sweden<br>1,800 kt CO <sub>2</sub> p.a.       |
|  <b>6   CCU 2026</b><br>Safi, Morocco<br>Upscaling capacity                     |  <b>13   CCUS 2030</b><br>Mitchell, USA<br>2,000 kt CO <sub>2</sub> p.a.      |
|  <b>7   CCUS 2027</b><br>Edmonton, Canada<br>> 1,000 kt CO <sub>2</sub> p.a.  |  <b>14   CCS 2030</b><br>Airvault , France<br>1,000 kt CO <sub>2</sub> p.a. |


\*EU funded projects

All dates estimated start of operations, timing dependent on various factors, incl. funding decision




# Overview of the project

## The world's first in the cement industry



**400,000 tonnes**  
of CO<sub>2</sub> per year



**55 tonnes**  
of CO<sub>2</sub> per hour



Capturing **50% of the plant's CO<sub>2</sub> emissions** – limited by available waste heat



**46 MW** waste heat recovery – ca **30 MW** from cement kiln, **16 MW** from CO<sub>2</sub> compressor



# The Longship Project

01 | Carbon capture from industrial sources incl. Brevik cement plant


02 | Transport to Øygarden

03 | Pipeline to storage in North Sea

Supported by state funding for installation and 10 years operation



- Transport by 2 ships
- 700 km distance
- Liquefied state (16 bar, -26°C)



## Temporary storage and ship loading



**Storage capacity:** 5,000 m<sup>3</sup>

6 storage tanks with a total capacity of 5,000 m<sup>3</sup> –  
enough to store the CO<sub>2</sub> from 4 days of production

**Preparing the CO<sub>2</sub> for transport**

CO<sub>2</sub> is compressed to 16 bar pressure and cooled to  
-26° C – liquid state, suitable for transport and interim storage.  
Insulated tanks. No active cooling





# People & project

More than **900,000 working hours**, very good performance on health & safety records

**15 “Carbon Catchers”** (operators + process engineers) have been hired, are being trained on a simulator and will be involved in commissioning

In total, plant will have **195 full -time employees** once the CCS facility is operational, of which 29 will be working for the CCS project



## Lessons Learned

- ❑ A clear recommendation for future CCS projects is to have **sufficient piping expertise** on the project team in areas like:
  - pipe suppliers and pipe supply markets
  - prefabrication methods and companies
  - logistics tracking of pipe components
  - productivity assessments in pipe fabrication and installation
- ❑ Include an **Operating Training Simulator** as part of the project to prepare dedicated process operators for the CCS plant for commissioning, startup and operation. The simulator also helped optimize and tune the PLC logic, controllers and timers for a smoother startup.
- ❑ Risks can be reduced by separating the CCS facility as much as possible from the operating plant. Challenges of having the CCS system closely integrated with the cement plant:
  - Civil engineering difficulties working with existing structures
  - Communicating and documenting interfaces to the existing plant - is this owner or supplier responsibility?
  - Limited room for construction activities adding pressure to the schedule
- ❑ Pipelines for liquid CO<sub>2</sub> need to be designed to be drained
- ❑ Identify safe locations of CO<sub>2</sub> venting (operational as well as emergency)
- ❑ Plate and frame heat exchangers to have flow control between units and able to be isolated for maintenance





Mounting the CCS plant: 4 heavy


-lift campaigns in 2023 and 2024



## The challenge

Several components weighing **200 tonnes** or more had to be lifted into place...

... and assembled with **millimeter precision.**





## Other Challenges

- ❑ The **offshore oil & gas (high cost/no -risk)** versus **cement (low cost/practical) cultural misunderstandings** have proven significant and challenging to overcome. It takes years to build a common understanding with suppliers even in the cement industry.
- ❑ **Reporting requirements for publicly funded projects** are much higher than for conventional projects within Heidelberg Materials. The project must be sufficiently staffed for these demands.
- ❑ Postponement of construction of maintenance building due to **space limitations**.
- ❑ The CO<sub>2</sub> loading point was **relocated twice** due to changes in base assumptions / space for docking.
- ❑ **Cost increase** to the forecasted budget and **project delays** of around 10 months.
  - The **scaffolding** for the support of construction works in the project has been far more than budgeted.
- ❑ Use of EN 13480 versus ASME B31 piping systems; availability of EN-piping has proven challenging
- ❑ Necessity of heat-tracing and insulating plant air (compressed air)
- ❑ Painting, equipment preservation (protection during installation)
- ❑ On-site installation of **insulation of liquid CO<sub>2</sub>** storage tanks required careful climate control during the installation process and is challenging to do in the winter due to risk of condensation on the tank surface.



# Thank You.

Gregory Ronczka, MPH, P. G.

Vice President, Environmental & Sustainability

Heidelberg Materials North America

[Gregory.Ronczka@heidelbergmaterials.com](mailto:Gregory.Ronczka@heidelbergmaterials.com)

