



# ENGINEERING-SCALE DEMONSTRATION OF THE MIXED-SALT PROCESS (MSP) FOR CO<sub>2</sub> CAPTURE

2024 FECM/NETL Carbon Management Research  
Project Review Meeting

PI: Indira Jayaweera, SRI

Presented by Elisabeth Perea, SRI

August 7, 2024 2:00-2:15 PM



DOE Contract # FE0031588



## **Disclaimer:**

This presentation includes an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

# Project Overview

**SRI:** Overall project management, procurement, skid testing and operation, data collection and decommissioning of the skid.


**NCCC:** Host-site; provides flue gas, utilities, and skid installation.

**Trimeric Corporation:** Preparation of the Process Design Package (PDP) for the pilot, support the modular fabrication effort and Techno-Economic Analysis (TEA).

**OLI Systems:** Optimization of the process flowsheet for the 0.5 MW<sub>e</sub> pilot, and modeling of 550 MW<sub>e</sub> (NETL Case B12B) for the power plant integration.

**EPIC Systems:** Modular MSP system fabricator; procurement, construction, and delivery of the modular system.

**Baker Hughes:** Cost-sharing industry partner



## Project Period (BP1 to BP5):

07/01/2018 - 12/31/2025

Total: \$21,949,080

## NCCC Project (BP4 and BP5):

03/1/2022 - 12/31/2025

## Project Cost:


Govt. Share: \$13,418,080

Cost Share: \$3,710,643

Total: \$17,128,723



# Current MSP Project Objectives



- Test at engineering scale (0.5 MW<sub>e</sub> equivalent)
- Demonstrate the MSP can capture CO<sub>2</sub> at 90%
- Regenerate CO<sub>2</sub> with 95% purity
- Long-term testing periods under dynamic and steady state conditions with a real flue gas stream
- Address concerns related to scale-up and integration of the technology to coal-based power plants
- Determine the pathway to reaching DOE targets for CO<sub>2</sub> capture costs

# Mixed-Salt Process (MSP) Technology Background



## Process Summary

- Uses inexpensive, industrially available material (potassium and ammonium salts)
- No solvent degradation
- Has the potential for easy permitting in many localities
- Uses known process engineering
- Accelerated development possible








## Demonstrated Benefits (by testing and modeling)

- Enhanced CO<sub>2</sub> capture efficiency
- High CO<sub>2</sub>-loading capacity
- High-pressure release of CO<sub>2</sub> (10-12 bar)
- Reduced energy consumption (~ 2.3 MJ/kg-CO<sub>2</sub> for coal-based applications)

## Expected Additional Benefits

- Capture from low-concentration CO<sub>2</sub> sources
- > 95% capture possible
- Removes common acid pollutants and particulates

## K<sub>2</sub>CO<sub>3</sub>-NH<sub>3</sub>-CO<sub>2</sub>-H<sub>2</sub>O system



Simplified Process Flow Diagram

# Advanced Ammonia Technology Background



Ammonia technology developed at SRI in 2004

MSP technology development started at SRI in 2012

SRI, Menlo Park



Bench-scale Absorber

2012-2014



Regenerator

IHI Research Center,  
Yokohama, Japan (IHI)



Large Bench-scale

2016

SRI, Menlo Park




Large Bench-scale

2015-2017

DOE Contract: DE FE0012959

MSP Engineering Pilot  
NCCC



2018 - 2025

DOE Contract: DE-FE0031588

## SRI has patent coverage for the MSP in the US, Japan, and Europe

SRI has entered into a global exclusive licensing agreement with Baker Hughes for MSP use for post-combustion CO<sub>2</sub> capture in 2021 (<https://netl.doe.gov/node/10671>), and this partnership will pave the pathway for early entry of the technology into the market.

# BP4 and BP5 Work Update and Schedule



<i>Activity</i>	<i>Start Date</i>	<i>End Date</i>	<i>Task #</i>
<b>BP4</b>			
Bid Request Period	February 24, 2023	April 7, 2023	Subtask 8.1
Bid Evaluations and Award	April 7, 2023	May 12, 2023	Subtask 8.1
Contract Execution	May 15, 2023	June 27, 2023	Subtask 8.2
Engineering & Procurement	June 28, 2023	August 9, 2024	Subtask 8.1-8.2
Skid(s) Fabrication	November 6, 2023	August 9, 2024	Subtask 8.3
Skid Prep & Delivery	August 19, 2024	September 4, 2024	Subtask 8.3
On-site Installation	September 4, 2024	October 31, 2024	Subtask 9.2
Shakedown & Pre-Commissioning	November 15, 2024	December 31, 2024	Subtask 9.3-9.4
<b>BP5</b>			
Commissioning	January 1, 2025	February 14, 2025	Task 11
Pilot testing	February 18, 2025	August 31, 2025	Task 12
Decommissioning	December 1, 2025	December 31, 2025	Task 13

In Progress


- SRI received DOE GO decision for the “Modular System” testing at NCCC site on May 22, 2024.
- SRI received the NCTE to extend BP4 from 7-31-2024 to 12-31-2024.

# Engineering Scale Pilot Design




## OSBL: From NCCC

Flue gas supply/return, process water, nitrogen, instrument air, electricity



## System Layout at NCCC Bay 2 (~10 TPD $\text{CO}_2$ Capture)





# Skid Progress

May 2024



Blower



Large bore SS piping



Large bore CS piping



Frames (4-skids)



Tanks



Various SS valves and piping

# Skid Progress

June 2024



Level 1



Levels 2- 3

Level 3

# Skid Progress

July 2024



Skids 1 and 4 (from the S-W corner)



Completed Skid 2



# Lessons Learned

- The details of connections between the site and process should be clearly defined at project onset to avoid having to fill gaps later
  - Flue gas, steam lines, auxiliary equipment
- Close collaboration between all parties (host site, EPC, technology developer) is essential to resolve issues quickly
- Leaving room initially for future changes/additions to the system design will minimize the impact of change orders
  - Extra electrical capacity to power add-on equipment
  - Extra I/O ports to accommodate added sensors

# Test Plan



Parameter to vary	Possible Range of Variation	Metric(s)
Flue gas flow rate	Flow rate through T101: 75-100% of design capacity	Overall CO <sub>2</sub> capture rate, Energy consumption
Regenerator (T-310) temperature	160° to 175°C	Overall CO <sub>2</sub> capture rate, CO <sub>2</sub> desorption, Steam flow rate, Energy consumption
Rich solvent flow from rich tank (TK-300) to regenerator (T-310)	Flow rate through P-300: 75-100% of design capacity	Overall CO <sub>2</sub> capture Rate, L/G Ratio, Energy consumption
Recycle flow rate in Absorbers 1 and Absorber 2 (T-210 and T-220)	Flow rate through P-210: 75-100% of design capacity	CO <sub>2</sub> capture rates in Absorber 1 and Absorber 2
	Flow rate through P-220: 75-100% of design capacity	
Regenerator steam flow rate	0-100% of design capacity	Overall CO <sub>2</sub> capture rate, CO <sub>2</sub> desorption, Energy consumption
NH <sub>3</sub> stripper (T-510) reboiler temperature	E-550 75-100% of full power	Ammonia stripping efficiency, Energy consumption
Water wash column (T-230) recycle rate	Flow rate through P-230: 75-100% of design capacity	Ammonia removal efficiency
CO <sub>2</sub> wash column (T-410) recycle rate	Flow rate through P-420: 75-100% of design capacity	CO <sub>2</sub> purity
H <sub>2</sub> SO <sub>4</sub> feed rate	1 to 1.5 lb/hr	ppmv contaminant removal from the clean flue gas

## Parametric testing:


- Test the sensitivities of key parameters on the performance.
- Performance is assessed by measuring the response variables for each run:
  - CO<sub>2</sub> Capture Efficiency (%)
  - Reboiler Duty (kJ/kg CO<sub>2</sub>)
  - Ammonia Emissions (ppm)

## Dynamic testing: Investigate the system's response and performance under transient and ramp operations

- Cold and warm starts
- Step changes in conditions such as flue gas composition and flow rate

	Range	Baseline
Inlet CO <sub>2</sub>	4 to 12.9%	12.9%
Capture Efficiency (%)	TBD	90%
L/G	1.4 to 2.5	1.88

# Technology Maturation Plan




- DOE funding is critical for getting the technology to market
- Technology licensee Baker Hughes (BH) is actively participating in finding opportunities for technology deployment
- Completion of the current project is crucial for demonstrating the technology's competitiveness and collecting data for designing a validation pilot

# Summary



- Expected delivery of skid to NCCC in 1 month
- Mixed Salt Skid operations will commence in Fall 2024 with full test plan to be carried out in 2025



Design  
becoming  
reality!



# Acknowledgements



- Krista Hill, Andrew Jones, Jose Figueroa, Dan Hancu, Lynn Brickett, and others at NETL
- NCCC team
- Epic Systems team
- Trimeric team
- OLI Systems team
- BH team
- SRI team led by Dr. Indira Jayaweera





# Thank you!

**Contact:**

**Dr. Indira Jayaweera**

[indira.jayaweera@sri.com](mailto:indira.jayaweera@sri.com)

1-650-859-4042