Pilot Testing of a Highly Efficient Pre-combustion Sorbent-based Carbon Capture System (Contract No. DE-FE-0013105)



Gökhan Alptekin, PhD Ambal Jayaraman, PhD Matt Cates Mike Bonnema David Gribble Jim Dippo

2019 DOE/NETL CO₂ Capture Technology Meeting

August 28, 2019

TDA Research Inc. • Wheat Ridge, CO 80033 • www.tda.com

Project Summary

- The objective is to develop a new sorbent-based pre-combustion capture technology for Integrated Gasification Combined Cycle (IGCC) power plants
- Demonstrate techno-economic viability of the new technology by:

1) Evaluating technical feasibility in 0.1 MW_e slipstream tests

2) Carrying out high fidelity process design and engineering analysis

- Major Project Tasks
 - ✓ Sorbent Manufacturing
 - ✓ Performance validation via long-term cycling tests
 - ✓ Reactor Design

✓ CFD Analysis and PSA cycle optimization/adsorption modeling

- ✓ Fabricate a Pilot-scale Prototype for Demonstration
- Evaluations at various sites using coal-derived synthesis gas
- Techno-economic analysis
 - High fidelity engineering analysis and process simulation



Project Partners



* 12 month no cost time extension is requested from DOE



TDA's Sorbent

- TDA's uses a mesoporous carbon with surface functional groups that remove CO₂ via strong physical adsorption
 - CO₂-surface interaction is strong enough to allow operation at elevated temperatures
 - Because CO₂ is not bonded via a covalent bond, energy input for regeneration is low
- Heat of CO₂ adsorption is 4.9 kcal/mol for TDA sorbent
 - Net energy loss in sorbent regeneration is similar to Selexol; much higher IGCC efficiency can be achieved due to high temperature CO₂ capture
- Favorable material properties
 - Pore size is tuned to 10 to 100 A
 - Mesopores eliminates diffusion limitations



US Patent 9,120,079, Dietz, Alptekin, Jayaraman "High Capacity Carbon Dioxide Sorbent", US 6,297,293; 6,737,445; 7,167,354 US Pat. Appl. 61790193, Alptekin, Jayaraman, Copeland "Precombustion CO_2 Capture System Using a Regenerable Sorbent"



Integration to the IGCC Power Plant



- Higher mass throughput to gas turbine higher efficiency
- Lower GT temperature Reduced need for HP N₂ dilution hence lower NO_X formation
- Elimination of heat exchangers needed for cooling and re-heating the gas
- Elimination of gray water treatment problem
- Potential for further efficiency improvements via integration with WGS



Operating Conditions

- CO₂ is recovered via combined pressure and concentration swing
 - CO₂ recovery at ~150 psia reduces energy need for CO₂ compression
 - Small steam purge ensures high product purity
- Isothermal operation eliminates heat/cool transitions
 - Rapid cycles reduces cycle time and increases sorbent utilization
- Similar PSA systems are used in commercial H₂ plants and air separation plants



Source: Honeywell/UOP



Technology Maturation Timeline



2008	2011	2013	2014	2017	2018	2019
Bench- scale tests	0.5-1 kW tests at NCCC	0.5-1 kW tests at Wabash River IGCC	Sorbent Scale-up IP secured	0.1 MW tests at NCCC	Integrated with WGS Tests with Praxair	0.1 MW Tests at Sinopec/ Yangtze Chem. Nanhua Plant

Primary Focus

- 0.1 MW_e evaluation in a world class IGCC plant to demonstrate full benefits of the technology
 - Testing with high pressure gas

Demonstrate full operation scheme

- 8 reactors and all accumulators
- Utilize product/inert gas purges
- \square H₂ recovery/CO₂ purity

Evaluations at various sites using coal-derived syngas

- Field Test #1 at NCCC Air blown gasification
- Field Test #2 at Sinopec Nanhua Petro-chemical Plant, Nanjing, Jiangsu Province, China – Oxygen blown gasification

Nanhua Plant Syngas Supply			
Composition	mol%		
H2	32.493		
СО	0.546		
CO2	24.715		
H2S	0.083		
COS	0		
C1	0.021		
N2	0.128		
AR	0.05		
NH3	0.069		
HCN	0		
HCL	0		
H2O	41.895		
温度 Temperature, C	265.6		
压力 Pressure, MPaG	4		



National Carbon Capture Center



Sinopec/Yangtzi Chemicals Petrochemical Complex



Slipstream Test Skid - Top View



Field Test Unit Installed at NCCC



- Fabrication is completed in 2016
- Installation with all the hook-ups were completed in March 2017
- Testing initiated in April 2017





Working Capacity of the Sorbent



- A successful 30 day (707 hrs) evaluation was completed at NCCC
 - Design flow at NCCC operating conditions was 1,420 SLPM (50 SCFM)
 - 97.3% capture @ 1,500 SLPM
 - 93% @ 1,800 SLPM
 - 90% @ 2,100 SLPM
- Pressure drop through the gas conditioning skid prevented flowing more than 2,100 SLPM of syngas through the PSA skids

Sorbent Performance



- Sorbent/PSA system maintained slightly higher CO₂ capacity than the earlier field tests at NCCC at ~60X scale
- At Sinopec we expect to achieve higher capacity than in the previous oxyfired gasification tests at Wabash River IGCC power plant
- Total Pressure 340 vs 500 psia
 - CO_2 Partial pressure <2X due to lower N₂ content and high syngas P



Sorbent Evaluations – Multiple Cycles



	Synthesis	Simulated	Steam	
	Gas	Gas	Purge	
Temperature	200°C	200°C	200°C	
Pressure	500 psig	200-500 psig	50-300 psig	
	Composition			
H_2	42.8%	53.4%	50.0%	
CO ₂	30.0%*	30.0%	-	
H ₂ O	26.6%	26.6%	50.0%+	
CO	0.6%	-	-	

 Long-term cycling of the scaled-up sorbent has been completed with stable performance over 60,000 cycles



* adjusted for purge with 100% steam at 150 psia

CFD Model Tuning



- Working with GTI, we developed a CFD model to support reactor design
- The model was tuned using the data from 1 kW and 0.1 MW systems evaluated at Wabash River IGCC Plant and NCCC field tests
- CFD simulations reached steady state in 6 cycles and the working capacity matched the data sets
- CFD model will be further tuned using data from Sinopec field datasets



Cycle Optimization





F. 10-step PSA cycle with CnBLO, purge, three PREQ & LPP

Applied Energy, Volume 254, 15 November 2019, 113624

 Cycle Schemes D, E and F that use pressure equalizations and co-current blowdown met DOE targets of 90% capture and 95% CO₂ purity



Minimization of Energy Penalty



Reactor Design

- Different reactor concepts have been evaluated
- Multiple train vertical reactors with internal flow distribution are selected for final design

	Vessels and Adsorbents	GE Gasifier	
		Syngas flow, kmol/h	34,747
A LA		Sorbent needed, kg	1,115,903
		L	1,859,838
		Cycle time, min	8
		Ads. GHSV, h ⁻¹	1,117
		Total Beds	16
		Bed. Volume, L	116,240
		Bed Dimensions	
上茶		Diameter, ft	14
		Length, ft	30.1
		Vessel wall thickness, in	5.0
		L/D	2.30
and the second s	Value Stat	Particle size, in	1/8
	Valve Skid	Bed Pressure drop, psid	3.6

TDA Design

Source: Honeywell/UOP

World-class PSA systems used in H₂ purification produces up to 400,000 m³/hr H₂ (compared to ~780,000 m³/hr flow rate used in TEA base case)



Full-scale System Design





Major Units

- 8 beds x 2 = 16
- 2 accumulator X 2 = 4
- Cycling Valves
 - $6 \times 8 \times 2 = 96$
- 2 recycle compressors
- 2 isolation vales x 2 per train = 4



Techno-economic Analysis

Gasifier	E-Gas		GE	
Case	1	2	3	4
	Cold Gas Cleanup	Warm Gas Cleanup	Cold Gas Cleanup	Warm Gas Cleanup
CO ₂ Capture Technology	Selexol [™]	TDA's CO ₂ Sorbent	Selexol [™]	TDA's CO ₂ Sorbent
CO ₂ Capture, %	90	90	90	90
Gross Power Generated, kW	710,789	670,056	727,633	674,331
Gas Turbine Power	464,000	425,605	464,000	417,554
Steam Turbine Power	246,789	244,450	257,657	246,746
Syngas Expander Power	-	-	5,977	10,031
Auxiliary Load, kW	194,473	124,138	192,546	120,661
Net Power, kW	516,316	545,917	535,087	553,671
Net Plant Efficiency, % HHV	31.0	34.1	32.0	34.5
Coal Feed Rate, kg/h	220,549	212,265	221,917	213,013
Raw Water Usage, GPM/MW	10.9	10.3	10.7	10.5
Total Plant Cost, \$/kW	3,464	3,102	3,359	3,212
COE without CO ₂ TS&M, \$/MWh	136.8	122.3	133.0	125.5
COE with CO ₂ TS&M, \$/MWh	145.7	130.4	141.6	133.4
Cost of CO ₂ Capture, \$/tonne	43	30	37	31

- IGCC plant with TDA's CO₂ capture system achieves higher efficiencies (34.5% and 34.1%) than IGCC with Selexol[™] (32.0% and 31.0%) for E-Gas[™] and GE gasifiers
- Cost of CO₂ capture is calculated as \$31 and \$30 per tonne for GE and E-Gas[™] gasifiers, respectively (16-30% reduction against Selexol[™])
- Cost of CO₂ capture is calculated as \$40 and \$28 per tonne for Shell and TRIG gasifiers, respectively (15-28% reduction against Selexol[™])



Sinopec Field Test Update

- 2 skids and 2 containers (containing sorbents, catalyst, analyzers, supplies, toolboxes) are shipped to China in December 2017
- Both skids and one of the containers were delivered to the site on April 2018
- One skid held up due to the hazardous nature of the WGS catalyst and regulations on some of the power equipment
- Catalyst, transformer, fiber optic cable etc. were procured locally





Installation Work at Sinopec



- Because of the delays getting all equipment to site, the test setup had to be moved to a different location in the plant
- An existing super-structure at the new site added complexity to installation
 - Skids were pipe rolled over berm and into place
 - Vessels were loaded manually via socks and buckets



Carbon Bed Filling



- Stainless mesh screens and Denstone deltaP media are added to the beds (not available in NCCC tests)
 - The inert ceramic beads eliminated some of the dead volume in the reactor top and bottom
 - Heavy Denstone beads also limits material movement in the bed during cycling



Pipework and Utility Connections



- Sinopec completed all needed site modifications and installations in the plant
 - Syngas Inlet Line 120 m insulated line
 - Syngas Return Line 120 m insulated line (high emphasis on reserving as much H₂ as possible)
 - Exhaust/flare lines 120 m
 - High and Low P nitrogen 100 m
 - Instrument air 100 m
 - Cooling water lines inlet and return 15 m
 - Electrical connections 400 m
 - 400VAC to 480VAC transformer procured from China was installed
 - Fiber optic lines from the control room to the skid PC 450 m



Pilot Plant Installed at Sinopec



Shakedown Tests

- All leak checks were completed
 - Long road trip from NCCC Alabama to Los Angeles, ocean travel to Shanghai, followed by another road trip to Nanjing
 - Skids were lifted several times China (one improperly despite having a specified lift plan)
- Pressure decay testing was performed at 4.0 MPag

All heaters, heated lines were





Very Early Results



- Testing started on 8/27/2019 at 21:50 MST
- High syngas flow, high T, low P during start-up to avoid water/tar condensation in the system
- 2500 SLPM Syngas Flow
- ~85% CO₂ removal efficiency
- ~110 kg/hr CO₂ removal rate



Next Steps

- A fiber optic cable with adapters to Ethernet at both ends will be installed to allow monitoring the equipment from the USA and for data transfer
 - The distance from the skids to the control room is roughly 400m
- Training of plant personnel is underway
- Within 2-3 weeks of routine operation, TDA will let Sinopec/Yangtze employees to run the unit (basic maintenance etc.)
- 6 to 9 month evaluation is planned



Acknowledgements

- DOE/NETL funding under the DE-FE-0013105 project
- Project Manager, Andy O'Palko
- **Chuck Shistla, GTI**
- Ashok Rao, UCI
- **Arvind Rajandran, UOA**
- **Frank Morton, NCCC**
- **Chen Chaomei and Ruan Tian, Sinopec**
- **Yang Xujie, Yangtze Petrochemicals Nanhua Plant**

